

SELECTIONS
FROM THE
RECORDS OF THE GOVERNMENT OF INDIA,
IN THE
PUBLIC WORKS DEPARTMENT.

No. CCXIX.

PUBLIC WORKS DEPARTMENT SERIAL No. 8.

PAPERS

RELATING TO

E. II. 47A.
THE PALAR ANICUT SYSTEM.



Published by Authority.

CALCUTTA:
PRINTED BY THE SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.
1886.



127-2 P
1886

CONTENTS.

List of Papers.	No. and date.	Page.	Plans.
Note by Colonel J. O. Hasted, R.E., on the Revised Estimate for the Palar Anicut System.	No. 105 I.	1	
Note by Mr. C. Vincent, Executive Engineer, D. Project Division, together with the Classified Abstract Estimate, Statements A to E-2, and Forecast Statement Nos. I to IV.	Dated 27th October 1883.	3	19
Order by the Government of Madras on the Revised Estimate.	No. 561 I., dated 13th June 1884.	29	
Despatch from the Government of India, to Her Majesty's Secretary of State, submitting for sanction the Revised Estimate for the Palar Anicut System as an Imperial Ordinary Work.	No. 57 P.W. of 27th October 1884.	29	
Despatch from Her Majesty's Secretary of State sanctioning the Estimate.	No. 79 P.W. of 11th December 1884.	30	

LIST OF PLANS.

1. Index Map.
2. General Plan of Head Works.
3. Plan and Sections of Palar Anicut, in 4 sheets.

NORTHERN SECTION.

4. Longitudinal Sections of Main Channels.
5. Cross Sections of Govindavadi Channel.
6. Longitudinal Section of Kambakal Channel.
7. Cross Sections of Kambakal Channel.
8. Longitudinal Section of Mahindravadi Channel.
9. Cross Sections of Mahindravadi Channel.
10. Drop Weir, Govindavadi Channel, at 9 miles 40 chains.
11. Bridge, Kambakal Channel, at 22 miles 44 chains.

SOUTHERN SECTION.

12. Head-sludge with screw-gearing shutters to Southern Channel.
13. Longitudinal Section of Sakkiramallur Channel.
14. Longitudinal and Cross Sections of Tennampattu Channel.
15. Longitudinal Section of Kalavai Channel.
16. Longitudinal and Cross Sections of Rajakal Channel.
17. Drop Weir, Sakkiramallur Channel, at 1 mile 60 chains.
18. Inlet, Sakkiramallur Channel, at 1 mile 3,696 feet.
19. Kilambadi Syphon Sluice, Sakkiramallur Channel.

PALAR ANICUT SYSTEM.

Note by Colonel J. O. Hasted, R.E., on the Revised Estimate for the Palar Anicut System, No. 105 I.

The Palar anicut was originally designed to give an improved supply to old channels which fed a series of old native tanks. The project which provided for construction of the anicut with under-sluices and head-sluices, and improvements of channels and tanks, was submitted to the Government of India in September 1853, and received the sanction of the Court of Directors in November 1854. The amount of this estimate was Rs. 8,66,144.

The work was commenced in the beginning of 1855, and the anicut was reported completed in September 1857, the total expenditure up to April 1858 being Rs. 5,15,977. The anicut was then only 5 feet high.

The works were connected very slowly, in consequence apparently of funds being limited, and were yet incomplete in 1864, when an estimate, amounting to Rs. 7,700, was sanctioned for raising the anicut 2 feet; additional works, fitting the scouring sluices with shutters and improving the apron, were then sanctioned, and subsequently improvements to the channels. The total expenditure on the project up to the end of March 1864 was Rs. 7,48,987. The system as it then stood possessed many defects, and in 1868 a special officer was deputed to take levels with a view to improving it. The investigations were, however, not completed until, in 1877, an officer was available who worked out the improvements of the channels on the north side, which were undertaken as famine works. Meanwhile, in October 1874, the anicut breached, nearly half its length in the middle of the river being carried away. The repairs were completed in 1875-76 at a cost of Rs. 1,35,349, the breached portion of the anicut being rebuilt clear of the foundations of the old work up stream. The estimates for the northern channels, sanctioned as famine-relief works, amounted to Rs. 2,82,000, and the expenditure incurred during the famine was Rs. 3,66,157, which the normal value of work done was estimated at Rs. 1,63,588, leaving Rs. 2,01,712 as excess due to famine.

Subsequently, revised estimates for the northern channels were prepared, which amounting to Rs. 3,58,430, including establishment and tools and plant charges, were submitted for the sanction of the Government of India, with Proceedings of Madras Government, No. 93 I., dated 5th February 1881, but were returned for revision and explanation. In paragraph 23 of a later Resolution of the Government of India, No. 56—A.I., dated 15th March 1882, it was ordered that complete revised estimates, which should include the improvements proposed for the southern channels, should be submitted.

2. Complete revised estimates have now been prepared by Mr. Vincent, Executive Engineer, in communication with this office, and are submitted with forecast statements, which have been countersigned by the Director of Revenue Settlement and Agriculture.

3. The expenditure on the system up to the end of 1882-83 is as follows :—

	Rs.
Works	12,29,002
Establishment	3,33,127
Tools and plant	29,875
TOTAL	15,92,004

The irrigation, which commenced in 1853-54 with an area of 9,055 acres first crop and 722 acres second crop, extended till in 1882-83 there was an area of 66,751 acres first crop and 20,652 acres second crop irrigated. The steady increase of irrigation, as well as the marked effect of famine years not only in decreasing the revenue at the time but also in checking the extension of irrigation for the next two years, is shown in Mr. Wilson's accounts submitted to the Government of India with Proceedings of Madras Government, No. 616 I., dated 7th August 1882. The net revenue derived from the system to end of 1882-83 (including enhanced land revenue) was Rs. 5,51,755, or 36.5 per cent. on the amount of direct charges, but the

charges for interest at the same date amounted to Rs. 13,71,171, leaving a balance of interest unpaid of Rs. 7,89,416.

4. The system is classed under "Irrigation and Navigation Works for which Capital and Revenue Accounts are kept, but not classed as Productive."

5. The anicut is 2,634 feet in length between wing-walls and 7 feet high, with a vertical fall having 22 under-sluiques on the north side and 10 on the south side; 3 head-sluiques, viz., the Kávérípák and Mahendravadi on the north bank, and one, the Dusi, on the south bank.

The channels on the north are the Mahendravadi channel supplying the tank of that name, the main channel branching into the Kávérípák supply channel at 3 miles from head, and the Govindavadi channel supplying the tank of that name at 21 miles from anicut. From the Govindavadi channel at 16½ miles the Kambankal channel takes off, and, after a course of 26½ miles, terminates in the Sriperambudur tank. On the south side there are 3 channels,—(1) the Sakkiramallur channel (now called Dusi channel) supplied by the under-sluiques, (2) the Tennampattu channel, and (3) the Kalavai channel. When water is available it is passed through the last tank supplied by the Sakkiramallur channel into the Rajahkal channel, which is taken off the river at some distance below the anicut to supply the Dusi-Mamandur tank.

6. The chief reason that the project has not realised the anticipations originally formed is that the supply in the river was over-estimated, but there were considerable defects in the channels as originally laid out. These are—

- (1) Excessive or irregular falls on bed slopes.
- (2) Disproportion between dimensions of channels and areas of irrigation.
- (3) Absence of effective regulation.

And they have been amended in the estimates now submitted, so that the fullest advantage may be taken of the supply in the river; but this supply is so variable that there is great difficulty in estimating the revenue to be expected in future.

7. The water registers (statement A appended to Executive Engineer's report) show that in the fifteen years for which water returns are given there are four during which no water passed over the anicut and one year during which no water was registered at all, and that, on the average, there are 273.73 days yearly on which no water is registered. The northern channels receive a full supply when there is 5½ feet on the anicut under-sluiques sill, and the southern channels not till there is 7 feet on this side.

8. The method that has been adopted in estimating the area to be irrigated by improving the works, any considerable extension of them being considered out of the question, is as follows. The full supply has been calculated from the number of days which, on the average, it is shown to be available for each channel, and to it is added one-fourth the average quantity that would pass through the head-sluiques when the water was below full supply and not less than 1 foot on the sills of the sluiques; this has been taken to determine the area that can be cultivated, allowing 7,000 cubic yards to be stored for each acre. Then, as all the tanks receive in addition to the river supply a supply from local drainage, the area cultivable under each tank commanded has been ascertained, an allowance made of 40 acres to be irrigated under each square mile of catchment, and the balance provided for from the river. This limits, of course, the number of the tanks to be supplied, and consequently it is proposed now to include only 201 in the system, instead of 270 as formerly. The additional supply available, that is, when the river is above full supply and when 1 foot or less is passing through the sluiques, is calculated to be sufficient to irrigate for second crop half the area of the first crop irrigation, or 84,000 acres, and as the latest return shows that the system has irrigated 66,751 acres first crop and 20,652 acres second crop, it is not unreasonable to suppose that with improved regulation this extent may be irrigated.

9. As in years when the river has a large flood discharge a much larger area could be irrigated than that provided for, the tanks selected for terminal tanks of the system are of considerable size and are provided with weirs, over which the available water can be passed on to tanks lower down, of which there are a considerable number. No credit is taken for this additional supply, as it will only be available occasionally, but it will be of great advantage to the country, and will, no doubt, be utilised.

10. Details of the work to be done have been given in the Executive Engineer's report. The northern channel estimates remain very nearly as when submitted before. These estimates provided for widening the main channel and heads of principal channels for drop weirs to reduce the bed fall, and improvements to head-sluiques, &c., and for minor sluiques and tank weirs. The amount under "Works" was, in the estimates submitted to the Government of India, Rs. 3,11,723, and is now Rs. 3,29,455, including Rs. 15,688 for unforeseen expenses, of which Rs. 2,02,024 has already been expended.

The only alteration to be made in the anicut itself is restoring the under-sluiques which have hitherto been used to supply the Sakkiramallur channel to their proper use, a new head for the channel being opened in the main channel. The cost of this work is Rs. 1,963.

The southern channel estimates are now submitted for the first time. They provide for constructing head-sluiques to each of the main branches, so as to have the water entirely under control, for improving the channels, reducing the fall to what the soil will stand, disposing of cross drainage, constructing sluiques to branch channels, and improving tank weirs. The amount for "Works" is Rs. 99,179.

The works are unimportant in character, but it is believed that they will remedy the defects above noticed, prevent waste of water, and improve the irrigation generally.

11. The total of the complete estimates as now submitted is as follows:—

Direct Charges.

	Rs.
Works	14,62,650
Establishment	3,97,861
Tools and plant	34,404
TOTAL	18,94,915

Indirect Charges.

Capitalisation of land revenue abated	17,147
Leave and pension allowances	81,831
TOTAL	98,978
GRAND TOTAL	19,93,893

Of which the actual outlay to end of 1882-83, on sanctioned estimates, has been—

Direct Charges.

	Rs.
Works	12,29,002
Establishment	333,127
Tools and plant	29,875
TOTAL	15,92,004

Indirect Charges.

Capitalisation of land revenue	16,217
Leave and pension allowances	72,744
TOTAL	88,961
GRAND TOTAL	16,80,965

12. The area expected to be irrigated at the end of four years is 68,700 acres first crop and 34,000 acres second crop, producing a gross revenue of Rs. 1,40,970; and deducting maintenance charges a net revenue of Rs. 93,720, which is 4.9 per cent. on direct charges, or 4.7 per cent. on direct and indirect charges. The balance of interest remaining unpaid will, as shown by the Director of Revenue Settlement and Agriculture, be paid in 45 years from date.

13. The remarks made by the Superintending Engineer regarding designs of minor works and those made in this office on the plan, will receive attention when the works are put in hand.

Note by Mr. C. Vincent, Executive Engineer, D. Project Division, on the Revised Estimates for the Palar Anicut System, dated 27th October 1883.

In paragraph 23 of the Resolution on the Preliminary Issue of the Irrigation Budget

Estimates called for. Estimate for 1882-83, printed in Proceedings of the Madras Government, No. 287 I. of 27th

March 1882, the Government of India ordered that a complete revised estimate for the Palar Anicut System should be submitted in the place of the completion estimate for the northern section of the system which had been previously forwarded, but which had been returned for

further information. The revised estimates prepared in accordance with the above orders are now forwarded for approval.

Palar river.

2. It may be well to preface this Note with a brief account of the Palar Anicut System.

The river Palar rises on the Mysore plateau and runs into the sea near Sadras after a course of about 220 miles. There is extensive irrigation from it throughout the district of North Arcot by means of river channels, which are chiefly provided with masonry heads. The anicut supplying the system has been built at about the 152nd mile, and is situated about 4 miles below the famous town and fort of Arcot. The drainage basin of the river up to this point is about 3,974 square miles, the maximum flood discharge about 25,000 cubic feet per second, and the maximum depth of flow passing over the anicut 6.75 feet.

3. The anicut itself is 2,634 feet in length between wing-walls. The body-wall, the crest of which is 489.5 feet above M.S.L., is 7 feet high with a vertical fall, and is built on a double

The anicut.

row of circular wells. There are three aprons; the first, of cut-stone in mortar, 10 feet wide; the second, of rubble stone in mortar, 36 feet wide; the third, of dry rubble stone, 30 feet wide. There are under-sluices on either flank. Those on the north side (the river runs from east to west) consist of 22 vents of 5' x 5' each. Those on the south side consist of 10 vents of the same dimensions. The anicut was breached for a length of 1,015 feet by the floods of October 1874, the damage being at once repaired. The original construction had been commenced about the year 1855.

4. Prior to the construction of the anicut, there was a large supply-channel to the Kávéri-pák tank, but in connection with the anicut a masonry head was built to this, the channel itself

The channels.

being largely extended, and new channels with masonry heads being excavated on both sides of the river. There are now four sets of head-sluices arranged as follows:—

Northern side . { Main or Kávéri-pák head-sluice, 18 vents of 5' x 5' each.
Mahendravadi head-sluice, 9 vents of 5' x 5' each.
Southern side . { Main or Dusi head-sluice, 15 vents of 5' x 5' each.
Sakkiramallur head-sluice, 2 vents of 5' x 5' each.

The last-mentioned head-sluice is at present situated in the line of the anicut, being formed, in fact, by the adaptation of two of the original under or sand sluices. This arrangement, which is very objectionable, will now be dispensed with, the Sakkiramallur channel being supplied from a new head in the Main or Dusi channel, and the sand sluices restored to their legitimate functions. There will then be only one head on the southern side. The following table shows the distribution of the main channels:—

Section.	Head-sluices.	Main Channels.
Northern . . .	{ Main or Kávéri-pák Mahendravadi	{ Kávéri-pák Tank. Govindavadi. Kambankal. Mohendravadi.
Southern . . .	{ * Sakkiramallur Main or Dusi	{ Sakkiramallur. Dusi or Tennampattu. Kalavai.

* Now to be dispensed with, as above stated.

The nomenclature of the Dusi head-sluice and channel is erroneous. It naturally implies that the channel feeds the large Dusi tank (*vide* sketch map). But this tank is supplied principally by means of an independent river channel with its head 14 miles below the anicut, and it only receives the *tail-water* of the Sakkiramallur and Dusi channels. The head-sluice will therefore be called throughout the remainder of this note "the southern head-sluice," and the channel "the Tennampattu channel," the latter being the name of the first tank into which it runs.

5. There is little or no direct irrigation from the main or branch channels. In almost every case the water is led into tanks in which it is stored. Some of these tanks are of very large size, especially the Kávéri-pák tank on the northern and the Dusi Mamandur tank on the

southern side, which irrigate directly 5,873 and 3,046 acres respectively. In the system as now revised, 127 tanks irrigating 38,269* acres have been included in the northern section, and 74 tanks irrigating 14,754† acres in the southern section. Only a portion of these areas require, however, river-water (*vide* paragraph 13).

6. During the famine years 1876—78 the question of improving the channels of the northern section of the system was raised. When these channels were first excavated, the bed fall

Proposals to complete works.

given to each was excessive, the natural slope of the ground having been adopted almost throughout. The result was that a very large amount of silt was carried into the channels, and a heavy expenditure to remove this had to be periodically incurred. The channels were also blocked in many places with a thick growth of prickly-pear. Mr. Rundall, Executive Engineer, was accordingly deputed to prepare the necessary estimates for the reformation of the channels, and these, which were at once provisionally sanctioned, were executed by means of famine labour.

The following table shows the main heads of the original estimate, the subsequent additions to it, the expenditure actually incurred, that written off against famine, and the balance remaining to be spent:—

Channels.	AMOUNT OF ESTIMATES.			Total Expenditure incurred from Famine Funds.	EXPENDITURE RECORDED AGAINST THE ESTIMATES.			Balance of Estimates.
	Mr. Rundall's Estimates.	Subsequent increase to the Estimate	Total.		Normal Value of work done during Famine.	Subsequent Expenditure.	Total.	
1	2	3	4	5	6	7	8	9
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.
Kávéri-pák main channel	1,01,300	37,702	2,29,002	3,66,157	1,63,588	27,471	1,91,059	37,943
Govindavadi do.	9,000	187	9,187	...	...	9,187	9,187	...
Kávéri-pák tank supply channel	12,000	...	12,000	...	...	361	361	11,639
Govindavadi do.	56,100	1,440	57,540	...	...	1,440	1,440	56,100
Kambankal do.	7,630	—152	7,478	...	...	1,428	1,428	6,050
Mahendravadi do.	...	...	...	...	...	...	...	...
TOTAL	2,76,030	39,177	3,15,207	3,66,157	1,63,588	39,867	2,03,475	1,11,732

A few of the masonry works have been completed since the famine, but all capital expenditure on the system was stopped by the Government of India, in letter No. 267 I.† of 9th July 1881. As above stated, a complete revised estimate for the whole system, to include past as well as proposed expenditure, was subsequently

called for. To meet this demand the whole of the figures relating to the northern section have been reconsidered and recast; the improvement of the southern section has been estimated for, and, finally, the question of the water-supply available has been carefully worked out, and the system strictly confined to the limits, which it is believed can be adequately supplied through the *existing* head-sluices and main channels. I italicise "existing," because neither the water-supply available nor the returns hitherto derived from the irrigation warrant any such expenditure as would be involved by the enlargement of the head works.

Financial statements in the authorised forms, showing the probable return due to the expenditure now proposed, have also been prepared.

It will be convenient to consider each of the above points separately and at some detail.

Water-supply.

7. Firstly, as regards the water-supply.

It is unfortunately true that it would scarcely be possible to have a worse river than the Pálar for the supply to a large irrigation system. A synopsis of the water registers which have been maintained since 1864 is given in Statement A, and from this it will be seen that during a period of 15 years the average number of days on which absolutely no water passed down the river was 273.73. In 1867 no water at all passed, and the average would be much worse but for the year 1874, during which water passed on 204 days.

The northern head-sluices receive a full supply when there is more than 5½ feet of water on the sill of the anicut under-sluices,§ and Statement A shows that this depth of water occurs on the average on 22.67 days in each year. The

§ The sills on the northern head-sluices and the anicut under-sluices are on the same level.

southern head-sluice only receives a full supply when there is more than 7 feet of water on the sill of the under-sluices,* which occurs on the average on only 14.07 days in the year.

* The sill of the southern head-sluice is 2 feet above that of the under-sluices.

8. The next point to be considered is the carrying capacity of the existing main channels, any further enlargement of which is, for the reasons above given, not contemplated. Mr.

Rundall, in his completion estimates for the northern section, which comprised the enlargement of the main channel, calculated that a depth of 4 feet and a fall of 3 feet per mile would give a discharge of 4,000 cubic feet per second in a channel 215 feet wide. On calculating the discharges afresh, and in making use of Bazin's discharge co-efficients, it has been found, however, that the discharge in the northern main channel will not amount to more than 3143.5 cubic feet per second. In the southern main channel, which is 113.5 feet wide, with a fall of 6 feet per mile, the discharge with a 4 feet depth of flow will be 2302.9 cubic feet per second. The details regarding these discharges, as well as those for intermediate depths of flow, are given in Appendix B.

Combining these results with the calculations regarding the water-supply available noticed in the previous paragraph, it is found that, in an average year, the northern main channel carries 6,158,110,000 cubic feet during the period of full supply, and that the southern main channel similarly carries 2,799,630,000 cubic feet. These are assumed as the volumes which determine the area capable of being irrigated, all supplies less than full being taken as only replenishing the intermediate tanks, and not as increasing the volume reaching the tail ends of the channels.

9. To determine the area that can be irrigated, the ayacut area of each tank in the system has been taken from the revenue returns, a calculation made of the catchment basin of each, and a corresponding deduction carried out to determine the area remaining to be supplied with river-water. These details are shown in Statements E-1 and E-2 for the northern and southern sections of the system respectively. It has been assumed that each square mile of catchment suffices for the irrigation of 40 acres, the rainfall averaging 35 inches per annum. For the balance of the irrigation 189,000 cubic feet (7,000 cubic yards) of river-water have been assumed as necessary for each acre. This is equivalent on the northern side to 0.0965 cubic feet per acre per second during the average period of full supply; and on the southern side to 0.1555 cubic feet per acre per second. Taking now the volume available at full supply, as stated in the last paragraph, it is found that 32,582 acres can be supplied with river-water on the northern side and 14,813 acres on the southern side.

10. In the case of the former, the selection of tanks to be in future included in the system has been made so that the area under them requiring river-water shall strictly correspond with the amount of such water calculated to be available. The selected tanks are shown in the sketch map of the section. It will be seen from Statement E-1 † that the total area entered as requiring river water is 32,698 acres, or only 116 acres in excess of the area capable of being supplied. The fact of the last tank in the series being a very large one accounts for this small discrepancy. It can be partly, but not wholly, supplied.

11. In the case of the southern section, however, circumstances are somewhat different. It has been said above that water is available for 11,813 acres, but of these only 14,309 acres have been entered in Statement E-2 of the tanks forming the section. The following reasons account for what at first sight appears an omission to fully utilise the water-supply.

It will be evident from what has been already said that the system is one which is now, and must always be, very far from a brilliant financial success, and it has therefore been considered that the works undertaken to complete it must be strictly confined to such as are absolutely necessary to secure a proper supply to and régime for the channels, combined with such other improvements as can be executed at small cost. Now it is unfortunately true that the southern channels were very badly aligned and carelessly excavated in the first instance. The head of the Sakkiramallur channel was put in a very inconvenient and wrong place, and no attempt was made to regulate the bed-slope of the main channels by means of masonry falls. These improvements are therefore essential, but at the same time the cost thereby incurred amounts to, if indeed it does not exceed, the expenditure on the section that can be termed legitimate. Unless, then, it could be clearly shown that the further expenditure required to

secure a free passage to tanks of the excess supply of water available would be directly met by an increased irrigation, or by a saving of remission under those tanks, it does not appear legitimate to incur this charge. But these conditions do not obtain. After very careful examination it appears certain that no extension of the area immediately under the channels as now laid down could be secured except at a cost which the corresponding increase to revenue would not justify.

It has been urged that by thus limiting the area under the channels of the southern section, hardship will be inflicted on many cultivators whose lands lying under tanks now to be excluded from the system have been assessed as "irrigated by river-water." But it is

* As a matter of fact probably, rather more, for the conversion of the present Sakkiramallur head into under-sluices will keep the southern head-sluice much more free from silt than heretofore.

a mistake to suppose that any such hardship will result. As much* water will enter the head of the main channel under the present proposals as previously, and it will be better carried as the régime of the main channels will be improved. The water will thus reach just as far, or further than, it ever has previously. Whether the tanks in question have been rightly classed hitherto as "river-fed" may be matter for question. Personally, I should say that the classification had been wrong, being certain that their supplies of river-water must have been very few and far between. But however this may be, their exclusion from present calculations is a matter purely of accounts interest, and does not affect, otherwise than to benefit, their position as regards "river-fed" tanks.

12. It will be noticed that throughout the foregoing remarks all mention of the Mahendravadi head-sluice and channel on the northern side has been omitted. But this channel is of very minor importance, only supplying 956 acres, which require river-water, much of which area has also an alternate supply from the Kávéripák tank. No detailed notice of the circumstances of this channel appear therefore to be called for.

13. The following table shows the area proposed to be irrigated by each of the principal channels according to the average existing area of cultivation under the various tanks:—

Section.	Channels.	Total Area irrigated.	Area of catchment basin.	Area rain-fed, at 40 acres per square Mile.	Area requiring river-water.
		Acres.	Sq. miles.	Acres.	Acres.
Northern Section	Kadaperi branch channel	920	3.00	120	800
	Kávéripák tank supply channel	5,873	15.00	600	5,273
	Do. surplus channels	10,081	43.41	1,737	8,344
	Govindavadi channel	7,953	20.75	830	7,123
	Kambakkal do.	12,396	30.95	1,238	11,158
	Mahendravadi do.	1,046	2.25	90	956
	Total	38,269	115.36	4,615	33,654
Southern Section	Sakkiramallur channel	2,574	17.5	700	1,874
	Rajakal do.	3,135	12.50	500	2,635
	Tennampattu do.	5,908	39.62	1,585	4,323
	Kalavai do.	3,137	16.50	660	2,477
	Total for both Sections	53,023	201.48	8,060	44,963

The above total of 53,023 acres will, it is contemplated, be ultimately increased to 68,700 acres (*vide* paragraph 37) in consequence of the improved supply reaching land now commanded but not fed.

14. Some details will now be given of the works it is proposed to undertake. It will be convenient to divide the description according to the main heads of the revised estimates.

15. No alteration is proposed to the anicut further than is implied by the abolition of the present Sakkiramallur head-sluice on the southern side. This is now formed, as has been already said, by means of two vents, each 5' x 5', of which the functions are properly those of under-sluices. The conversion of these two vents to other than their proper uses has resulted in a great silting up of the head of the Tennampattu channel, and also on more occasions than one, in the breaching of the bank of the Sakkiramallur channel, owing to the admission of water to the latter being now under imperfect control. It is therefore proposed to restore the

present head-sluice vents to their proper functions, supplying the Sakkiramallur channel from a new cut in the left bank of the southern main channel. The cost of this alteration, so far as the head works are concerned, will be only Rs. 1,963, the cost of the new cut coming under the head of main canals and branches.

16. Turning now to the northern section, it appears necessary to refer in some detail to Mr. Rundall's estimates, to which allusion has already been made in paragraph 4, as the whole of the expenditure incurred under them has yet to receive sanction, and because the works remaining to be executed are, almost wholly, those which Mr. Rundall proposed, but which have not yet been carried out. In the comparative statement attached to the revised estimates, the entries under "Works proposed" consist, in the case of completed works, of the actual cost of execution, where this is more than the estimated cost; in other cases, the estimated cost is entered. It will be convenient, therefore, to treat of these works as a whole, *i.e.*, without specifying those entirely or partially completed, or those not commenced, leaving these details to be gathered, if desired, from the comparative statement.

17. The estimates include a provision of Rs. 5,126 for removing the old shutter-gear from the head-sluices of the main channel and replacing it by screw-gearing of the latest and most approved type.

Provision is also made for the widening of the main channel, with side-slopes of 4 to 1, from about 160 feet to 215 feet, and for the reduction of the bed-fall from 7 feet to 3 feet per mile. This reduction is obtained by means of two falls, 7 feet and 6 feet high respectively. The above section, with a maximum depth of flow of 4 feet, will give a velocity of discharge of 3.4 feet per second. The main channel is 3 miles 7 chains long up to the point at which it divides into the Kávérípák and Govindavadi channels. There is only one small off-take from the main channel up to this point, *viz.*, the Kadaperi channel, which supplies tanks irrigating 920 acres. The heads to the two channels into which the main channel bifurcates are protected by means of head or division sluices, for which new screw-shutter gearing is provided in the present estimates. The Kávérípák channel head has 10 vents, each 6' x 4', and the Govindavadi channel head 13 vents, each 6' x 4½'.

18. Little work to the Kávérípák tank supply channel has been estimated for, beyond widening the upper portion of it, the old channel being, in most places, capable of carrying the whole discharge required. The hydraulic details are given in Statement D, from which it will be seen that the average bottom width is 86 feet, depth of flow 5 feet, the side-slopes 2 to 1, and the bed-fall 2.6 feet per mile. This gives a velocity of 3.65 feet per second and a carrying capacity of 1,753 cubic feet per second. The channel is required to irrigate 13,617 acres, for which the average supply required, according to the method of calculation adopted in paragraph 8, is only 1,314 cubic feet per second, so that the channel will actually carry 439 cubic feet per second more than the theoretically required supply. It is obvious, however, that some such margin is necessary, in order that any high temporary freshes may be rapidly passed into the tanks and stored.

19. The tank supply channel is 2½ miles long to the point at which it enters the Kávérípák tank. This tank is one of the largest and finest in the Madras Presidency. Its bund or bank is nearly 4½ miles long, with its top 6 feet above M.W.L., 8 feet above full tank level, and 4½ feet above the level of the sill of the lowest sluice. There is thus a maximum height of water against the bank of 36 feet. The bank is protected by means of a massive stone revetment. This reservoir was formed before the country came under British rule, and it possesses more than ordinary historical interest, for it was in and around the supply channel to it that Clive, in February 1752, fought a memorable but little known-of battle—a battle that Colonel Malleon, in his recent "Life of Lord Clive," declares to have been the turning-point of British supremacy in Southern India, and "in very deed one of the decisive battles of the world."

There are ten sluices for the supply of the irrigation immediately below the tank, and the surplus arrangements consist of two weirs and two surplus sluices. The most southern of the two weirs is 310 feet long, and is provided with 37 sluice-vents, each 5 feet wide, with pivot-shutters. The second weir is 278 feet long, and has 34 vents, 4 feet wide, similarly fitted. The sills of all these vents are 4 feet below full tank level.

20. One channel carries off the water passing from these two weirs, and this becomes known eventually as the Kortalayar river, which, after receiving affluents, forms the source of supply to the Red Hills and Cholavaram reservoirs, serving the city of Madras. Thirty-five tanks, included in the northern section of the Pálar system, are supplied by this surplus channel. They irrigate in all 6,669 acres, of which 1,300 acres are rain-fed and 5,369 acres require river-water. The supply is fairly well maintained and provided for; but as it is not proposed to spend any money on the improvement of this surplus channel or its off-takes, it is not necessary to give here any further details regarding either, as all necessary particulars can be obtained from Statement E and the sketch map of the section.

21. Neither is it necessary to say anything regarding the first surplus sluice, a work of very small importance, and responsible only for the irrigation of 650 acres, of which 508 acres require river-water.

22. Of the second surplus sluices, some more particulars are required, as under present arrangements, 2,762 acres will be supplied through these, of which 2,467 acres require river-water. It will be seen, on referring to the sketch map, that the tanks thus supplied lie on the extreme north of the section, and, until lately, it was supposed that they derived the whole of their river-water through the Mahendravadi channel, the existence of the surplus sluices being ignored.

Now, however, it has been determined to make the Govindachari tank the terminal of those fed by the Mahendravadi channel, and to supply all the remaining tanks on this side of the system through these surplus sluices. The necessary volume of water will be thus obtained more easily and surely, and the heavy cost of widening the upper portion of the Mahendravadi channel, which would otherwise be necessary, will be avoided. The surplus sluices in question consist of 9 vents, each 5' x 4½', with their sills half a foot below those of the weir-sluices above mentioned. No expenditure of importance is proposed to be incurred on this portion of the section.

23. To return now to the Govindavadi channel, which is the second branch of the main channel alluded to in paragraph 17. This channel is 17½ miles long to where it enters the Govindavadi tank. Up to 13 miles 1 chain, where the Kambankal channel takes off, it has also to carry the supply of this channel. The whole area to be fed by it up to the point of bifurcation is therefore 20,349 acres, of which 18,281 acres require river-water. For this area the volume calculated in the manner previously indicated should be 1,764 cubic feet per second, but with a full supply passing through the head-sluice and also down the Kávérípák channel only 1,753 cubic feet would be available. To allow, however, any exceptional fresh to pass rapidly down it, the channel, as altered, has been designed to carry 1,847 cubic feet per second up to the point of bifurcation. To obtain this, allowance is made for the widening of the channel to a bottom width of about 106 feet with a 4½ feet maximum depth of flow. The estimated cost of the earthwork is Rs. 71,347. An expenditure of Rs. 23,325 is also rendered necessary for the removal of the prickly-pear with which the channel was found much overgrown. The previous bed-fall was excessive, amounting to an average of 10 feet or 11 feet per mile. This has been reduced, by means of 14 drop weirs, with body-walls from 4½ to 7 feet high, to an average of 2.84 feet per mile. The total estimated expenditure on falls and weirs is Rs. 56,485. Other works estimated for include the conversion into a road-dam of a bridge of three arches, each of 15 feet span, which would require an addition of at least five similar arches to suit the increased dimensions of the channel. Also, for widening another bridge, now consisting of one arch of 30 feet and two of 15 feet span, by the addition of three arches of 20 feet span. Also, for the improvement of the off-takes to the minor channels leading to the several tanks, and for the removal of the present small masonry falls.

The regulator, at the point where the Kambankal branches off from the Govindavadi channel, consists now of a weir 61 feet long across the head of the former, and of a sluice of 3 vents, each 6 feet broad, to continue the supply into the latter. As this is the first point at which water can be surplused, it has been considered advisable to increase the Govindavadi channel sluices to 6 vents, each 5' x 4' closed by screw-gearing shutters, at an estimated cost of Rs. 1,800. A weir 15 feet long with its crest at the same level as that across the Kambankal will also be provided, so as to regulate the ordinary distribution of water between the two channels. The distribution might, of course, be effected through the proposed sluices; but as

the proportionate distribution would then be depended on the judgment of the man in charge, a weir seems to be required. The sluices will only be used when it is considered advisable to reduce the supply to the Kambankal.

24. At a distance of $2\frac{1}{2}$ miles below these division works, some further works of the same description are found consisting of a weir 92 feet long across an escape channel, with its crest 3 feet above the bed of the Govindavadi channel. It is proposed to remove the present body-wall of this weir, and to fit it with screw-gearing shutters; 10 vents, each $10\frac{1}{2}$ feet long and 3 feet high, being allowed for, with the sill of the vents at bed level. The estimated cost is Rs. 3,450. Across the head of the tank channel a drop-weir will also be placed at a cost of Rs. 900. The channel from this point to where it enters the Govindavadi tank is $1\frac{1}{2}$ miles long and requires a little clearing, and also the removal of prickly-pear. The Govindavadi tank irrigates 976 acres, of which 936 acres require river-water.

25. The passage of an improved supply down the channel, known as the Kambankal, forms the principal object of the present proposals, so far as the northern section is concerned. The tanks lying above this channel have always received a more or less good supply, but complaints from the Chingleput district, in which most of the irrigation under the Kambankal lies, have always been rife, as to the short supply of water received by the tanks there situated, and held to form part of the Palar system. No doubt these complaints have been well-founded, and it is hoped that, by the arrangements just detailed for the purpose of bringing a larger supply to the head of the Kambankal, an improved state of affairs may now be inaugurated. But the uncertain supply of water furnished by the Palar will, it is feared, prevent complete satisfaction from being given. Moreover, the Kambankal channel does not lend itself, nor can it at any reasonable cost be adapted, to a by-any-means perfect system of irrigation. Its present fall and section are very unequal. In the first $12\frac{1}{2}$ miles the natural fall of about 6.5 feet per mile is considerably broken by numerous drops. In the next 7 miles there is scarcely any fall at all. The longitudinal section shows clearly how extremely irregular the channel is at present; in fact, it seems to have been excavated without any regard to levels. The line has, however, been judiciously chosen, as for the first 18 miles it runs along a ridge, receiving little or no drainage, and irrigating on both sides. But one of the chief reasons why no water has ever yet reached the tail of the channel is to be found in the fact that all the existing sluices had been made of uniform size, $6' \times 4'$, whether they supply a channel leading to a tank irrigating 90 acres, or whether one leading to a tank irrigating 1,300 acres, and the consequent waste of water has been enormous.

The principal works proposed to be undertaken consist of—

- Lengthening the weir at the head of the channel from 61 feet to 81 feet, and raising its body-wall $1\frac{1}{2}$ feet, at an estimated cost of Rs. 1,190.
- Deepening the channel where necessary, especially through a ridge in the 22nd mile, at an estimated cost of Rs. 39,020.
- Four new drop-weirs between the 12th and 20th mile, at a cost of Rs. 7,900.
- The alteration of the existing falls and heads to channels.

The terminal tank of this channel and of the northern section of Palar system is the Sriperambudur, which irrigates 1,256 acres, of which 1,056 require river-water.

26. The Mahendravadi channel, which is the last main channel on the northern side requiring notice, has, as was stated in paragraph 12, a separate head from the Palar, consisting of 9 vents, each $5' \times 5'$. It was at one time supposed that the supply to the Kortalar river, and consequently that to the Madras city reservoirs, could be materially improved by means of this channel, but this hope has now been abandoned owing to the deficient water-supply in the Palar. The functions of the channel are therefore confined to irrigation, and, as has been said in paragraph 22, the whole of the tanks below that of Govindaehari, previously taken as lying under it, can now be better supplied from the Kávéripák tank. The irrigated area under the channel consists therefore of only 1,046 acres, of which 956 acres require river-water. A supply of 92.25 cubic feet per second is sufficient for this area, and only three of the nine vents of the head-sluice require to be fitted with new screw-gearing. The cost of this is entered as Rs. 959. The channel itself is very irregular in bed-fall and section, but there is no object in devoting a large sum to its reformation, and an expenditure of Rs. 5,460 on earthwork, and the revision of the designs of a few of the existing masonry works, will provide everything that is absolutely required.

27: It is not proposed to undertake any works of importance under the heads Distributaries and Cross Drainage Works. As regards the former, only small improvements to the heads of some of the tank channels are allowed for, leaving the channels themselves and the tank bunds to be dealt with out of the grant for revenue maintenance and repairs as occasion may arise. Most of the drainage of the country irrigated by the system is intercepted by means of the tanks, and the small quantity that enters the channels will, it is assumed, pass down them without requiring to be specially dealt with.

28. Turning now to the southern section, it may be said, firstly, that an allowance of Rs. 2,760 is entered in the estimate for the improvement of the shutter-gearing of the head-sluices by which the whole of this section will now be supplied. This work has been carried out in anticipation of sanction.

29. It is proposed to construct the new head to the Sakkiramallur channel, to which reference has already been made in paragraph 15, at a point 3.8 chains below the southern head-sluice. New heads to the Tennampattu and Kalavai channels, in the place of the imperfect ones now existing, are also proposed at a point 9.5 chains below the head-sluice. These will all be fitted with screw-gearing shutters, the total estimated outlay being as follows:—

	Rs.
Sakkiramallur channel	5,457
Tennampattu do.	5,046
Kalavai do.	3,823

A thorough control over the water-distribution will thus be secured. The following table shows the number and dimensions of the vents in each division sluice:—

Channel.	Number of Vents.	Dimensions.
1. Sakkiramallur	5	$6' \times 4'$
2. Tennampattu	6	$6' \times 4'$
3. Kalavai	4	$6' \times 4'$

30. The new cut for the Sakkiramallur channel, starting from the sluice mentioned in the last paragraph, joins the old channel at a distance of 20 chains from the new head. Crossing over a new siphon-sluice to carry the water of a small existing irrigation channel, the Sakkiramallur channel falls into the tank of that name, about $1\frac{1}{2}$ miles below the same point. Up to this the channel is to be 40 feet broad with a depth of flow of 4 feet, a bed-fall of 3 feet per mile, and a velocity of 3.14 feet per second. The Sakkiramallur tank irrigates 291 acres, of which 191 acres require river-water. The channel passes out of the tank by a surplus weir 45 feet long, in which are 8 vents, each $4' \times 4'$. From this weir the channel is to be of the following dimensions:—

Bottom width	30 feet.
Depth	3 "
Fall	4.58 "
Velocity	3.82 " per second.

No very regular course is followed by the existing channel below the Sakkiramallur tank. It passes through a series of minor tanks, and finally loses itself in some flat low-lying ground below the Esyanur tank. This defect it is now proposed to remedy by means of a new cut starting from the head of the channel leading to the Anatangal tank, $4\frac{1}{2}$ miles below the head of the main channel. This cut will be about $2\frac{1}{2}$ miles long, and will run into the remains of the original channel, whence a series of drops will carry the water into the Natteri tank. This tank irrigates 400 acres. One surplus from it supplies the Bramadesam tank, irrigating 191 acres, and another carries the balance of the water into a natural drainage channel leading to the Vengalattur tank, irrigating 453 acres, which is the terminal tank of this channel. The surplus from the Vengalattur tank goes into the Rajakal (*vide* next paragraph), and thence into the Dusi-Mamandur tank.

The total area irrigated by the channel is 2,574 acres, of which 1,874 acres require river-water. The required water-supply, on the assumption stated in paragraph 8, is 291 cubic feet per second. The carrying capacity of the channel at its head has, however, been made equal to 580 cubic feet per second, or an excess of 289 cubic feet per second. The necessity for provision for the rapid passage of flood-water accounts for this large excess.

31. It is convenient to consider the Rajakal in the light of an adjunct to the Sakkiramallur channel, for it occasionally receives a considerable supply from the surplus to the Vengalattur tank, though it mainly depends on a separate river-head consisting of 6 vents of 5' x 4' each.

The channel from the river will have its bed-fall reduced from 6.1 to 3 feet per mile by means of two masonry falls, but no other improvements of importance are proposed. The channel falls into the Dusi-Mamandur tank after a course of about $8\frac{3}{8}$ miles. This tank is the second largest in the Palar anicut system, being exceeded only by the Kāvērīpāk tank. It irrigates 3,046 acres, of which 2,576 require river-water. It is of old native formation, the bank being formed between two hills. There are two low-level and two high-level sluices, also two surplus weirs provided with self-acting shutters. The surplus falls back into the Palar near its junction with the Cheyār.

32. The next channel to be described is that previously known as the Dusi, but which it is now proposed to call the Tennampattu channel.

Tennampattu channel. This irrigates 5,908 acres, of which 4,323 require river-water, involving a carrying capacity of 672 cubic feet per second. The channel as proposed will carry 716 cubic feet per second, or a margin of 44 cubic feet. At its commencement this channel runs with a very small fall through a stiff gravelly and rocky soil, but its fall rapidly increases until at a point 5 miles below the head it reaches 14 feet per mile. Some drops are proposed which will reduce the maximum fall to 10 feet per mile, giving a velocity of 4.37 feet per second, which it is considered can be carried without erosion. In the 9th mile the channel falls into the Tennampattu tank, irrigating 262 acres. Out of this it now flows without any control, but a weir with vents is proposed to regulate the supply to the channel below the tank. No works are proposed below the weir, the channel being in sufficiently good order to pass down any river-water that may reach so far into the various tanks which are fed by it either directly or by means of branch channels. The main channel eventually terminates in the Tirupanamur tank, the surplus of which goes into the Kil Nelli tank, and thence serves to augment the supply of the Dusi-Mamandur tank.

33. The Kalavai channel requires but brief notice. It irrigates 3,177 acres, of which 2,477 require river-water. The corresponding

Kalavai channel.

carrying capacity is 385 cubic feet per second, and it is proposed to pass 402 cubic feet per second, or an excess of 17 cubic feet, down the channel.

The new joint head to be formed for this and the Tennampattu channel has been already described. The bed of the Kalavai channel is extremely irregular, and three drops are proposed

Paragraph 29.

to bring its fall within reasonable limits. In the 5th mile below its head the channel enters the Kalavai tank irrigating 932 acres. This tank has three surplus weirs, each forming the head of a branch channel supplying the remaining tanks fed by the Kalavai main channel.

34. The remarks made in paragraph 27 as regards the distributaries in the northern section apply also to the southern section. The most

Southern section: Distributaries and cross drainage works.

important distributary on the southern side is the so-called Tennampattu high-level channel, which takes off at $6\frac{1}{2}$ miles from the head of the main channel. It supplies 18 tanks, irrigating 2,473 acres, of which 1,713 acres require river-water. Some alterations and improvements to the existing head are proposed at an estimated cost of Rs. 8,733; also deepening the channel where necessary.

The only new cross-drainage works proposed are for the Sakkiramallur channel, a considerable portion of which is formed simply by a retaining bank on ground with a side-long slope. The drainage along this portion is led into the channel by means of passages made of rough stone, the bank of the channel opposite these being reveted. There are two such passages estimated to cost in the aggregate Rs. 1,651.

35. This concludes all that need be said in description of the revised estimates so far as works are concerned. It remains to consider their financial aspect.

36. The classified abstract estimate shows that the total expenditure up to date, which cannot be properly distributed by heads and sub-heads, amounts to Rs. 13,19,498, divided as follows:—

	Rs.
Works	10,26,978
Establishment	2,68,675
Tools and plant	23,845

The proposed new expenditure for which sanction is now awaited amounts to Rs. 5,63,250, divided thus:—

	Rs.
Works	4,35,556
Establishment	1,18,162
Tools and plant	9,532

Of this amount, Rs. 2,72,506 thus divided—

	Rs.
Works	2,02,025
Establishment	61,452
Tools and plant	6,030

has been spent in anticipation of sanction, leaving Rs. 2,90,744 remaining to be spent, divided as follows:—

	Rs.
Works	2,33,532
Establishment	53,710
Tools and plant	3,502

A margin for unforeseen works, amounting to 5 per cent. on the unsanctioned works expenditure, or to Rs. 20,647, has been provided for.

The total gross expenditure thus amounts to Rs. 18,82,748, divided into—

	Rs.
Works	14,62,534
Establishment	3,86,839
Total and plant	33,477

37. Forecast statements in the most recent forms prescribed by the Government of India

Forecast statements.

have been drawn up and are appended. The revenue figures in these have been filled in by Mr. Wilson, Director of Revenue Settlement and Agriculture, and in charge of the irrigation accounts. These forecasts show that it is proposed to spend one lakh a year on works in each of the years 1884-85 and 1885-86, and the balance of Rs. 33,521 in 1886-87.

The ultimate area of irrigation under the tanks to which the system is now confined amounts to 68,700 acres. It is calculated that with the improvements proposed half this area will be double-cropped, bringing the total irrigated area up to 102,700 acres, as against 87,403 acres, the actual area irrigated in 1882-83. The increase amounts to 15,297 acres. The estimated gross revenue due to the 102,700 acres amounts to Rs. 1,40,970, the manner in which this is calculated being shown in paragraph 5 of Mr. Wilson's letter No. 67 of 19th October 1883. The estimated maintenance charges, calculated at 8 annas per acre, *minus* the old maintenance charges, amount to Rs. 47,250, leaving Rs. 93,720 as the net revenue due to the works, excluding interest. Simple interest at 4 per cent. on the estimated gross expenditure of Rs. 18,82,748 amounts to Rs. 75,310, leaving therefore a yearly balance of Rs. 18,410 in favour of the system. There being at present a deficit on it, amounting to Rs. 7,9,416, the estimated annual surplus will suffice to pay this deficit off, and so to clear the system, in forty-five years.

38. This Note is accompanied by complete financial and hydraulic statements, by sketch maps of the system, by index longitudinal sections, by detailed plans of the masonry works remaining to be executed, and by detailed and abstract estimates for all works.

Statements to accompany Note.

PALAR ANICUT SYSTEM.
Classified Abstract Estimate.

Names of Channels.	(1) HEAD WORKS.		(2) MAIN CANALS AND BRANCHES.										(3) DISTRIBUTARIES.					Total Works.	Establishment.	Tools and Plant.	Grand Total.
	C. Works.	Total.	B. Land.	D. Regulators.	E. Falls and Weirs.	F. Other Cross Drainage Works.	G. Bridges.	H. Escapes.	L. Earthwork.	O. Miscellaneous.	Total.	B. Land.	C. Works.	L. Earthwork.	Total.						
Old outlay on Head Works and Northern and Southern Sections, not classified.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.		
	1,903	1,903																			
			1,000	5,124	15,222				36,324	4,200	61,876										
				2,514	1,120				1,570	9,147	13,231										
			2,725	4,720	67,365			3,450	72,097	27,825	1,74,718	50		4,006	350	4,408	1,79,126				
				1,100	11,305			1,800	39,020	63,415	85,740			2,636	150	2,885	56,100				
				950	409			240	5,400	350	7,478						7,478				
			3,725	14,538	84,534		7,816	3,990	1,58,425	83,945	3,06,674	50	6,543	600	7,003	3,13,767					
																	15,688				
																	3,39,475	83,750	7,941	4,31,165	
Add 5 per cent. for unforeseen works.																					
Total for Northern Section.																					
Expenditure already incurred.																					
Sakkimallur Channel.																					
Tennampatti do.																					
Kalavai do.																					
Bajakal do.																					
Total proposed new expenditure.																					
* Expenditure incurred in investigating the project and charged to 34, Protective Works, Irrigation.																					
GRAND TOTAL.																					

MADRAS;

The 27th October 1883.

* Added in the office of the Chief Engineer for Irrigation.

C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT A.

PALAR ANICUT SYSTEM.

Synopsis of the Water Registers at the Anicut from 1864 to 1880.

Years.	NUMBER OF DAYS IN EACH YEAR ON WHICH WATER STOOD AT THE HEIGHTS SHOWN ABOVE THE LEVEL OF THE SILLS OF THE ANICUT UNDER-SLUICES.															MAXIMUM FLOOD.		Number of days on which no water passed.		
																Date.	Height.			
	More than 8' 0".	7' 6" to 8' 0".	7' 0" to 7' 6".	6' 6" to 7' 0".	6' 0" to 6' 6".	5' 6" to 6' 0".	5' 0" to 5' 6".	4' 6" to 5' 0".	4' 0" to 4' 6".	3' 6" to 4' 0".	3' 0" to 3' 6".	2' 6" to 3' 0".	2' 0" to 2' 6".	1' 6" to 2' 0".	1' 0" to 1' 6".	0' 0" to 1' 0".	0' 0" to 0' 6".			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
1864	1	3	1	2	1	2	1	1	1	3	1	6	6	4	8	4	6	5th December	9	321
1865	6	7	5	3	1	3	1	4	2	3	4	4	7	2	2	...	2	26th October	11	229
1866	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	0
1867	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1868	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1869	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1870	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1871	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1872	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1873	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1874 Entries only up to 31st October, when the anicut breached.																				
1875	24	14	4	11	2	0	5	6	4	9	11	13	5	14	8	3	1	25th October	13	461
1876	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1877	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1878	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1879	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
1880	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Average for 15 years	115	53	43	60	23	46	30	61	65	109	135	124	108	125	105	81	37	...	...	...
Total for Northern Section, vide Statement B	7-07	3-35	2-37	4-0	1-53	3-07	2-0	4-07	4-33	7-27	8-27	6-87	8-33	7-0	5-4	2-47	...	...	...	273.
Total for Southern Section, vide Statement C	14-07	4-76	2-3	3-54	4-07	4-33	7-27	8-27	6-87	8-33	7-0	5-4	2-47	...	...	...	...	...	...	...

CHERAK,

27th October 1883.

C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT B.
PALAR ANICUT SYSTEM.
CALCULATIONS FOR DISCHARGES.
BAZIN'S CO-EFFICIENTS.
NORTH MAIN CHANNEL.

Bottom width 215 feet. Side slopes 4 to 1. Fall 3 feet per mile = $\frac{1}{17.80}$.

Item No.	Particulars.	DEPTH OF FLOW IN CHANNEL.						
		1'	1'5"	2'0"	2'5"	3'0"	3'5"	4'0"
1	Wetted perimeter (feet)	223.2	227.36	231.4	235.6	239.8	243.8	248.
2	Area (square feet)	219.	331.5	446.	562.5	681.	815	924.
3	Hydraulic mean depth	0.98	1.46	1.92	2.38	2.82	3.28	3.72
4	Co-efficient of discharge	48.	55.	61.	66.	68.5	72.	74.
5	Velocity of flow (feet per second)	1.1327	1.5841	2.0148	2.427	2.742	3.1082	3.4021
6	Discharge (c. feet per second)	248.05	525.13	898.58	1365.8	1867.3	2491.2	3141.5

SOUTH MAIN CHANNEL.

Bottom width 113.5 feet. Side slopes $1\frac{1}{2}$ to 1. Fall 6 feet per mile = $\frac{1}{88.0}$.

Item No.	Particulars.	DEPTH OF FLOW IN CHANNEL.						
		1'	1'5"	2'0"	2'5"	3'0"	3'5"	4'0"
1	Wetted perimeter (feet)	117.1	119.26	120.7	122.5	124.3	126.12	127.9
2	Area (square feet)	115.	173.6	233.	293.	354.	415.6	478.
3	Hydraulic mean depth	0.98	1.45	1.93	2.39	2.88	3.29	3.73
4	Co-efficient of discharge	48.	55.	61.	66.	69.	72.	74.
5	Velocity of flow (feet per second)	1.6018	2.2325	2.8567	3.4395	3.9022	4.4024	4.8178
6	Discharge (c. feet per second)	184.21	387.57	665.62	1007.8	1381.4	1829.6	2302.9

CHEPÁK,
27th October 1883.

C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT C-1.
PALAR ANICUT SYSTEM.

NORTHERN MAIN CHANNEL.

Statement showing the average annual supply of water that may be expected.

18 vents, each 5' x 5', sills 7' below crest of anicut.

Full supply in channel with 4' depth of flow.

Depth of water above sill of head-sluice.	Corresponding area of discharge.	Depth of flow in channel.	Head of water available.	Average theoretical discharge through head-sluice.	Average carrying capacity of channel.	Average number of days of flow from Statement A.	Total corresponding discharge (columns 6 and 7).	Discharge assumed to be available yearly.
1	2	3	4	5	6	7	8	9
More than 5'5"	Sq. ft.	Ft.		C. ft. per sec.	C. ft. per sec.		C. ft.	C. ft.
From 5'5" to 4'5"	450	4	1'5"	3,538	3,144	22.67	6,158,110,000	6,158,110,000
" 4'5" to 3'7.5"	From 450 to 405.	From 4' to 3'5"	From 1'5" to 1'	Not less than	2,818	6.07	1,477,890,000	+ of 1,559,304,500
" 3'7.5" to 3'	" 405 to 337.5	" 3'5" to 3'	" 1 to 0.75	3,069	2,179	7.97	1,500,470,000	
" 3' to 2'5"	" 337.5 to 292.5	" 3' to 2'5"	" 0.75 to 0.5	2,238	1,616	12.63	*1,748,160,000	
" 2'5" to 2'	" 292.5 to 225.	" 2'5" to 2'	" 0.5	1,602	1,133	8.27	809,560,000	
" 2' to 1'5"	" 225 to 180.	" 2' to 1'5"	" 0.5	1,179	712	6.87	422,620,000	
" 2' to 1'5"	" 180 to 135.	" 1'5" to 1'	" 0.5	919	387	8.33	278,528,000	
				715		TOTAL	12,395,328,000	7,717,414,500

* Average theoretical discharge (column 5) taken.
 Allowance of water for cultivation = 189,000 cubic feet (7,000 cubic yards) per acre.
 The total average yearly supply with full channel as given above is therefore sufficient for the cultivation of 32,662 acres.

CHEPÁK,
27th October 1883.

C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT C-2.
PALAR ANICUT SYSTEM.
SOUTHERN MAIN CHANNEL.

Statement showing the average annual supply of water that may be expected.
 15 vents, each 5' x 5' sills 5' below crest of anicut.
 Full supply in channel with 4' depth of flow.

Depth of water above sill of head-sluice.	Corresponding area of discharge.	Depth of flow in channel.	Head of water available.	Average theoretical discharge, through head-sluice.	Average carrying capacity of channel.	Average number of days of given depth of water from Statement A.	Total corresponding discharge (columns 6 and 7).	(Discharge assumed to be available yearly.
1	2	3	4	5	6	7	8	9
	Sq. ft.	Ft.	Ft.	C. ft. per sec. Not less than	C. ft. per sec.		Ft.	C. ft.
More than 5'	375	4	1	2,408	2,303	14.07	2,799,630,000	2,799,630,000
From 5' to 4'-25"	From 375 to 318.75	From 4 to 3.5	From 1 to 0.75	2,090	2,017	4.76	829,519,000	
" 4'-25 to 3'-75"	" 318.75 to 281.25	" 3.5 to 3	" 0.75	1,668	1,606	2.3	319,144,000	
" 3'-75 to 3'	" 281.25 to 225	" 3 to 2.5	" 0.75 to 0.5	1,202	1,195	3.54	365,498,000	
" 3' to 2'-5"	" 225 to 187.5	" 2.5 to 2	" 0.5	936	837	4.07	204,329,000	
" 2'-5 to 2'	" 187.5 to 150	" 1.5 to 1	" 0.5	766	627	4.33	197,157,000	
" 2' to 1'-5"	" 150 to 112.5	" 1 to 0.5	" 0.5	566	286	7.27	179,614,000	
						TOTAL	4,981,921,000	3,345,952,750

Allowance of water for cultivation = 199,000 cubic feet (7,000 cubic yards) per acre.
 The total average supply with full channel as given above is therefore sufficient for the cultivation of 14,913 acres.

CHEPÁK,
 27th October 1883.

C. VINCENT,
 Executive Engineer, D. Project Division.

STATEMENT D-1.

PALAR ANICUT SYSTEM.

Hydraulic Details of Main Branch Channels of Northern Section.

Item number.	CHANNEL.	Area under channel.	Discharge required to give 18 in. cubic feet per acre in 22 or 27 days.	Proposed carrying capacity of channel.	Excess carrying capacity.	Maximum depth of flow.	BOTTOM WIDTH.		Side slopes.	FALL.			Wetted perimeter.	Area when full.	Hydraulic mean depth.	Coefficient.	Velocity.	REMARKS.
							Present.	Proposed.		Present.	Proposed.	Ratio to unity.						
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
		Acres.	C. ft. per sec.	C. ft. per sec.	C. ft. per sec.	Ft.	Ft.	Ft.					Ft.	Sq. ft.			Ft. per sec.	
	Discharge in Main Channel, 3,144 cubic feet per second.																	
1	Kadaperi	800	77	1,753	439	5	86	86	2 to 1	2.6	2.6	2,021 to 1	108.36	480	4.43	78	3.6519	
2	Káveripák tank	13.617	1,314	1,847	83	4½	106	106	2 to 1	2.84	2.84	1,859 to 1	126.12	517.5	4.1	76	3.5691	* Only 1,753 cubic feet per second available, vide Statement E.
3	Govindaradi	(a) 18,281	1,764*															
	TOTAL	32,698	3,155	3,600	522													
4	Kambankal	11,158	1,077	1,258	181	5	61	61	2 to 1	...	2.63	1,970 to 1	...	355	4.28	77	3.5425	
5	Mahendraradi.	• 956	92															

The present channel is very much wider than is necessary, and its hydraulic details are therefore of unimportance.

(a) Includes Kambankal.

CHEPÁK,
 27th October 1883.

C. VINCENT,
 Executive Engineer, D. Project Division.

STATEMENT D-2.

PALAR ANICUT SYSTEM.

Hydraulic Details of Main Branch Channels of Southern Section.

[illegible]

СНЕГАК,
27th October 1883.

C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT E-1.
PALAR ANICUT SYSTEM.

NORTHERN SECTION.

Areas to be irrigated by Branch Channels and corresponding Water-supply.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated by river-water.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.0865 c. feet per acre per second.	Balance of water.	REMARKS
1	2	3	4	5	6	7	8	9	10	11
			Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
...	Kadaperi	1. Kadaperi Channel. Kadaperi . . . Semathangy . . . Jadayeri . . . TOTAL	276 311 333 920	0.5 0.5 2.0 3.0	20 20 80 120	256 291 253 800	800	77	3,144 3,067	
		2. Kávéripák Tank Supply Channel. Kávéripák . . .	5,873	15.0	600	5,273	5,273	509	*1,314	
		3. Kávéripák Main Surplus.								
1	Alapákam	Alapákam . . . Sattuvanattam . . . Pudupattu . . .	71 80 91	0.75 0.5 0.5	30 20 20	41 60 71	172	17	788	
2	Iralacheri Kondam	Iralacheri Kondam . . .	35	0.5	20	15	15	2	786	
3	Otturampattu Kondam.	Otturampattu Kodam . . .	71	0.5	20	51	51	5	781	
4	Darmaindi	Darmaindi . . . Nangamangalam . . .	162 168	1.0 1.0	40 40	122 128	250	24	757	
5	Peruvalayam.	Peruvalayam . . . Siruvalayam . . .	324 451	1.0 1.5	40 60	284 391	675	65	692	
6	Kalapalampattu	Torayoor . . . Kalapalampattu . . . Alagarantangal . . .	101 95	1.0 0.62	40 25	61 70	131	13	679	
7	Beddivalam	Beddivalam . . .	114	0.5	20	94	94	9	670	
8	Vettankulam	Vettankulam . . . Punnai . . . Veperi . . . Kondenkerai . . .	138 283 117 105	0.75 0.75 1.0 0.5	30 30 40 20	108 253 77 85	523	50	620	
9	Nedampalli Kondam.	Nedampalli Kondam . . .	344	0.5	20	324	324	31	589	
10	Asanallikuppam	Asanallikuppam . . . Kolattúr . . . Nelvoy . . . Polúr, large . . . " Putteri . . . " Chitteri . . .	610 267 303 445 99 139	2.0 1.0 1.5 1.5 0.75 0.5	80 40 60 60 30 20	530 227 243 385 69 119	1,573	152	437	
11	Nemali	Nemali . . .	165	0.12	5	160	160	15	422	
12	Sayanaveram.	Sayanaveram, large and small. Alapákam . . . Santhamangalam, large. Do, small Ganapatipuram . . . Murungai . . .	754 32 89 264 235	3.0 0.25 1.25 1.2 0.0	120 10 50 50 80	634 22 39 214 155	1,064	103	319	
13	Paramaswaramangalam.	Paramaswaramangalam. Attupakkam, large Punnai, large	165 118 149	1.0 1.0 1.5	40 40 60	125 78 89	292	28	291	
14	Illapetandalam	Illapetandalam . . .	85	1.0	40	45	45	4	287	
		TOTAL	6,689	32.5	1,308	5,369	5,369	518	...	

Allowance for Kávérip channel.

STATEMENT E-1—contd.

Areas to be irrigated by Branch Channels and corresponding Water-supply—contd.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated by river-water.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.0865 c. feet per acre per second.	Balance of water.	REMARKS.
1	2	3	4	5	6	7	8	9	10	11
		4. Kāvripāk first surplus sluices.	Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
1	Gangadaravellore .	Gangadaravellore .	91	0.75	30	61	61	6	281	
2	Kilviranam, small .	Kilviranam, small .	44	0.5	20	24				
		Sirukolam	87	0.25	10	77	101	10	271	
3	Direct	Ponniyar	122	0.50	20	102				
		Padur	194	1.25	50	144				
		Vedantangal	112	0.28	12	100	346	33	238	
		TOTAL	650	3.53	142	508	508	49		
		5. Kāvripāk second surplus sluice.								
	Govindachari	Govindachari	412	1.0	40	372	372	36	202	
	Kilviranam	Kilviranam	99	0.5	20	79	79	7	195	
	Maliamedu	Maliamedu	66	0.125	5	61	61	6	189	
	Main	Mahendravadi	320	1.0	40	280	280	27	162	
	Balakistnapuram . .	Balakistnapuram . . .	56	0.125	5	51				
		Kattupakam	42	0.125	5	37				
		Meleri	53	0.25	10	43				
		Velithangipuram . . .	136	0.5	20	116				
		Arasankuppam	90	0.5	20	70	317	31	131	
	Kilneedi, small . . .	Kilneedi, small	178	0.5	20	158	158	15	116	
7	Mahendravadi south surplus.	Paraperi	200	0.5	20	180				
		Kilneedi, large	595	1.0	40	555				
		Narientangal	59	0.25	10	49				
		Voolianellore	456	1.0	40	416	1,200	116	...	
		TOTAL	2,762	7.38	295	2,467	2,467	238		
		6. Govindavadi Channel.								*1,753 * Allowance for Govindavadi channel.
1	Avalur	Avalur	355	1.5	60	295				
		Sangarambadi	155	2.0	80	75				
		Damel	2,254	2.0	80	2,174				
		Perumbulipakam . . .	140	0.5	20	120				
		Kolattur	575	2.0	80	495				
		Karivadu	295	0.5	20	275	3,434	331	1,422	
2	Peyanallur	Peyanallur	193	0.25	10	183				
		Panavakam	388	0.5	20	368				
		Mambakam	140	1.0	40	100	651	63	1,359	
3	Thandalam	Thandalam	370	2.0	80	290				
		Narasapetai	135	0.75	30	105				
		Melvembakam	74	0.5	20	54				
		Kilvembakam	173	0.5	20	153	602	58	1,301	
4	Tayapakam	Tayapakam	102	0.5	20	82				
		Muthuvakam	219	0.75	30	189	271	26	1,275	
5	Melbungaram	Melbungaram	57	0.5	20	37	37	4	1,271	
6	Govindavadi tank . .	Govindavadi	976	1.0	40	936				
		Ooveri	229	0.25	10	219				
		Maniachi	75	0.5	20	55				
		Putteri	85	0.25	10	75				
		Pullalur	624	0.5	20	604				
		Pondavakam	108	0.5	20	88				
		Kottuvakam	197	1.5	60	137				
		Konakambakam	34	0.5	20	14	2,128	205	1,066	
		TOTAL	7,953	20.75	830	7,123	7,123	687		

STATEMENT E-1—contd.

Areas to be irrigated by Branch Channels and corresponding Water-supply—contd.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated by river-water.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.0865 c. feet per acre per second.	Balance of water.	REMARKS.
1	2	3	4	5	6	7	8	9	10	11
		7. Kambankal Channel.	Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
1	Vaithiyur	Vaithiyur	94	0.75	30	64	64	6	1,066	* Allowance for Kambankal channel.
2	Podupakam	Podupakam	929	2.00	80	849				
		Tiroomalpuram	380	0.5	20	360	1,200	117	943	
3	Kuram	Kuram	974	1.25	50	924				
		Ariyamperambakam . .	346	1.0	40	306	1,230	119	824	
4	Periakaramboo . . .	Periakaramboo	238	0.25	10	228				
5	Sembrambakam . . .	Sembrambakam	305	1.5	60	245	228	22	802	
6	Vishakandikuppam . .	Vishakandikuppam . . .	124	0.5	20	104				
		Injambakam	398	0.3	12	386	490	47	731	
7	Velur	Velur	740	0.5	20	720				
		Parandur, large	212	0.75	30	182	902	87	644	
8	Siruvakam	Siruvakam	370	0.75	30	340				
		Siruvallur	363	0.5	20	343	683	66	578	
9	Podavur	Podavur	302	0.75	30	272	272	26	552	
10	Nagapedu	Nagapedu	138	0.25	10	128	128	12	540	
11	Nelvoy	Nelvoy	244	1.0	40	204	204	20	520	
12	Tikanaveram	Tikanaveram	398	0.3	12	386	386	37	483	
13	Thandalam	Thandalam	746	0.3	12	734				
		Melmaduramangalam . .	192	1.25	50	142	876	85	398	
14	Singlepandi	Singlepandi	141	0.25	10	131	131	13	385	
15	Mahadevamangalam .	Mahadevamangalam . .	270	0.75	30	240	240	23	362	
16	Maduramangalam . .	Maduramangalam, large . .	458	0.75	30	428	428	41	321	
17	Kanakarambakam . .	Kanakarambakam	231	0.5	20	211	211	20	301	
18	Kannantangal	Kannantangal, large . .	271	0.3	12	259				
		Do. small	40	0.5	20	20	279	27	274	
19	Maduramangalam . .	Maduramangalam, small . .	118	0.5	20	98	98	9	265	
20	Podupattu	Podupattu, large	118	0.5	20	98				
		Ettikuttimedu	55	0.5	20	35	133	13	252	
21	Maduramangalam . .	Maduramangalam	47	0.75	30	17	17	2	250	
22	Kondur	Kondur	326	1.0	40	286				
		Kiranellore	396	0.75	30	366	652	63	187	
23	Podavur	Podavur shrotriem . . .	176	0.75	30	146	146	14	173	
24	Nandimedu	Nandimedu	88	0.5	20	68	68	7	166	
25	Tirumangalam	Tirumangalam	178	0.25	10	168	168	16	150	
26	Pillapakam	Pillapakam	734	3.0	120	614	614	59	91	
27	Sriperambudur	Sriperambudur	1,256	5.0	200	1,056	1,056	102	—11	11 c. ft. per second short.
		TOTAL	12,396	30.95	1,238	16,151	11,158	1,077	...	

STATEMENT E-1—concl'd.

Areas to be irrigated by Branch Channels and corresponding Water-supply—concl'd.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.0833 c. ft. per acre per second.	Balance of water.	REMARKS.
1	2	3	4	5	6	7	8	9	10	11
		8. Mahendravadi Channel.	Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
	Main . . .	Pundi, large . . .	532	1.0	40	492	492	...	...	
	Pundi Samudram . . .	Pundi Samudram . . .	24	0.125	5	19	122	...	...	
		Do. Putteri . . .	132	0.25	10		141	...	...	
1	Merideri . . .	Merideri . . .	59	0.125	5	54	54	...	...	
2	Bagavali, large . . .	Bagavali, large and small . . .	52	0.25	10	42	42	...	...	
3	Valluvambakam . . .	Valluvambakam . . .	168	0.25	10	158	158	...	...	
4	Vangoorthangal . . .	Vangoorthangal . . .	75	0.25	10	69	69	...	...	
		TOTAL . . .	1,046	2.25	90	956	956	...	...	

ABSTRACT.

Section.	Name of Channel.	Area irrigated.	Catchment area of Channel.	Corresponding area irrigated.	Leaving area to be irrigated.	Corresponding water-supply.
		Acres.	Acres.	Acres.	Acres.	C. ft. per second.
Northern Section	Kadaperi . . .	920	3.0	120	800	77
	Kavérupak tank supply . . .	5,873	15.0	600	5,273	
	Do. main surplus . . .	6,669	32.5	1,300	5,369	
	Do. first do. . .	650	3.53	142	508	1,314
	Do. second do. . .	2,762	7.38	295	2,467	
	Govindavadi . . .	7,953	20.75	830	7,123	1,764
	Kambankal . . .	12,396	30.95	1,238	11,158	
	Mahendravadi . . .	1,046	2.25	90	956	...
	GRAND TOTAL . . .	38,269	115.36	4,615	33,654	...

CHEPÁK,
27th October 1883.C. VINCENT,
Executive Engineer, D. Project Division.

STATEMENT E-2.

PALAR ANICUT SYSTEM.

SOUTHERN SECTION.

Areas to be irrigated by Branch Channels and corresponding Water-supply.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.1555 c. ft. per acre per second.	Balance of water.	REMARKS.
1	2	3	4	5	6	7	8	9	10	11
		1. Sakkiramallur Channel.	Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
	Main channel . . .	Sakkiramallur . . .	281	2.25	90	191	191	30	...	
1	Anatangal . . .	Anatangal . . .	141	1.25	50	91				
		Arimbakkam . . .	225	1.0	40	185				
		Sattuvantagal . . .	56	0.5	20	36				
		Munjuriputtu . . .	78	0.75	30	48				
		Kurumulitangal . . .	35	0.25	10	25				
2	Chitrapakkam . . .	Chitrapakkam . . .	103	1.75	70	33				
		Eayanur . . .	305	1.0	40	265				
3	Puntandalam . . .	Puntandalam . . .	69	1.0	40	29				
		Pulivalam . . .	144	0.5	20	124				
		Sonaipattu . . .	93	0.5	20	73				
4	Natteri . . .	Natteri . . .	400	1.25	50	350				
		Brammadesam . . .	191	1.5	60	131				
	Vengalattur . . .	Vengalattur . . .	296	4.0	160	136				
		Umayapuram . . .	157			157				
		TOTAL . . .	2,574	17.5	700	...	1,874	291	...	
		2. Rajahkal Channel.								
1	Namandi . . .	Namandi . . .	89	0.75	30	59				
	Rajahkal . . .	Dusi-Mamandur . . .	3,046	11.75	470	2,576				
		TOTAL . . .	3,135	12.50	500	...	2,635	409	...	
		3. Tennampattu Channel.								
1	Paneri . . .	Paneri . . .	51	0.25	10	41				
		Kirambadi . . .	123	0.75	30	93				
2	Kadapantagal . . .	Kadapantagal . . .	39	0.5	20	19				
		Do. Chitteri . . .	27	0.25	10	17				
		Macantagal . . .	25	0.25	10	15				
		Mullavadi . . .	201	1.0	40	161				
		Do. Chitteri . . .	28	0.25	10	18				
		Mecheri, large . . .	188	1.75	70	118				
3	Arimbakkam . . .	Arimbakkam Chit- teri . . .	104	0.75	30	74				
		Sirivanjiputtu . . .	148	0.75	30	118				
		Iravavaram . . .	156	0.75	30	126				
		Oteri . . .	200	1.0	40	160				
4	Mecheri channel . . .	Mecheri small tank . . .	188	1.75	70	118				
		Randan large tank . . .	106	0.75	30	76				
		Do. small tank . . .	65	0.50	20	45				
4a	Nayantagal . . .	Nayantagal . . .	71	0.50	20	51				
		Tandapantagal . . .	49	0.5	20	29				
		Vallanampakkam . . .	112	1.5	60	57				
		Perangathur . . .	474	2.5	100	374				
		Kodayambakkam . . .	71	1.5	60	51				
		Mantagal . . .	65	0.5	20	45				
		Somangali . . .	103	0.5	20	83				
		Kunnathur . . .	108	1.5	60	93				
		Kahanam . . .	243	1.5	60	183				
		Sittatur . . .	231	1.75	70	161				
		TOTAL . . .	4,292	29.26	1,000	...	3,292	182	...	

STATEMENT E-2—contd.

Areas to be irrigated by Branch Channels and corresponding Water-supply—contd.

Number of channel (vide sketch map).	Name of Branch Channel.	Name of Tank.	Area to be irrigated.	Catchment area of tank.	Corresponding area irrigated.	Leaving area to be irrigated by river-water.	Total area under branch channel requiring river-water.	Corresponding water-supply at 0.1555 c. ft. per acre per second.	Balance of water.	REMARKS.
1	2	3	4	5	6	7	8	9	10	11
		3. Tennampattu Channel—contd.	Acres.	Acres.	Acres.	Acres.	Acres.	C. ft. per second.	C. ft. per second.	
46	Melbuder . . .	Melbuder . . .	59	0.75	30	29				
		Pullavakkam, large . . .	116	0.75	30	86				
		Do. small . . .	45	0.5	20	25				
		Aratirivellur . . .	106	0.75	30	76				
		Moranam . . .	124	1.0	40	84				
	Main . . .	Tennampattu . . .	262	2.0	80	182	300	47	...	
5	Meleri . . .	Meleri . . .	134	0.5	20	114	182	28	...	
6	Kuttanur . . .	Kuttanur . . .	299	1.5	60	239	239	37	...	
7	Alivaditangal large tank.	Alivaditangal . . .	440	2.0	80	360	360	56	...	
8	Alivadi Chitteri . . .	Alivadi Chitteri . . .	129	0.5	20	109	109	17	...	
9	Vembakkam . . .	Vembakkam . . .	156	1.25	50	106	106	17	...	
	Main . . .	Tirapanamur . . .	287	1.5	60	227				
		Seleri . . .	28	0.25	10	18				
		Pakantangal . . .	34	0.375	15	19				
		Voorooleri . . .	94	0.5	20	47				
		Karandi . . .	107	0.75	30	77				
		Kilnelli . . .	175	1.25	50	125	540	84	...	
		TOTAL . . .	5,908	39.625	1,585	...	4,323	672		
		4. Kalavai Channel.								
1	Kukundi . . .	Kukundi . . .	106	0.75	30	76	76	12	...	
2	Velur . . .	Velur . . .	451	2.0	80	371	371	58	...	
3	Karikantangal . . .	Karikantangal . . .	95	0.25	10	85	85	13	...	
	Main channel . . .	Kalavai . . .	932	4.50	180	752	752	117	...	
	Kalvai first surplus . . .	Nallur . . .	75	1.0	40	35	35	5	...	
	Do. second do. . .	Kalavaipattur . . .	185	1.0	40	145				
		Vembi . . .	112	0.75	30	82				
		Kodali . . .	120	0.75	30	90				
		Pali . . .	171	0.75	30	141				
		Melapulam . . .	59	0.75	30	29				
		Pennalur . . .	249	0.75	30	219				
		Donimeda . . .	98	0.75	30	68	774	120	...	
	Do. third do. . .	Vellambi . . .	282	0.75	30	252				
		Pullaitangal . . .	87	0.75	30	57				
		Attayanam, large and small . . .	115	1.0	40	75	384	60	...	
		TOTAL . . .	3,137	16.50	660	...	2,477	385		

ABSTRACT.

SECTION.	Name of Channel.	Area irrigated.	Catchment area of channel.	Corresponding area irrigated.	Leaving area to be irrigated by river-water.	Corresponding water-supply.
		Acres.	Acres.	Acres.	Acres.	C. ft. per second.
Southern Section.	Sakkiramallur channel . . .	2,574	17.5	700	1,874	291
	Rajahkal do. . .	3,135	12.50	500	2,635	409
	Tennampattu do. . .	5,908	39.625	1,585	4,323	672
	Kalavai do. . .	3,137	16.50	660	2,477	385
	GRAND TOTAL . . .	14,754	86.125	3,445	11,309	1,757

CHEPÂK;
27th October 1883.C. VINCENT,
Executive Engineer, D. Project Division.

H.—EXPENDITURE ON PUBLIC WORKS NOT CLASSED AS PRODUCTIVE.

46.—IRRIGATION AND NAVIGATION.

Imperial.

Works for which Capital and Revenue Accounts are kept.

PALAR ANICUT SYSTEM.

No. I.—Summary of the Actual and Estimated Direct Charges to Capital.

Year.	Works.	Establishment.	Tools and Plant.	TOTAL.
1	2	3	4	5
	Rs.	Rs.	Rs.	Rs.
Actual outlay to end of 1882-83 . . .	12,29,002	3,33,127	29,875	15,92,004
Probable outlay during 1883-84 . . .	...	...	...	...
" " 1884-85 . . .	1,00,127	34,024	2,527	*1,36,678
" " 1885-86 . . .	1,00,000	23,000	1,500	1,24,500
" " 1886-87 . . .	33,521	7,710	502	41,733
TOTAL . . .	14,62,650	3,97,861	34,404	18,94,915

* Includes Rs. 12,167 provided to admit of the reconpmnt to F.—Famine Relief and Insurance, 34.—Protective Works—Irrigation, of the outlay incurred therefrom during 1881-82 and 1882-83 for investigating the project.

J. O. HASTED, Colonel, R.E.,
Chief Engineer for Irrigation.

No. II.—Summary of the Actual and Estimated Indirect Charges to Capital.

Year.	Capitalisation of Land Revenue abated.	Loss by Exchange on Payments in England.	Charges on Leave and Pension Allowances.	TOTAL.
1	2	3	4	5
	Rs.	Rs.	Rs.	Rs.
Actual outlay to end of 1882-83 . . .	16,217	...	72,744	88,961
Probable charges during 1883-84 . . .	...	...	...	...
" " 1884-85 . . .	*930	...	4,801	5,731
" " 1885-86 . . .	...	...	3,258	3,258
" " 1886-87 . . .	...	...	1,028	1,028
TOTAL . . .	17,147	...	81,831	98,978

* This amount has been calculated at twenty-five times the annual assessment on land to be taken up for the works, the annual assessment being, in the absence of information, taken at one-twentieth of the unspent balance of the estimate for land compensation.

J. O. HASTED, Colonel, R.E.,
Chief Engineer for Irrigation.

No. III.—Estimate of Growth of Irrigation and Revenue Receipts and Charges.

Year.	IRRIGATED AREA AT END OF YEAR.		NET RECEIPTS AND CHARGES.					
	1st Crop.	2nd Crop.	GROSS REVENUE DUE TO WORK.			Charges, both Direct and Indirect.	NET REVENUE DUE TO WORK.	
			Direct Receipts.	Enhanced Land Revenue or Indirect Receipts.	Total.		Including enhanced Land Revenue.	Residual enhanced Land Revenue.
1	2	3	4	5	6	7	8	9
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.
Actuals to end of 1882-83	66,751	20,682	2,080	13,21,321	13,23,351	7,41,596	5,81,755	...
Estimated during 1883-84	67,200	22,800	250	1,13,960	1,14,210	41,000	73,210	...
" 1884-85	67,700	26,300	900	1,23,710	1,24,010	43,000	71,010	...
" 1885-86	68,200	29,800	350	1,31,850	1,32,200	45,000	87,200	...
" 1886-87	68,700	34,000	400	1,40,870	1,40,970	47,250	93,720	...
TOTAL	...	...	3,330	18,31,411	18,34,741	9,17,846	9,16,896	...

J. O. HASTED, Colonel, R.E.,

Chief Engineer for Irrigation.

W. WILSON,

Director of Revenue Settlement and Agriculture.

MADRAS,

12th October 1883.

N.B.—The only alteration made since Mr. Wilson countersigned is the separation of the extent irrigated with first and second crops.

No. IV.—Estimate of Net Financial Results to date of Completion of the Work.


Year.	Direct Capital Outlay during the Year.	Direct Capital Outlay to end of Year.	Simple Interest at 4 per cent. on Capital Outlay to end of previous year, plus half Outlay during Year.	Net Revenue, including enhanced Land Revenue: Column 7 of Table III.	Simple Interest less Net Revenue.	Net Revenue less Simple Interest.
1	2	3	4	5	6	7
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.
Actuals to end of 1882-83.	...	15,92,034	13,71,171	5,81,755	7,89,416	...
Estimated during 1883-84	...	15,92,004	63,680	73,210	...	9.
" 1884-85	1,26,678	17,28,682	66,413	81,010	...	14,54
" 1885-86	1,24,500	18,53,182	71,637	87,200	...	15,59
" 1886-87	41,783	18,94,915	74,962	93,720	...	18,56
" 1887-88	...	18,94,915	75,797	93,720	...	17,92
" 1888-89	...	18,94,915	75,797	93,720	...	17,92
" 1889-90	...	18,94,915	75,797	93,720	...	17,92
" 1890-91	...	18,94,915	75,797	93,720	...	17,92
" 1891-92	...	18,94,915	75,797	93,720	...	17,923
" 1892-93	...	18,94,915	75,797	93,720	...	17,923
" 1893-94	...	18,94,915	75,797	93,720	...	17,923
" 1894-95	...	18,94,915	75,797	93,720	...	17,923
" 1895-96	...	18,94,915	75,797	93,720	...	17,923
" 1896-97	...	18,94,915	75,797	93,720	...	17,923
TOTAL	...	18,94,915	24,05,833	18,54,095	7,89,416	2,37,678

J. O. HASTED, Colonel, R.E.,

Chief Engineer for Irrigation.

PALAR ANICUT SYSTEM.
GENERAL PLAN
OF
HEAD WORKS.

SCALE 1000 FEET TO AN INCH
SCALE FOR SECTION 40 FEET TO AN INCH



REFERENCE TO ANICUT

CONCRETE
BRICK IN CHUNAM
CUT STONE
ROUGH-STONE WORK
RUBBLE MASONRY
NATURE OF SURFACE SOIL SANDY
DR — SUB SOIL DR
DESIGNED BY — LT SWINER
BUILT BY — DR
AMOUNT OF ESTIMATE — Rs 135,000
ACTUAL COST — Rs 135,350


(SIGNED) J. O. HASTED
CHIEF ENGINEER
D. PRASAD DIVISION

(SIGNED) W. WILSON
DIRECTOR OF REVENUE SETTLEMENT AND AGRICULTURE


PHOTOCOPIED AT THE SURVEY OF INDIA OFFICE, CALCUTTA, DECEMBER 1883.

PALAR ANICUT SYSTEM

PALAR ANICUT




PLAN N° 5
SHEET N° 1



REPRODUCED AT THE SURVEY OF INDIA OFFICES, CALCUTTA, INDIA.

PLAN. N°3.
SHEET N°12.



PHOTOGRAPHED AT THE SURVEY OF INDIA OFFICE, CALCUTTA, SEPTEMBER 1860.

PLAN NR3
SHEET NR3

CROSS SECTION OF

PALAR ANICUT

REFERENCE
CONCRETE
CUT STONE
ROUGH STONE WORK
RUBBLE MASONRY
BRICK IN CHUNAM
NATURE OF SURFACE SOIL
OR SUB-SOIL
Designed By L. T. SWITZER
BUILT BY DR
AMOUNT OF ESTIMATE 135,000 Rs.
ACTUAL COST 135,360 Rs.

AREA OF DRAINAGE BASIN 2874 SQ. MILES
M.F. DISCHARGE - ABOUT 25,000 CFS PER SEC.
MAXIMUM DEPTH OF FLOW PASSING OVER THE ANICUT - 6.75 FEET.
LENGTH OF ANICUT BETWEEN WING WALLS - 2654 FEET.
CREST OF BODY WALL ABOVE M.S.L. +59.8 FEET.

SCALE 20 FEET TO AN INCH
FOR SECTION
SCALE 1 INCH FOR PLAN
M.F.L. OF 1974 - 458.25
M.S.L. OF 1974 - 458.10

SECTION OF ANICUT THROUGH A-A

45.0
10.0

M.S.L. OF 1974 - 458.10

SECTION OF ANICUT THROUGH A-A

7.5

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0

10.0


10.0

10.0

ADJACENT SHEET NR 4

PALAR ANICUT SYSTEM

NORTHERN SECTION
N14




(SIGNED) C. VINCENT
ENGINEER
PROJECT DIVISION

(SIGNED) C. VINCENT
CAPTAIN R.E.
PROJECT DIVISION

N96

VERTICAL SCALE 400



PHOTOGRAPHED AT THE SURVEY OF INDIA OFFICE, CALCUTTA, DECEMBER 1900

(H.C.) *Am. Stuart* CAPTAIN R.E.
Asst. Chief Engr. For Inspection

PALAR ANICUT SYSTEM

CROSS SECTIONS
KAMBAKAL CHANNEL

Scale 1" = 100'

NORTHERN SECTION

No. 7.

C.S. NO. 1 (1/4 Mile)

C.S. NO. 2 (1/4 Mile)

C.S. NO. 3 (1/4 Mile)

C.S. NO. 4 (1/4 Mile)

(Sd/-) J. O. HAYES Lt. Col. R.E.
Ordn. Corps Engineer
For Information



(Sd/-) *W. S. Haynes* Captain R.E.
Asst. Corps Engineer For Bombardment

FLAR ANICUT SYSTEM

LONGITUDINAL SECTION
OF
MAHENDRAVADI CHANNEL

NORTHERN SECTION

N88



(Signed) C. Vincent
S. S. Engineer
D. Project Division

(Sd) Anil Kumar
S. S. Engineer
D. Project Division

PROVIDED AS THE SURVEY OF INDIA OFFICE, CALCUTTA


PALAR ANICUT SYSTEM

CROSS SECTIONS
OF
MAHENDRAVADI CHANNEL




NORTHERN SECTION
NR 9


C.S. NR 1 (1/4 Mile)




C.S. NR 2 (1/4 Mile)




C.S. NR 3 (2 1/2 Miles)
Common to Bas Level 3852.




C.S. NR 4 (5 1/2 Miles)
C.B.L. 3877



C.S. NR 5 (5 1/4 Miles)
C.B.L. 377-76



C.S. NR 6 (6 Miles)
C.B.L. 38340



(Stamp) C. Vincent
Eng. Engineer
D. Project Division


PHOTOGRAPHED AT THE SURVEY OF INDIA OFFICE, MADRAS, FEBRUARY 1961.

(Signature)
Chief Engineer, P. & M. Division

GOVINDAVADI CHANNEL

NR10

AT
9 MILES 40 CHAINS.



RUBBLE MASONRY
CUT STONE WORK
ROUGH-STONE WORK

NATURE OF SOIL.....	ALLUVIAL
OR SUB-SOIL.....	SR
DISCHARGE	1989 C.F. PER SECOND
AMOUNT OF ESTIMATE	RUPEES 5000

PHOTOGRAPHED AT THE SURVEY OF INDIA OFFICE, CALCUTTA, SEPTEMBER 1966.

PALAR ANICUT SYSTEM

REFERENCE



BRICK IN CONCRETE
BRICK IN CONCRETE (ARCH WORK)
NATURE OF SOIL SUB-SOIL GRAVEL
DITCHES 525 C.F.F. PER SECOND
AMOUNT OF ESTIMATE RUPEES 1000

KAMBAKAL CHANNEL
BRIDGE

AT
22 MILES. 44 CHAINS.

SCALE 1/20

NORTHERN SECTION



Survey C. P. M. or
Expenditure
B. Project Division

Am. Kambakal
Survey C. P. M. or
Expenditure
B. Project Division


REPRODUCED AT THE SURVEY OF INDIA OFFICE, CALCUTTA, 1900

PALAR ANICUT SYSTEM


REFERENCE

METAL WORK
 CIVIL ENGINEERING
 DRAWING BOOK
 PART II (Mechanical)
 Vol. 1
 Appendix of Examples No. 5300


PLAN OF HOLDING DOWN BOLT PLATE



SECTION




ENLARGED SECTION OF HOLDING DOWN GEAR PLATE




CROSS SECTION OF HOLDING DOWN PLATE




PLAN OF GEAR PLATE




PLAN OF ANGLE IRON BEARING



SECTION



ENLARGED PLAN OF SHUTTER




N.B. THICKNESS OF SHUTTER 5

HEAD SLUICE TO SOUTHERN CHANNEL


SCALE 1/2 INCH TO AN INCH



SCALE 2 FEET TO AN INCH FOR SHUTTER




SCALE 1 FOOT TO AN INCH FOR DETAILS OF SHUTTER





REAR ELEVATION

FRONT ELEVATION AND SECTION ON A.A.



SOUTHERN SECTION

NO 12





(SIGNED) JOHN PENNYCOK CAPTAIN R.E.
DISTRICT ENGINEER
NORTH ARCTIC

54
Arthur J.
 CAPTAIN R.E.
 ADDL CHIEF ENGINEER FOR IRRIGATION

PALAR ANICUT SYSTEM

LONGITUDINAL SECTION OF SAKKIRAMALLUR CHANNEL

SOUTHERN SECTION
NR13.




(Signed) C. VINCENT
S. E. ENGINEER
D. PROJECT DIVISION

(Sd) *Ambrant*
CAPTAIN H. E.
ASSY. CHIEF ENGINEER

PALAR ANICUT SYSTEM

LONGITUDINAL AND CROSS SECTIONS OF TENNAMPATTU CHANNEL


SOUTHERN SECTION
NR 14.



PALAR ANICUT SYSTEM

SOUTHERN SECTION

LONGITUDINAL SECTION
OF
KALAVAI CHANNEL



(SIGNED) C.VINCENT
ENR ENGR
D. PROJECT DIVISION

(8th) *Antenna*






CAPTAIN R. E.
ASST CHIEF ENGINEER FOR/ROMATION

PHOTOZINCGRAPHED AT THE SURVEY OF INDIA OFFICES, CALCUTTA, DECEMBER 1904.

PALAR ANICUT SYSTEM

SOUTHERN SECTION
No 16.

LONGITUDINAL AND CROSS SECTIONS OF RAJAKAL CHANNEL



PROPOSED BED
CHIEF 22.67 FLOOD 230.13
JUNCTION OF VINDHAYAN
VELOCITY CHANNEL
CUT OF SUNDAYAN
HEAD SLUICE 237.76
CUT OF ANANDAPURAM
HEAD SLUICE 237.76
CUT OF ANANDAPURAM
HEAD SLUICE 237.76
CUT OF ANANDAPURAM
HEAD SLUICE 237.76

(SIGNED) C. VINCENT
ENR. CHIEF
D. PROJECT DIVISION





(SIGNED) *Antoine*
CAPTAIN R. E.
ASST. CHIEF ENGINEER FOR IRRIGATION

PALAR ANICUT SYSTEM

SAKKIRAMALLUR CHANNEL DROP WEIR AT 1 MILE 60 CHAINS

SOUTHERN SECTION No. 11

REFERENCE
 CONCRETE
 BRICK IN CHAMBER
 RUBBLE MASONRY
 ROUGH-STONE WORK
 CURBSTONE
 B.S.D. OF CHANNEL 475.12
 CREST 478.97
 FLOOR 478.40
 WATER LEVEL IN FRONT 479.32
 " " " " IN REAR 477.40
 DISCHARGE 386.71 PPS SECOND C/S 525
 NATURE OF SOIL SUB SOIL RED LOAM MIXED WITH GRAVEL
 ESTIMATE No. 1524
 DESIGNED BY C. V. MANGAT ESE-N



SIGNED: C. V. MANGAT
 ENGINEER
 D. PROJECT DRAWING

Captain R.E.
 1181, CIVIL ENGINEER, PUNJAB, INDIA


FALAR ANICUT SYSTEM

REFERENCE
ROUGH STONE MASONRY AND APRON
GRAVEL BACKING
DRAINAGE AREA 0.5 Sq Miles C-400
Discharge: 100 cfs per second C. 825
Depth of Water 1.5 Feet
Floor of Inlet 478.87
NATURE OF SOIL & SUB SOIL Red Loam Mixed with Gravel
ESTIMATE Rupees 912.
Designed by C. Vincent Esq.

SAKKIRAMALLUR CHANNEL


INLET
AT
1 MILE 3000 FEET.

SCALE 1/8" = 10' 0"



DESIGNED BY C. VINCENT ESQ. AT THE SURVEY OF INDIA OFFICE, CALCUTTA, DECEMBER 1900

SOUTHERN SECTION
N 1/2 E



DESIGNED BY
C. VINCENT
ESQ.
D. P. S. DIVISION
1900

ASSISTANT CHIEF ENGINEER FOR IRRIGATION

PLAN
OF

KILAMBADI SYPHON LUICE

SOUTHERN SECTION

BOARD OF

FRONT ELEVATION

LONGITUDINAL SECTION ON A.

REFERENCE

[illegible]

(Signed) Vincent
 ESE ENGINEER
 CIVIL ENGINEERING DIVISION
 (old) *Carman*
 ASST. CIVIL ENGINEER P&H INSPECTION
 CROFTON, R. L.

WENT TO READING RM AT 6PM FOR DISCUSSION

Order by the Government of Madras, No. 561-I., dated 13th June 1884.

The complete revised estimates for the Palar anicut project, as follows :—

<i>Direct Charges.</i>		Rs.
Works		14,62,650
Establishment		3,97,861
Tools and plant		34,404
	TOTAL	18,94,915
<i>Indirect Charges.</i>		
Capitalisation of land revenue		17,147
Leave and pension allowances		81,831
	TOTAL	98,978

will be forwarded for the sanction of the Government of India.

2. The variable nature of the water-supply renders any considerable increase of irrigation improbable, but the improvement of the channels will result in a fair return on the expenditure, though the balance of interest charges unpaid, the consequence of defective original designs and accidents, will for many years absorb the greater part of the revenues.

Despatch from the Government of India, to Her Majesty's Secretary of State for India, No. 57-P.W., dated 27th October 1884.

We have the honour to submit, for the approval and sanction of Her Majesty's Government, a revised estimate for the Palar Anicut System in the Madras Presidency, amounting to Rs. 19,93,893, of which Rs. 18,94,915 represent the direct, and Rs. 98,978 the indirect, charges.

2. The previous history of the project is briefly described in paragraph 1 of the Note by Colonel J. O. Hasted, R.E., Chief Engineer for Irrigation, Madras, which explains how the scope of the work has been enlarged, from time to time, since 1854. The estimate originally sanctioned by the Court of Directors proved quite insufficient for the complete scheme, so that revised and supplementary estimates became necessary, and finally in 1882 we called on the Madras Government to submit a complete revised estimate covering the cost of all necessary improvements. The present estimates have, therefore, been prepared to provide for works intended for the full utilisation and regulation of the available supply of water. For details of the proposed improvements and those which have already been carried out, we beg to refer Your Lordship to the Executive Engineer's report which accompanies this despatch.

3. Out of the estimated direct outlay of Rs. 18,94,915, Rs. 15,92,004 have been expended up to the close of 1882-83, leaving a balance of Rs. 3,02,911 for future expenditure. The work is therefore very nearly completed.

• Estimated capital outlay :—		Rs.
Direct		18,94,915
Indirect		98,978
	TOTAL	19,93,893
<i>Add—Simple interest less net revenue up to the tenth year after the completion of the work</i>		<i>5,51,738</i>
	TOTAL SUM AT CHARGE	25,45,631

4. On the completion of the entire project, in 1886-87, the area of irrigation is expected to reach 68,700 acres of first and 34,000 acres of second crop. The net revenue expected to be obtained from the irrigation of this area will amount to Rs. 93,720, being a return of 3.68 per cent. on Rs. 25,45,631,* the total sum which will be at charge in the tenth year after the completion of the project.

5. The estimate of the growth of irrigation and revenue receipts and charges has been countersigned by Mr. Wilson, Director of Revenue Settlement and Agriculture; and we have not considered it necessary to call for a separate report on the subject, as the present case is one in which the anticipated results do not differ very markedly from those actually attained.

6. The scheme will not prove sufficiently remunerative to allow of its being classed as a Productive Public Work, and it is shown in our accounts as an Imperial Ordinary Work. We therefore request Your Lordship's sanction to the estimate now submitted as a charge against the ordinary revenues of the country.

Documents accompanying.

1. Endorsement by the Madras Government, No. 562-I., dated 13th June 1884, and enclosures.
2. Two maps and four plans.

Despatch from Her Majesty's Secretary of State for India, No. 79-P.W., dated 11th December 1884.

I have received and considered in Council Your Excellency's Public Works letter No. 57, dated 27th October 1884, submitting for my sanction a revised estimate for improving and completing the Palar Anicut System in the Madras Presidency.

2. It appears from your letter and the documents accompanying it that this project, which was commenced in 1855, has been enlarged in scope from time to time till 1882, when your Government called on the Government of Madras for a complete revised estimate covering the cost of all necessary improvements. This final estimate, which you now transmit, provides for a total expenditure on the work of Rs. 19,93,893, of which Rs. 15,92,004 have already been expended, leaving, therefore, a balance of Rs. 4,01,889 to be provided, Rs. 3,02,911 of this sum being direct, and Rs. 98,978 indirect, outlay.

3. The direct returns obtained hitherto from the operations of this work have not been satisfactory, but this is accounted for by the fact mentioned in the enclosures to your letter, that the river Palar, which supplies the system, is absolutely without water for three-fourths of the year, and also by the defects in the headworks and distributing channels. In spite of these drawbacks, however, the area irrigated has increased from a total of 9,777 acres in 1855 to a total of 87,403 acres in 1882-83, and it is estimated that by the improvements to be now effected, a total irrigated area of 102,700 acres will be reached in 1887-88, these figures representing first and second crops combined. The benefits conferred by the work must, therefore, have been, and will probably continue to be, considerable, and the comparatively small further expenditure estimated to be required to remedy existing defects and improve and regularize the water-supply should also bring about, eventually, better results still.

4. Although the accounts of this work show that there still remains an accumulated charge of about eight lakhs of rupees on account of the excess of interest on capital above net revenue in past years, I observe that the present net return is rather more than 4 per cent on the direct capital outlay. This result is satisfactory, and I sanction the revised estimate of cost for the Palar Anicut System, amounting to Rs. 19,93,893, of which Rs. 18,94,915 represents direct, and Rs. 98,978 indirect, charges, the work being classed as an Imperial Ordinary Work, and the funds provided from your ordinary revenues by such advances as having regard to other works which are in progress, your Government may be able to spare.

