

Ecclesiastical (1899) Department.

ORDINARY MS.

G.O., No. 11

DATED 24-1-88.

INDEXED.

[Despatch Abstract.]

Coming to the Venble the
Archdeacon pro D.W.D. sancts, for execution
when funds are available, an estimate
amounting to Rs 3,200 for removing & re-roofing
the existing roof of St Paul's Church at Walfair

T
24-1-88

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

Indice
Electoralities (1899) Department

CURRENT No. 25

BUILDINGS AND ROADS.
CIVIL WORKS.

Government {1899} of Madras.
PUBLIC WORKS.

✓ (a.s.)

Order no 11 of 24-1-99
This Communicated to
the Honorable the
Archdeacon

Recd. 21-1- }
Regd. 21-1- } 1899.

Enclosures
Spare copies *C. C. 12-1-99* *24/1/99*

To the Honorable the
Archdeacon } on ac.

G.O., No. 77 W., 9th January 1899.

JANUARY.

St. Paul's Church at Waltair

Estimate of Rs. 3,200 for removing and re-roofing the existing roof of —, in the Vizagapatam district, sanctioned, with remark, for execution when funds are available.

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

READ—the following papers:—

From the Venerable W. WESTON ELWES, M.A., Archdeacon of Madras, to the Chief Secretary to Government, dated 14th October 1898, No. 4686.

I have the honour to forward, for the favourable consideration of Government, an estimate for Rs. 2,850 for "removing and re-roofing the existing roof of St. Paul's Church at Waltair."

2. I forward enclosed—

- (a) Report.
- (b) Data for 100 cubic feet of brick in chunam.
- (c) Estimate from detail measurements.
- (d) " from abstract.
- (e) Plan.

No. 2346, Ecclesiastical.

Approved and transferred to the Public Works Department.

1st November 1898.

(Signed) A. EDGINGTON,
Ag. Assistant Secretary.

Office-note from the Examiner, P.W. Accounts, dated 15th Dec. 1898, No. 4246 B./A.

Note by the Chief Engineer, Public Works Department.

The estimate for re-roofing St. Paul's Church at Waltair is recommended for sanction, subject to the following remark:—

The section proposed for the rolled steel girders, viz., 16" × 5" weighing 50 lb. per foot run, is weak, and is altered to 18" × 7" weighing 75 lb. per foot run. The total weight of the girders is thus increased from 60.7 cwts. to 91 cwts., and the amount of the estimate from Rs. 2,850 to Rs. 3,200.

17th December 1898.

(Signed) W. B. DEWINTON,
Chief Engineer.

ORDER—No. 77 W., dated 9th January 1899.

The estimate amounting to Rs. 3,200, as altered by the Chief Engineer, for removing and re-roofing the existing roof of St. Paul's Church at Waltair, in the Vizagapatam district, is sanctioned for execution when funds are available.

2. Attention is drawn to the Chief Engineer's note read above.

3. This sanction has been registered as Provincial No. 98 W. of 1898-99, and classified as Civil Buildings—Original Works.

(True Extract.)

Under Secretary to Government.

To the Superintending Engineer, I Circle, with five enclosures.
" Examiner, Public Works Accounts.
" Ecclesiastical Department.

Exd. T. K. Narayana Aiyangar.

When given for copying 1/
When copied 24/ 1899.
When examined /
When signed /

READ AGAIN G.O., No. , DATED
189 ,

CURRENT No.

ENCLOSURES TO G. No

ORDER OF GOVERNMENT A A A A A A A

LETTER OF GOVERNMENT.

STATEMENT WITH DITTO.

PAPERS NOT FILED UP, BEING MEANT FOR DESPATCH
IN ORIGINAL.

N.B.—

A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only.