

al ①
1 & Munl. (190¹⁵) Department.

~~Plague.~~

MISCELLANEOUS.

G.O., No. 183 mis *R*

(pp-11)

DATED 19-2-15.

63 + 15 = 78 *man*

[Despatch Abstract.]

5A
Wing Grant. Recd viz with
to go no. 165 Ed., of 15.2.15,
from the D.P.I recommending
for St. Joseph's College
improvement.

Educational DEPARTMENT.

Received 191 . Registered 191 .

Subject.

Recommending a half grant towards the construction of an upper storey over the northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.

ENCLOSURES

No.

Ref. on Cur. No. 7931/14.

Spare copies

Station Madras, Dated the 11 November 1914

From (Name) The Hon. Mr. J.H. Stone, M.A., F.R.H.S.,
C.I.E.,

(Designation) Director of Public Instruction.

To The Secretary to the Government of Madras,
Educational Department.

Sir,

I have the honour to submit an application
for building grant together with plans (bearing Nos. 174 (a)

Enclosures.

- | | | |
|--|---|---------------|
| 1. Application for building grant. | 0 | and 174 (b)) |
| 2. Plan of the proposed upper storey (in triplicate) | 0 | |
| 3. Site plan (in triplicate) | 0 | and estimates |
| 4. Estimates in (duplicate) | 0 | amounting to |

Rs.25,066 for the construction of an Upper Storey over the Northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly. The necessity for the proposal and the nature of work have been explained on page 5 of the application. I beg to recommend that a grant not exceeding

2784/15 12-1-14


one-half of the total estimated cost may be sanctioned, payable when funds become available.

2. The Correspondent requests that if the grant is sanctioned, the whole amount may be paid in advance relying for a precedent on the payment in advance of a grant for a hostel. The special grant for hostels was distributed in advance for our convenience and I see no reason in this case for payment of an advance before any work at all is done, and I do not therefore support the request. He may make an application for payment of an advance supported by a certificate from the Public Works Department when the work is partially completed.


I have the honour to be,

S i r,

Your most obedient servant,



for Director of Public Instruction.



P.V.S.

The Director of Public Instruction submits for sanction, through the Educational Department, plans and estimate amounting to Rs. 25066 for an upper storey over the northern wing of the Lawley Hall of St. Joseph's College, Trichinopoly.

II. The plans and estimates cannot be scrutinized for want of the following information:-

A. The sizes of the doors and windows of the existing north wing and the positions of the truss in the Central hall are not marked on the plans.

B. The nature of the existing roofs should be described, whether Mangalore tiles over flat tiles with air spaces, Mangalore tiles imbedded in 1" mx mortar or plain Mangalore tiles.

C. The scantlings of the existing roof timbers should be marked on the plans with their spacing centre to centre.

D. There is no need of one additional truss as those removed from the existing roof are sufficient for the proposed first floor.

E. The thickness of the walls on the proposed first floor are marked 13 inches ^{on the plan} but the estimate shows 18 inches.

F. The weights per foot of Cast iron columns for 5½" ^{average} and 3½" diameters are given as 45.31 lbs. against an approximate weight of 34.95 and 20.22 lbs. per foot respectively.

: 2 : 6 5

With these remarks the plans and
estimates are returned for resubmission
with the required informations.

(Sd) S. B. Murray.

Again G.O. No. , dated

191

Current No. 352182 from the D.P. I

, No. 7931, dated 11-11-1914



Current No. from the

, No. , dated 191

SUBJECT.

Grant for the construction of an upper story over the northern wing of the Lawley Hall attached to the St. Joseph's College, Trichinopoly.

Submitted that the plans and estimates may first be forwarded to the M.D. uo. for scrutiny.



139
17-11-14
17-11-14


P.W.D. uo
19-11-14

Col uo 3521-1
20-11-14

P.W.D.

HA 3-4 CF

Note by the Chief Engineer P.W.D. No. 344C
dy 15-1-15



For the Deputy Secretary

The remarks of the Chief Engineer on the plans and estimate are contained in his note read above. Submitted that the file may now be returned to the Edl Dep^t with the request that the information required by the Chief Engr may be obtained.

Flag A.
(HA 3-4 CF)

Notes in CD 18-1-15
Note 1-4 CF.
P.W. uo 2749 W.K.S. B. 10
16-1-15

11-1-15 Edl uo. when the defn

(9)

Ed. Dept

G.O. No. 165 Ed. (N)
15-2-15

This is one of the cases in which it has been decided that sanction for the building grant should be deferred. If sanction should be deferred it seems unnecessary ^{at present} to call for the additional information asked for by the P.D. A diary order recording the papers is submitted for approval.

158
17-2-15
TL
17-2-15

18/2/15

15-
mP
202915

APPENDIX M.

CHAPTER VIII, RULE 52.

Application for aid towards the cost of constructing an upper storey
building on the Northern wing of the Lawley Hall,
School St. Joseph's at Trichinopoly in the District
College
of Trichinopoly

Number and date of the Proceedings or Memorandum recognizing the school under the
Madras Educational Rules

11423 dated 28th Sept. 1891.

Brief history of the institution from the date of its establishment to the date of
application tracing its growth and development and furnishing among other things an
accurate account of its financial condition.

Already furnished in our application for
building grant No 49 dated 19-9-1912.

History of the Institution—cont.

- NOTE.—(1) This need not be given if a reference to a history previously given can be furnished.
- (2) The names and designations of the persons who form the committee of management should be specified.

The strength of the different classes or forms as it stood on the 31st March of every year for five years preceding the year in which the application is submitted.

	191	191	191	191	191	Number of pupils in each class on the date of application.	Number of pupils that can be accommodated in each class room.
VI Form ..							
V " ..							
IV " ..							
III " ..							
II " ..							
I " ..							
IV Class ..							
III " ..							
II " ..							
I " ..							
Infant ..							
Total ..							

Class room.	Area.	Class room.	Area.
a		k	
b		l	
c		m	
d		n	
e		o	
f		p	
g		q	
h		r	
j		s	

NOTE.—If there be any striking variations in the strength as shown above such variations should be accounted for.

Character of and necessity for the proposed work in detail.

We propose to build on the northern wing of the Lawley Hall, a storey which will contain six rooms.

Of these six rooms, 3 are to be used as class rooms, 2 as retiring rooms for Professors and one as a Reading room for the College Union. This new Reading room will be one room downstairs, now used as Reading room, but to be turned to a lecture room, when the proposed building is completed.

The necessity for more rooms arises from several circumstances

i) Our lay staff has increased very much these last few years. Under the old system, we had no lay staff attached to the College beyond the Tamil, Malayalam and Sanskrit Pandits. Our present staff includes 6 assistant Professors, Lecturers, Tutors, Demonstrators etc., and it is absolutely necessary to provide them with rooms where they may retire when they are not actually on duty. I believe the two rooms, detailed for that purpose, is a bare minimum, in fact insufficient, but we cannot afford to do more for the time being.

ii) The Courses in the various groups and for the various University Degrees have now reached their full extension, in fact have become more extensive than could have been foreseen some years ago, and have given rise to unforeseen needs. I may particularly mention languages.

I must add that we ought to have built in May 1914, but were unable to do so owing to our architect being too ill to have the plans ready in time. The delay has increased our difficulties and we cannot wait any longer.

(i) Is a sketch plan of the proposed site and building attached? *yes.*

(ii) Does it show—

(a) The relation of the proposed building or extension to the existing buildings? *yes.*

(b) Any alteration in existing buildings necessitated by it?

Removing roof, raising walls and changing columns of veranda.

(c) The purpose to which the existing buildings are now put?

Class rooms and one Reading Room.

(d) The purpose to which they will be put when the new building or extension is complete?

Class rooms.

NOTE—Any notes that cannot be conveniently inserted in the plan may be given under each of the above headings.

(a) Probable cost of the proposed work.

Rs. 25066/-

(b) Whether the management has the necessary funds to complete the work in the event of the application being favourably considered.

yes.

(c) Whether the managing body has been registered under the Indian Companies Act of 1882 and if so, whether attested copies of the Memorandum of Association and the Articles of Association are submitted.

No.

(d) If the aid sought for is towards the cost of site, declaration that it is the cheapest suitable site.

Nil.

(e) Declaration that the management is prepared to execute the prescribed deed if required by the Director to do so.

The management is prepared to execute the prescribed deed if required.

(f) If the property is not owned by the correspondent, declaration that the owner or his or her legal representative will execute the deed or will be made a party to the deed.

The property is owned by the Society, St. Joseph's College, Trichinopoly.

The Procurator will execute the deed.

(g) In the case of mission institutions the name and address in full of the person who holds a power of attorney on behalf of the mission to execute the prescribed deed.

*Rev. B. Sauthier, S.J. is
the Procurator, St. Joseph's College, Trichinopoly.*

(h) Name, designation and qualification of the person by whom detailed plans and estimates and specifications will be prepared.

*The Rev. Brother X. Antony, S.J.
College Architect.*

(i) Whether the title to the property is clear and in order and by whom the title-deeds were examined.

yes. There is prescription as we have been in undisputed possession of the land for more than 30 years.

(j) The latest date on which the management wishes to (i) begin the work and (ii) complete the work.

(i) 1st. April, 1915.

(ii) As early as possible after 1st. July 1915.

N.B. College work should not be interfered with; hence building should be completed during vacation, if possible.

(k) Is the declaration with regard to encumbrance, alienation and the conditions of recognition and aid attached?

yes. See Page 10.

(l) Amount of building grants drawn by the institution in previous years with the number and date of the sanction and the purposes for which given (Particulars should be given for 20 years).

Rs. 1000/- for the addition of a storey to the old Physics Class room. Pro. D.P.F. No. 4830 of 19-6
 Rs. 6400/- for the construction of a Hostel. Pro. D.P.F. No. Ref. no C. 7616 of 12 27 24-2-1913.

(m) If the aid sought is towards the construction of a hostel, declaration that the hostel will be managed according to rules approved by the Director of Public Instruction.

Nil

(n) The treasury at which the grant if sanctioned is to be payable.

Tirichinopoly.

(o) The annual expenditure incurred in the upkeep of the institution and how much of it is met from—

	Fees.			Government grant.			Other sources.			Manager's funds.			Total.		
	Rs.	A.	P.	Rs.	A.	P.	Rs.	A.	P.	Rs.	A.	P.	Rs.	A.	P.
1910	21,820	10	3	15,420	-	-	300	7	-	35277	2	72824	1	5	
1911	22,048	9	9	15,545	-	-	850	15	6	39201	5	77645	9	8	
1912	4,123	15	-	15,145	-	-	250	-	-	49830	1	97449	-	10	
1913	43,418	11	-	28,897	-	-	300	-	-	29265	1	71,980	12	7	
1914	53,497	5	-	21,687	-	-	260	-	-	46308	14	121,753	3	-	
Total.	182,509	3	-	96,644	-	-	1967	6	6	193,713	2	474,883	11	6	

Particulars for five years to be furnished.

Inspecting officer's remarks about accommodation from his inspection reports for the two previous years.

Director's review of such remarks

DECLARATION with regard to encumbrance, alienation and the conditions of recognition and aid.—“On behalf of the management of the school, I hereby declare that the property is unencumbered and that it will not be alienated or encumbered without the consent of Government within twenty years and that the conditions of recognition and aid laid down in the Madras Educational Rules and in the Grant-in-aid Code are being, and will continue to be, fully observed, excepting those rules from which the institution has been specially exempted by the Director's Proceedings, No. , dated , and that I am prepared to subject the institution together with its current, endowment and trust accounts, its establishment, time-table and registers to inspection and to furnish such returns as may be required by the department; and that I shall abide by the provisions of rule 55 of the Grant-in-aid Code in the event of the building being diverted, prior to the lapse of twenty years after the date of payment of grant, to other than educational purposes approved by Government.”

STATION, Trichinopoly
Dated 28-8-1914.

100/100

Correspondent.

Inspecting officer's remarks and recommendations.

18

6

General Specification.

Name of work: Constructing an upper storey over the Northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.

The plans and estimates have been prepared in accordance with the Chief Engineer's Circular No.116 C, dated 4th January 1913 and are signed by Brother Antony S.J., Architect, St. Joseph's College, Trichinopoly.

List of drawings.

Site survey plan: Scale 1 inch = 24 ft.

Building plan, section, side elevation and the front elevation etc. Scale 1 inch = 8 ft.

Total amount of the estimate: Rs. 25066-0-0

Details of construction.

Nature of surface soil:	Hard earth to a height of 2 feet.
Nature of sub-soil:	Soft rock to a height of 3 feet and rock below.
Maximum pressure on soil:	Vide calculation attached. Calculation for Rolled steel girder is attached.
Description of foundation as existing	The concrete foundation stone jelly in mortar has been laid out to a height of 6 feet and 3½ ft. in breadth.
Description of basement:	The basement was constructed with brick in mortar, the height of basement 3 ft and the breadth 2½ ft.
Description of Superstructure:	The superstructure was constructed with brick in mortar and the proposed work will be constructed with brick in mortar over the existing walls.
Name of timber which it is proposed to use for roof timbers.....	Teak.
Name of timbers which it is proposed to use for doors, windows and ventilators...	Teak.
Roofing materials.....	The roof will be of Mangalore tiles imbedded with one inch mortar over country flat tiles & teak reopers. The existing Mangalore tiled roof will be removed and replaced with necessary new materials.
Flooring materials.....	The rooms will be paved with Portland cement ½" thick and watered for a week.

Plastering: The exterior and the interior walls of the building will receive 2 coats of fine chunam.

Painting : The replaced roof timbers will be painted with 2 coats of chocolate paint, hand railing with fine green paint 2 coats and the iron work will be painted with fine light blue, 2 coats.

Wood oiling: The joists and rafters will be painted with wood oil, 2 coats.

Varnishing : The doors, windows and ventilators will be varnished, 2 coats.

St. Joseph's College, I

Trichinopoly,

14 - 3 - 1914

M. Anthony S. J.
College Architect.

Calculation showing the maximum pressure on the foundation for the construction of an upper story building on the northern wing of the Lawley Hall, attached to St. Joseph's College, Trichinopoly.

Concrete foundation stone	1	=	1 x 6 x 3 1/2 x 145 lbs.	=	3045
Jelly in mortar	...				
Basement brick in mortar	..	=	1 x 3 x 2 1/2 x 120 lbs.	=	900
Superstructure brick in mortar.	...	=	1 x 2 x 17 1/2 x 120 lbs	=	4200
Girdor (14" x 6") weighing		=	1 x 12 x 57 lbs.	=	684
57 lbs per foot run	..				
Terrace brick in mortar	..	=	1 x 10 x 173 lbs.	=	1730
Upper story superstructure		=	1 x 1 1/2 x 17 1/2 x 120 lbs	=	3675
brick in mortar	...				
Terrace verandah brick in mortar		=	1 x 4 1/2 x 173 lbs	=	822
Mangalore tiled verandah	.	=	1 x 5 1/2 x 35 lbs	=	193
Mangalore tiled roofing	.	=	1 x 15 x 35 lbs	=	560
Total					15809

For 3 1/2 ft. = 15809
∴ 1 Sq.ft = 15809 - 3 1/2 = 2.01 tons.

As the existing building was built strongly on the rocky soil, the proposed structure will stand safely.

St. Joseph's College
Trichinopoly
14 - 3 - 1914.

On. Anthony S.J.
College Architect

Calculation for the section of the rolled steel girder
in the class room (24'x 18') clear span.

Divided by No.1 Rolled steel girder the area to be supported
= 24'x 9' = 216 sft of the terrace roof.

The weight of 216 sft of terrace, at dead load 20 lbs and live
load 70 lbs = 150 lbs per sft. $\frac{216 \times 150}{2240} = 14.91$ tons.

According to the Rule of selecting beams for the span that the
depth of the girder should not be less than 1/20 of the span

The depth of the girder required span $\frac{24' \times 12''}{20} = 14.4$

Taking the depth of the girder is 14" the section required for
calculated load of 14.91 tons = 14"x 6" at 57 lbs per foot run
which will safely carry a load of 15 tons.

St. Joseph's College
Trichinopoly

Bn. Anthony S.J.
College Architect.

ESTIMATE FORM. Detail Measurements.

23

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Estimate for constructing the North Wing of the Lawley Hall into an upper story building attached to St. Joseph's College at Trichinopoly.						
<u>Lower floor.</u>						
<u>Concrete</u>						
Staircase partition wall in passage. ..	1	22 $\frac{3}{4}$	2 $\frac{1}{4}$	6	307	
Verandah staircase pillars ..	2	3 $\frac{1}{2}$	3 $\frac{1}{2}$	3	74	
Extending the existing walls in verandah for staircase ..	2	5 $\frac{1}{2}$	3 $\frac{1}{2}$	3	116	
Total concrete work in cft.						497
<u>Basement brick in mortar</u>						
Staircase partition wall in passage ..	1	23 $\frac{1}{2}$	1 $\frac{3}{4}$	3	123	
Verandah walls in staircase .	2	5 $\frac{1}{2}$	1 $\frac{1}{2}$	8	132	
Pillars for staircase in verandah ..	2	2	2	8	64	
Total basement brick in mortar c.ft.						319
<u>Superstructure brick in mortar</u>						
Staircase partition wall in passage ..	1	24	1 $\frac{1}{2}$	17 $\frac{1}{2}$	525	
Building walls all round at 3 sides of the north wing ..	1	217 $\frac{3}{4}$	2	$\frac{1}{2}$	218	
Building walls on the southern side of the north wing ..	1	169 $\frac{3}{4}$	2 $\frac{1}{2}$	$\frac{1}{2}$	191	
Pillars for staircase in verandah ..	1	1 $\frac{1}{2}$	1 $\frac{1}{2}$	10 $\frac{1}{2}$	24	
Do. Do. ..	1	1 $\frac{1}{2}$	1 $\frac{1}{2}$	5	11	
Total superstructure brick in mortar ..cft.						969

ESTIMATE FORM.—Detail Measurements.

24

19

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Cutstone work.</u>						
Bed plates under girders ..	22	1	1 $\frac{3}{4}$	$\frac{1}{2}$	19	
Total cutstone work						19
<u>Iron girders</u>						
Rolled steel girders (14" x 6") weighing 57 lbs per foot run in the main building ..	11	28 x 57 lbs			17556	
Rolled steel girders (7" x 4") weighing 16 lbs per foot run to be used as bressummers over the columns in the verandah ..	1	177 x 16 lbs			2832	
Total girders in lbs or say in Tons						9.1
<u>Cast iron columns including brackets</u>						
Columns in verandah top 5" Dr. and the bottom 6" Dr. thickness of metal $\frac{3}{4}$ " (45-310) per foot run ..	23	average 5 $\frac{1}{2}$ " Dr			15 $\frac{1}{2}$	16153
Total columns in lbs.						16153
<u>Terrace work</u>						
Verandah ..	1	177 $\frac{1}{4}$	9 $\frac{1}{2}$		1684	
Main rooms ..	1	158 $\frac{1}{2}$	25		3963	
Portion of staircase ..	1	9	4		36	
Total terrace work					Sq. ft.	5683
<u>Teak wood wrought and put up</u>						
Joists in main rooms including overlapping ..	19	165	2 $\frac{1}{2}$ "	7"	380.98	
Joists in staircase passage ..	4	9	2 $\frac{1}{2}$ "	7"	4.57	
Joists in stair platform ..	1	10	4"	8"	3.22	
Do. Do. ..	1	10	2 $\frac{1}{2}$ "	7"	1.21	
Planks for platform ..	1	8	4	1 $\frac{1}{2}$	4.00	
carried over						392.78

ESTIMATE FORM.—Detail Measurements. 25

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward					392.78	
Rain board in verandah ..	1	175	1"	6"	7.29	
Joists in verandah ..	140	9½	2½"	6"	138.54	
Beam in staircase ..	1	7	4"	8"	1.55	
Total wood wrought and put up						540
<u>D O O R S</u>						
Toak panolled doors with frames in centre room ..	2	4		9½	76	
Total doors					Sq.ft.	7
<u>Cement plastering 1" thick.</u>						
Basement all round of the proposed extension of verandah	1	25	7½		188	
Do. Do. at top	1	11	1½		17	
Do. Do. pillars	2	8		7½	120	
Total cement plastering					Sq.ft.	325
<u>Mangalore tiled roof</u>						
Removing the existing tiled verandah ..	1	170	10		1700	
Removing the existing main roof on both sides ..	1 x 2	170	16		5440	
Total roofing removing					Sq.ft.	7140
<u>Plastering with chunam, 2 coats.</u>						
Plastering with chunam all round in and out for the raised portion ..	1	772		¾	579	
Partition wall on both sides	1 x 2	24		17	816	
Sides and soffit of doors ..	2	23	2½		96	
Total plastering					Sq.ft.	1491

ESTIMATE FORM.—Detail Measurements.

26

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Wood oiling, 2 coats.</u>						
Joists in main rooms ..	19	159	1 5/12		4279	
Joists in verandah ..	140	9	1 3/4		1575	
Staircase joists ..	4	8	1 5/12		45	
Joists in staircase platform .	1	8	1 2/3		13	
Do. Do. ..	1	8	1 5/12		11	
Planks on both sides ..	1 x 2	8	4		64	
Beam in staircase ..	1	6 1/4	1 2/3		10	
Total wood oiling					Sq.ft.	5997
<u>Varnishing, 2 coats</u>						
Doors ..	76 x 2 1/4 times				171	
Total varnishing					Sq.ft.	171
<u>Painting iron works.</u>						
Columns with brackets ..	23	15 1/2 x 17.278			513	
Girders ..	11	24 x 49			1078	
Bressummers girder ..	1	170 x 26			368	
Total painting					Sq.ft.	1959
<u>Iron rail</u>						
Iron rails to support the staircase					24	
Total S.I.R. rails					R.ft	24

27

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Estimate for construction of an upper story building over the north wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.						

UPPER FLOOR.						

Superstructure brick in mortar.						
Building up walls on southern side of the north wing ..	1	169 $\frac{3}{4}$	1 $\frac{3}{4}$	8	2377	
Building up walls at 3 sides of the north wing ..	1	217 $\frac{3}{4}$	1 $\frac{3}{4}$	18	6859	
Cross walls in main building .	6	24	1 $\frac{1}{2}$	18	2808	
End walls of the main building	2	25 $\frac{3}{4}$	1 $\frac{3}{4}$	18	1622	
Gable of cross walls in centre	6	25 $\frac{3}{4}$	1 $\frac{1}{2}$	4 $\frac{1}{2}$	697	
Gable of end walls ..	2	27 $\frac{3}{4}$	1 $\frac{3}{4}$	6 $\frac{1}{2}$	631	
Total					14994	
Deduct for doors ..	18	4 $\frac{1}{2}$	1 $\frac{3}{4}$	9	1276	
Deduct for flat arch over doors	18	5 $\frac{5}{8}$	1 $\frac{3}{4}$	1 $\frac{1}{2}$	266	
Deduct for windows at ends	4	4	$\frac{1}{2}$	5	40	
Deduct for flat arch over windows at ends ..	4	5	1 $\frac{3}{4}$	1 $\frac{1}{2}$	53	
Deduct for ventilators ..	19	4	1 $\frac{3}{4}$	4	532	
Deduct for flat arch over ventilators ..	19	5	1 $\frac{3}{4}$	1 $\frac{1}{2}$	249	
Deduct for rectangular opening in staircase passage wall ..	1	7	1 $\frac{3}{4}$	5 $\frac{1}{2}$	67	
Deduct for semi-circular space in staircase passage wall ..	1 x 7 ²	x .7854 x 1 $\frac{3}{4}$ x 1 $\frac{1}{2}$			50	
Deduct for circular arch work in staircase passage wall ..	1 x 8 $\frac{3}{4}$	x $\frac{3 \cdot 1416}{2}$ x 1 $\frac{3}{4}$ x 1 $\frac{1}{2}$			38	
carried over					2571	

-2- 28
ESTIMATE FORM.—Detail Measurements.

Detail of Work,	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward					2571	
Deduct for ventilators ..	19	4	1 1/2	2	266	
Deduct for semi-circular opening in end walls ..	2 x 52 x .7854 x 1/2				20	
Deduct for circular arch work in end walls ..	2 x 6 1/2 x 3.1416 x 1 1/2 x 1 1/2				107	
Total deduction in cft.....					2964	
Total superstructure less deduction					<i>est.</i>	1203
<u>Flat arch work in mortar.</u>						
Doors ..	18	5 7/8	1 1/2	1 1/2	266	
Windows ..	4	5	1 1/2	1 1/2	53	
Ventilators ..	19	5	1 1/2	1 1/2	249	
Total flat arch work in mortar					cft.	568
<u>Circular arch work in mortar.</u>						
Circular arch in staircase opening ..	1 x 8 3/4 x 3.1416 x 1 1/2 x 1 1/2				38	
Circular arches in end walls ..	2 x 6 1/2 x 3.1416 x 1 1/2 x 1 1/2				107	
Total circular arch work					cft	145
<u>Cutstone work.</u>						
Lintel stones over ventilators ..	19	6	1 1/2	1	100	
Steps	1	4 1/2	3 3/4	1	17	
Total cutstone work					cft.	117
<u>Cast iron columns</u>						
Columns in verandah top 3" Dr. & the bottom 4" Dr. thickness of metal 3/4" (45-310) per foot run ..	23	<i>average</i> 3 1/2" Dr.		9	9379	
Total columns in lbs.....						9379

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Mangalore tiled roof.</u>						
Verandah ..	1	170	11		1870	
Ridge ventilators on both sides ..	2	168	5½		1848	
Staircase passage ..	1	32	5		160	
Do. Do. ..	1	6	14		84	
Total Mangalore tiled roof					Sq.ft.	3967
<u>Re-roofing with Mangalore tiles &c.</u>						
Re-roofing the main building on both sides ..	2	169	17½		5915	
Total re-roofing					Sq.ft.	5915
<u>Teak wood wrought and put up</u>						
Rafters in verandah ..	86	10½	2½"	5"	78.93	
Raw board in verandah ..	1	175	1"	6"	7.29	
Rafters in porch ..	8	5½	2"	4"	2.44	
Staircase rafters including overlapping ..	3	34	2½"	6"	10.62	
Purlins ..	3	6	3"	5"	1.87	
Post in staircase ..	3	9½	4"	4"	3.16	
Collar pieces ..	4	4	2"	3"	0.66	
Bressummers in staircase ..	2	9	4"	6"	3.00	
Do. Do. ..	1	6½	3"	5"	0.67	
Struts in Ridge ventilators on both sides ..	166	3	2"	3"	20.75	
Rafters on both sides of the ridge ventilators ..	166	4½	2"	3"	31.12	
Collar piece for Do. ..	83	5	2"	3"	17.29	
Total wood work					Sq.ft.	177.80

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>D O O R S.</u>						
Teak panelled doors ..	18	4 $\frac{1}{2}$		9	729	
Total doors					Sq.ft.	729
<u>W I N D O W S.</u>						
Windows ..	19	4		6	456	
Total windows					Sq.ft.	456
<u>W I N D O W S.</u>						
Windows ..	19	4		4		
Total windows					Sq.ft.	304
<u>Ventilators</u>						
Ventilators ..	19	4		2	152	
Total ventilators					Sq.ft.	152
<u>Cement plastering, $\frac{1}{2}$" thick</u>						
Floor of class rooms ..	1	39 $\frac{3}{4}$	24		954	
Do. Do. ..	1	23 $\frac{1}{2}$	24		564	
Do. Do. ..	1	14	24		336	
Do. Do. ..	1	18 $\frac{1}{2}$	24		444	
Do. Do. ..	1	18 $\frac{1}{2}$	24		444	
Do. Do. ..	1	37	24		888	
Verandah floor ..	1	176	10		1760	
Drain to pass off the rain water from the roof ..	1	165	2		332	
Doorway sills ..	18	4 $\frac{1}{2}$	1 $\frac{1}{2}$		150	
Archway sill ..	1	7	1 $\frac{1}{2}$		12	
Platform ..	1	8	4		32	
Total cement plastering					Sq.ft.	5916

ESTIMATE FORM.-Detail Measurements.

31 26

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Cornice work</u>						
Cornice all round the main building, gable walls and porches etc.	1	432			432	
Total cornice work					R.ft.	432
<u>Earthenware pipe 6" Dr.</u>						
Earthenware pipe to be fixed in wall to run off rain water	9	9			81	
Total pipe					R.ft.	81
<u>Galvanized iron gutter.</u>						
gutter Galv. iron at eaves of the main roof with necessary iron fittings etc.	1	170			170	
Do. in staircase	1	6			6	
Total galvanized iron gutter.....					R.ft.	176
<u>Teak hand railings</u>						
Teak hand railings turned in verandah all round	1	183½	2½		459	
Do. Do. in staircase	1	32	3		96	
Do. Do. Do.	1	38	3		114	
Total hand railings					Sq. ft.	669
<u>Plastering with chunam, 2 coats</u>						
Union reading room all round inside	1	127½	16½		2102	
Professors' room all round inside, large	1	94⅝	16½		1564	
Do. Do. small	1	76⅝	16½		1257	
Staircase passage all round inside	1	64½	16½		1064	
Carried over					5987	

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward					5987	
Honours Mathematics room all round inside ..	2	84 $\frac{5}{8}$		16 $\frac{1}{2}$	2799	
Intermediate Mathematics room all round inside ..	1	121 $\frac{1}{2}$		16 $\frac{1}{2}$	2012	
Verandah front wall including top portion. ..	1	169 $\frac{3}{4}$		16	2716	
Rear wall of the building ..	1	169 $\frac{3}{4}$		5	849	
Side walls of the building ..	2	27 $\frac{1}{2}$		16 $\frac{1}{2}$	908	
Gable of cross walls ..	14	24		8	2688	
Gable of end walls ..	2	27 $\frac{1}{2}$		9	495	
Sides of arch including soffit	1	19	1 $\frac{3}{4}$		33	
Sides and soffit of doors	18	22 $\frac{1}{2}$	1 $\frac{3}{4}$		709	
Sides, soffit and sill of windows ..	4	18	$\frac{1}{2}$		36	
Sides, soffit and sill of ventilators ..	19	13	1 $\frac{3}{4}$		432	
			Total		19664	
Deduct for doors ..	18 x 2	4 $\frac{1}{2}$		9	1458	
Deduct for ventilators ..	18 x 2	4		4	576	
Deduct for rectangular portion in arch-way ..	1 x 2	7		5 $\frac{1}{2}$	77	
Deduct for semi-circular portion of the arch in staircase ..	1 x 2	12			24	
Total deduction				Sq.ft.	2135	
Total plastering less deduction				Sq.ft.	17529	
Varnishing, 2 coats.						
Doors ..	729 x 2 $\frac{1}{2}$ times				1823	
Windows ..	456 x 1 $\frac{3}{4}$ times				798	
Carried over					2621	

5

ESTIMATE FORM.—Abstract.

3.34 29

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
Estimate for constructing an upper story building over the northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.					
----- LOWER FLOOR. -----					
<u>Earth work</u>					
497 cft	Excavating foundation and refilling in <u>Concrete.</u>	10-0	1000cft	5	
497 "	Concrete broken stone jelly in mortar <u>Brick work.</u>	20-0	100 cft	99	
319 "	Basement brick in mortar	24-0	Do.	77	
159 "	Superstructure brick in mortar	26-0	Do.	252	2
<u>Cutstone work.</u>					
19 "	Cutstone work including dressing etc.,	2-0	cft.	38	
<u>Iron work.</u>					
9.10tons	Rolled steel girders	200-0	ten	1820	
Do.	Hoisting and setting charges	10-0	"	91	
16153 lb.	Ornamental cast iron columns including brackets etc.	0-2	lb.	2019	
24 Rft.	Iron rails for staircase supports S.I.R.	1-4	Rft.	30	3960
<u>Roofing.</u>					
5683 sft	Best terracing with brick on edge 3" concrete 2 courses of flat tiles and plastering with chunam at bottom	31-0	100 sft	1752	
7140 "	Removing the existing Mangalore tiled roofing with the roof materials etc.	5-0	Do.	357	2119
Carried over					6550

Grand Total of Estimate ...

Station _____
Date _____ 191 _____

22

Grand Total of Estimate ...

Station _____
Date _____ 191 _____

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
	UPPER FLOOR. =====				
	<u>Brick work.</u>				
12030cft	Superstructure brick in mortar	.. 27-0	100 cft	3248	
568 "	Flat arch work brick in mortar	.. 28-0	Do.	159	
145 "	Circular arch work brick in mortar	.. 29-0	Do.	42	344
	<u>Cutstone work.</u>				
117 cft	Cutstone work including dressing etc.	.. 2-0	cft	234	
	<u>Iron work.</u>				
9379 lb.	Ornamental cast iron columns	.. 0-2	lb.	1172	
1	Providing new wooden truss with iron bars as per existing one	.. 75-0	each	75	
	<u>Roofing.</u>				
3962sft	Mangalore tiled roofing with flat tiles imbedded in mortar with teak reepers and iron nails etc., complete	.. 30-0	100 sft	1189	
5915 "	Re-roofing with Mangalore tiles with new country flat tiles imbedded in mortar with teak reepers and iron nails etc. (available old materials will be used) and the roof timber will be painted with chocolate colour	.. 20-0	Do.	1183	2372
	<u>Wood work.</u>				
178.80cft	Teak wood wrought and put	.. 5-8	cft	983	
669 sft.	Teak wood turned hand railings	.. 1-0	sft	669	1652
	<u>Doors</u>				
729 sft	Teak pannelled doors with frames etc. glazed shutters at top with iron bars and iron fittings	.. 1-8	sft	1094	1094
	<u>Windows.</u>				
456 sft.	Teak windows with frames and iron bars with glazed shutters and iron fittings	.. 2-0	sft	912	
304 "	Teak windows with frames thick ribbed glass shutters with iron fittings etc.	.. 2-0	Do.	608	
	Carried over.....			1520	10048

Grand Total of Estimate ...

 Station _____ }
 Date _____ 191 _____ }

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
	Brought forward.....			1520	10048
152 sft	Teak ventilators with frames and glazed shutters with iron fittings ..	1-0	sft.	152	1672
	<u>Flooring.</u>				
5916	"Paved with cement plastering, $\frac{1}{2}$ " thick ..	10-0	100sft	592	5
	<u>Finishing.</u>				
472 "	Cornice work in mortar ..	0-6	2ft.	162	
17529 "	Plastering with chunam, 2 coats ..	2-8	100sft	438	
3305 "	Varnishing, 2 coats ..	2-8	Do	83	
190 "	Painting with light blue, 2 coats ..	3-0	Do.	6	
1004 "	Green paint, 2 coats ..	3-0	Do.	30	
1547 "	Painting with chocolate colour, 2 coats to roof timbers ..	2-8	Do.	39	
	<u>Miscellaneous</u>				
81 Rft	Earthenware pipe 6" Dr. 9' long fixing in cement etc., complete ..	1-0	Rft	81	
176 "	Galvanized iron gutter with supports and nails etc., complete ..	0-8	Do.	88	
	Providing teak staircase with necessary fittings etc., complete ..			250	
	Preparation of Plans and estimate etc. ..			70	
	Clearing site and removing rubbish etc. ..			50	539
	Contingencies ..				600
	Petty supervision ..				600
	Total Rupees				14809

Bn. Antang. S. J.
College Architect.

Grand Total of Estimate ... 14809

Station Trichinopoly }
Date 191 }

ESTIMATE FORM.-Abstract. 3 38

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
1	Lower Floor as per separate estimate ..				10257
2	Upper Floor as per separate estimate ..				1480
Grand total of estimate Rupees ..					25

B. Antang. S. J.
College Architect.

Grand Total of Estimate ... 25066

Station Trichinopoly
Date 18 August 1914.

for Survey
Correspondent.

for Director of Public Works



ESTIMATE for constructing an Upper
story building on the northern
wing of the Lawley Hall
attached to St. Joseph's
College, Trichinopoly.

Total amount of Y Rs. 25066-0-0
estimate. |

THE NORTH WING OF THE LA
TO BE CONVERTED INTO AN UPPER STORY ST.
AT
TRICHINOPOLY
SCALE 6" = 1" HIGH

SCALE 6'-1 INCH

USED WORK
DENOTES PI
E
ING WORK
DS
415

E LAWLEY HALL EXISTING BUILDING ON A.A.

GROUND



LEVEL

COLLEGE

PLAN
OF
THE NORTH WING OF THE LAWLEY
TO BE CONVERTED INTO AN UPPER STORY ST JOSEPH'S COLLEGE
AT
TRICHINOPOLY
SCALE 1/8" = 1' - 0"


DP.L. 174 (a)

FRONT ELEVATION ON A.B





PROPOSED PLAN OF THE UPPER FLOOR

LOWER



PLAN OF THE LAWLEY HALL
EXISTING



CORRESPONDENT
31. 12. 19

General Specification.

Name of work: Constructing an upper storey over the Northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.

The plans and estimates have been prepared in accordance with the Chief Engineer's Circular No. 116 C, dated 4th January 1913 and are signed by Brother Antony S.J., Architect, St. Joseph's College, Trichinopoly.

List of drawings.

Site survey plan: Scale 1 inch = 24 ft.

Building plan, section, side elevation and the front elevation etc. Scale 1 inch = 8 ft.

Total amount of the estimate: Rs. 25066-0-0

Details of construction.

Nature of surface soil:	Hard earth to a height of 3 feet.
Nature of sub-soil:	Soft rock to a height of 3 feet and rock below.
Maximum pressure on soil:	Vide calculation attached. Calculation for Rolled steel girder is attached.
Description of foundation as existing	The concrete foundation stone jelly in mortar has been laid out to a height of 6 feet and 3 1/2 ft. in breadth.
Description of basement:	The basement was constructed with brick in mortar, the height of basement 3 ft and the breadth 2 1/2 ft.
Description of Superstructure:	The superstructure was constructed with brick in mortar and the proposed work will be constructed with brick in mortar over the existing walls.
Name of timber which it is proposed to use for roof timbers	Teak.
Name of timbers which it is proposed to use for doors, windows and ventilators...	Teak.
Roofing materials	The roof will be of Mangalore tiles imbedded with one inch mortar over country flat tiles & teak reapers. The existing Mangalore tiled roof will be removed and replaced with necessary new materials.
Flooring materials	The floors will be paved with Portland cement 2" thick and mortar 1" thick.

- Plastering: The exterior and the interior walls of the building will receive 2 coats of fine chunam.
- Painting : The replaced roof timbers will be painted with 2 coats of chocolate paint, hand railing with fine green paint 2 coats and the iron work will be painted with fine light blue, 2 coats.
- Wood oiling: The joists and rafters will be painted with wood oil, 2 coats.
- Varnishing : The doors, windows and ventilators will be varnished, 2 coats.

St. Joseph's College,

Trichinopoly,

14-3-1914

B. M. Antony, S. J.
College Architect.

Calculation showing the maximum pressure on the foundation for the construction of an upper story building on the northern wing of the Lawley Hall, attached to St. Joseph's College, Trichinopoly.

Concrete foundation stone		=	6 x 3 $\frac{1}{2}$ x 145 lbs.	=	3045
Jolly in mortar	...				
Basement brick in mortar	..	=	1 x 3 x 2 $\frac{1}{2}$ x 120 lbs.	=	900
Superstructure brick in mortar.			1 x 2 x 17 $\frac{1}{2}$ x 120 lbs	=	4200
Girder (14" x 6") weighing		=	1 x 12 x 57 lbs.	=	684
57 lbs per foot run	..				
Terrace brick in mortar	..	=	1 x 10 x 173 lbs.	=	1730
Upper story superstructure		=	1 x 1 $\frac{3}{4}$ x 17 $\frac{1}{2}$ x 120 lbs	=	3675
brick in mortar	..				
Terrace verandah brick in mortar		=	1 x 4 $\frac{3}{4}$ x 173 lbs	=	822
Mangalore tiled verandah	.	=	1 x 5 $\frac{1}{2}$ x 35 lbs	=	193
Mangalore tiled roofing	.	=	1 x 16 x 35 lbs	=	560

Total 15809

For 3 $\frac{1}{2}$ ft. = 15809

∴ 1 Sq.ft = 15809 ÷ 3 $\frac{1}{2}$ = 2.01 tons.

As the existing building was built strongly on the rocky soil, the proposed structure will stand safely.

St. Joseph's College
Trichinopoly
- 3 - 1914.

B. S. S. S.
College Architect

47
38

Calculation for the section of the rolled steel girder
in the class room (24'x 18') clear span.

Divided by No. 1 Rolled steel girder the area to be supported .
= 24'x 9' = 216 sft of the terrace roof.

The weight of 216 sft of terrace, at dead load 80 lbs and live
load 70 lbs = 150 lbs per sft. $\frac{216 \times 150}{2240} = 14.91$ tons.

According to the Rule of selecting beams for the span that the
depth of the girder should not be less than $\frac{1}{20}$ of the span

The depth of the girder required span $\frac{24' \times 12''}{20} = 14.4$

Taking the depth of the girder is 14" the section required for
calculated load of 14.91 tons = 14"x 6" at 57 lbs per foot run
which will safely carry a load of 15 tons.

St. Joseph's College
Trichinopoly

B. Antang. S. J.
College Architect.

ESTIMATE FORM.—Detail Measurements. 48 39

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Estimate for constructing the North Wing of the Lawley Hall into an upper story building attached to St. Joseph's College at Trichinopoly.						

<u>Lower floor.</u>						
<u>Concrete</u>						
Staircase partition wall in passage. ..	1	22 $\frac{3}{4}$	2 $\frac{1}{4}$	6	307	
Verandah staircase pillars ..	2	3 $\frac{1}{2}$	3 $\frac{1}{2}$	3	74	
Extending the existing walls in verandah for staircase ..	2	5 $\frac{1}{2}$	3 $\frac{1}{2}$	3	116	
Total concrete work in cft.						497
<u>Basement brick in mortar</u>						
Staircase partition wall in passage ..	1	23 $\frac{1}{2}$	1 $\frac{1}{2}$	3	123	
Verandah walls in staircase ..	2	5 $\frac{1}{2}$	1 $\frac{1}{2}$	8	132	
Pillars for staircase in verandah ..	2	2	2	8	64	
Total basement brick in mortar c.ft.						319
<u>Superstructure brick in mortar</u>						
Staircase partition wall in passage ..	1	24	1 $\frac{1}{2}$	17 $\frac{1}{2}$	525	
Building walls all round at 3 sides of the north wing ..	1	217 $\frac{3}{4}$	2	$\frac{1}{2}$	218	
Building walls on the southern side of the north wing ...	1	169 $\frac{3}{4}$	2 $\frac{1}{2}$	$\frac{1}{2}$	191	
Pillars for staircase in verandah ..	1	1 $\frac{1}{2}$	1 $\frac{1}{2}$	10 $\frac{1}{2}$	24	
Do. Do. ..	1	1 $\frac{1}{2}$	1 $\frac{1}{2}$	5	11	
Total superstructure brick in mortar ...cft.						969

ESTIMATE FORM.—Detail Measurements. *49 W*

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Cutstone work.</u>						
Bed plates under girders ..	22	1	1 $\frac{1}{2}$	$\frac{1}{2}$	19	
Total cutstone work					cft.	<u>7</u>
<u>Iron girders</u>						
Rolled steel girders (14" x 6") weighing 37 lbs per foot run in the main building ..	115	28 x 57 lbs			17556	
Rolled steel girders (7" x 4") weighing 16 lbs per foot run to be used as bressummers over the columns in the verandah ..	1	177 x 16 lbs			2832	
Total girders in lbs or say in Tons						<u>9</u>
<u>Cast iron columns including brackets</u>						
Columns in verandah top 5" Dr. and the bottom 6" Dr. thickness of metal $\frac{3}{4}$ " (45-310) per foot run ..	22	<i>average</i> 5 $\frac{1}{2}$ " Dr			15 $\frac{1}{2}$	16153
Total columns in lbs.						<u>16153</u>
<u>Terrace work</u>						
Verandah ..	1	177 $\frac{1}{2}$	9 $\frac{1}{2}$		1684	
Main rooms ..	1	158 $\frac{1}{2}$	25		3963	
Portion of staircase ..	1	9	4		36	
Total terrace work					Sq. ft.	<u>5683</u>
<u>Teak wood wrought and put up</u>						
Joists in main rooms including overlapping ..	19	165	2 $\frac{1}{2}$ "	7"	380.98	
Joists in staircase passage ..	4	9	2 $\frac{1}{2}$ "	7"	4.37	
Joists in stair platform ..	1	10	4"	8"	2.22	
Do. Do. ..	1	10	2 $\frac{1}{2}$ "	7"	1.21	
Planks for platform ..	1	8	4	1 $\frac{1}{2}$ "	4.00	
carried over						<u>392.78</u>

-3-

ESTIMATE FORM.—Detail Measurements. 50.4

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward						392.78
<u>EAVE</u>						
Plank board in verandah ..	1	175	1"	6"	7.29	
Joists in verandah ..	140	9 $\frac{1}{2}$	2 $\frac{1}{2}$ "	6"	136.54	°
Beam in staircase ..	1	7	4"	9"	1.55	
Total wood wrought and put up						54
<u>DOORS</u>						
Teak panelled doors with frames in centre room ..	2	4		9 $\frac{1}{2}$	76	
Total doors						Sq.ft.
<u>Cement plastering $\frac{1}{2}$" thick.</u>						
Basement all round of the proposed extension of verandah	1	25	7 $\frac{1}{2}$		188	
Do. Do. at top	1	11	1 $\frac{1}{2}$		17	
Do. Do. pillars	2	8		7 $\frac{1}{2}$	120	
Total cement plastering						Sq.ft. 325
<u>Mangalore tiled roof</u>						
Removing the existing tiled verandah ..	1	170	10		1700	
Removing the existing main roof on both sides ..	1 x 2	170	16		5440	
Total roofing removing						Sq.ft. 7140
<u>Plastering with chunam, 2 coats.</u>						
Plastering with chunam all round in and out for the raised portion ..	1	772		3	579	
Partition wall on both sides	1 x 2	24		17	816	
Sides and soffits of doors ..	2	23	2 $\frac{1}{2}$		96	
Total plastering						Sq.ft. 1491

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Wood oiling, 2 coats.</u>						
Joists in main rooms ..	19	159	1 3/12		4279	
Joists in verandah ..	140	9	1 3/4		1575	
Staircase joists ..	4	8	1 3/12		45	
Joists in staircase platform .	1	8	1 2/3		13	
Do. Do. ..	1	8	1 5/12		11	
Planks on both sides ...	1 x 2	8	4		64	
Beam in staircase ..	1	6 1/2	1 2/3		10	
Total wood oiling					Sq.ft.	599
<u>Varnishing, 2 coats</u>						
Doors ..	75 x 2 1/2 times				171	
Total varnishing					Sq.ft.	171
<u>Painting iron works.</u>						
Columns with brackets ..	23	15 1/2 x 17.278			513	
Girders ..	11	24 x 49			1078	
Bressumers girder ..	1	170 x 26			368	
Total painting					Sq.ft.	1959
<u>Iron rail</u>						
Iron rails to support the staircase ..	4	6			24	
Total S.I.R. rails					R.ft.	24

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Estimate for construction of an upper story building over the north wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.						
----- UPPER FLOOR. -----						
Superstructure brick in mortar.						
Building up walls on southern side of the north wing ..	1	169 $\frac{3}{4}$	1 $\frac{1}{2}$	8	2377	
Building up walls at 3 sides of the north wing ..	1	217 $\frac{3}{4}$	1 $\frac{1}{2}$	18	6859	
Cross walls in main building .	6	24	1 $\frac{1}{2}$	18	2808	
End walls of the main building	2	25 $\frac{3}{4}$	1 $\frac{1}{2}$	18	1622	
Cable of cross walls in centre	6	25 $\frac{3}{4}$	1 $\frac{1}{2}$	4 $\frac{1}{2}$	697	
Cable of end walls ..	2	27 $\frac{3}{4}$	1 $\frac{1}{2}$	6 $\frac{1}{2}$	631	
Total					14994	
Deduct for doors ..	18	4 $\frac{1}{2}$	1 $\frac{1}{2}$	9	1276	
Deduct for flat arch over doors	18	5 $\frac{5}{8}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	266	
Deduct for windows at ends	4	4	$\frac{1}{2}$	5	40	
Deduct for flat arch over windows at ends ..	4	5	1 $\frac{1}{2}$	1 $\frac{1}{2}$	53	
Deduct for ventilators ..	19	4	1 $\frac{1}{2}$	4	532	
Deduct for flat arch over ventilators ..	19	5	1 $\frac{1}{2}$	1 $\frac{1}{2}$	249	
Deduct for rectangular opening in staircase passage wall ..	1	7	1 $\frac{1}{2}$	5 $\frac{1}{2}$	67	
Deduct for semi-circular space in staircase passage wall ..	1 x 7 $\frac{2}{2}$ x 7.854 x 1 $\frac{1}{2}$ x 1 $\frac{1}{2}$				50	
Deduct for circular arch work in staircase passage wall ..	1 x 8 $\frac{3}{4}$ x $\frac{3 \cdot 1416}{2}$ x 1 $\frac{1}{2}$ x 1 $\frac{1}{2}$				38	
carried over					2571	

ESTIMATE FORM. - Detail Measurements. 53 44

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward					2571	
Deduct for ventilators ..	19	4	1 1/2	2	266	
Deduct for semi-circular opening in end walls ..	2 x 52 x .7854 x 1/2				20	
Deduct for circular arch work in end walls ..	2 x 6 1/2 x 3.1416 x 1 1/2 x 1 1/2				107	
Total deduction in cft.					2964	
Total superstructure less deduction					Sq. ft. 126	
<u>Flat arch work in mortar.</u>						
Doors ..	18	5 7/8	1 1/2	1 1/2	266	
Windows ..	4	5	1 1/2	1 1/2	53	
Ventilators ..	19	5	1 1/2	1 1/2	249	
Total flat arch work in mortar					cft. 568	
<u>Circular arch work in mortar.</u>						
Circular arch in staircase opening ..	1 x 8 1/2 x 3.1416 x 1 1/2 x 1 1/2				38	
Circular arches in end walls ..	2 x 6 1/2 x 3.1416 x 1 1/2 x 1 1/2				107	
Total circular arch work					cft. 145	
<u>Outstone work.</u>						
Lintel stones over ventilators ..	19	6	1 1/2	1	100	
Steps	1	4 1/2	3 3/4	1	17	
Total outstone work					cft. 117	
<u>Cast iron columns</u>						
Columns in verandah top 3" Dr. & the bottom 4" Dr. thickness of metal (45.312) per foot run ..	23	average 3 1/2" Dr.		9	9379	
Total columns in lbs.						9379

-3-

ESTIMATE FORM.—Detail Measurements. 54 45

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Mangalore tiled roof.</u>						
Verandah ..	1	170	11		1870	
Ridge ventilators on both sides ..	2	168	5½		1848	
Staircase passage ..	1	32	5		160	
Do. Do. ..	1	6	14		84	
Total Mangalore tiled roof					Sq.ft.	<u>39</u>
<u>Re-roofing with Mangalore tiles &c.</u>						
Re-roofing the main building on both sides ..	2	169	17½		5915	
Total re-roofing					Sq.ft.	<u>591</u>
<u>Toak wood wrought and put up</u>						
Rafters in verandah ..	86	10½	8½"	5"	79.93	
EAVE board in verandah ..	1	17	1	6"	7.20	
Rafters in porch ..	8	5½	2"	4"	2.40	
Staircase rafters including overlapping ..	3	34	8½"	6"	10.68	
Purlins ..	3	6	3"	5"	1.87	
Post in staircase ..	3	9½	4"	4"	3.16	
Collar pieces ..	4	4	2"	3"	0.66	
Bressummers in staircase ..	2	9	4"	6"	3.00	
Do. Do. ..	1	6½	3"	5"	0.67	
Struts in Ridge ventilators on both sides ..	166	3"	2"	3"	20.75	
Rafters on both sides of the ridge ventilators ..	166	4½	2"	3"	31.12	
Collar piece for. Do. ..	83	5	2"	3"	17.29	
Total wood work					Sq.ft.	<u>177.80</u>

-4-
ESTIMATE FORM.—Detail Measurements. 55

Detail of Work.	Number.	MEASUREMENTS IN Feet.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>DOORS.</u>						
Teak panelled doors	18	4 $\frac{1}{2}$		9	729	
Total doors					Sq.ft.	<u>729</u>
<u>WINDOWS.</u>						
Windows	19	4		6	456	
Total windows					Sq.ft.	<u>456</u>
<u>WINDOWS.</u>						
Windows	19	4		4	304	
Total windows					Sq.ft.	<u>304</u>
<u>Ventilators</u>						
Ventilators	19	4		2	152	
Total ventilators					Sq.ft.	<u>152</u>
<u>Cement plastering, $\frac{1}{2}$" thick</u>						
Floor of class rooms	1	39 $\frac{3}{4}$	24		954	
Do. Do.	1	23 $\frac{1}{2}$	24		564	
Do. Do.	1	14	24		336	
Do. Do.	1	18 $\frac{1}{2}$	24		444	
Do. Do.	1	18 $\frac{1}{2}$	24		444	
Do. Do.	1	37	24		888	
Verandah floor	1	176	10		1760	
Drain to pass off the rain water from the roof	1	166	2		332	
Doorway sills	18	4 $\frac{1}{2}$	1 $\frac{1}{2}$		150	
Archway sill	1	7	1 $\frac{1}{2}$		12	
Platform	1	8	4		32	
Total cement plastering					Sq.ft.	<u>5916</u>

ESTIMATE FORM.—Detail Measurements. 56 47

Detail of Work.	Number	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
<u>Cornice work</u>						
Cornice all round the main building, gable walls and porches etc.	1	432			432	
Total cornice work					Sq. ft.	432
<u>Earthenware pipe 6" Dr.</u>						
Earthenware pipe to be fixed in wall to run off rain water	9	9			81	
Total pipe					Sq. ft.	81
<u>Galvanized iron gutter.</u>						
gutter Galv. iron at eaves of the main roof with necessary iron fittings etc.	1	170			170	
Do. in staircase	1	6			6	
Total galvanized iron gutter					Sq. ft.	176
<u>Teak hand railings</u>						
Teak hand railings turned in verandah all round	1	183½		2½	459	
Do. Do. in staircase	1	32		3	96	
Do. Do. Do.	1	38		3	114	
Total hand railings					Sq. ft.	669
<u>Plastering with chunam, 2 coats.</u>						
Union reading room all round inside	1	127½		16½	2102	
Professors' room all round inside, large	1	94½		16½	1564	
Do. Do. small	1	76½		16½	1257	
Staircase passage all round inside	1	64½		16½	1064	
Carried over					8987	

ESTIMATE FORM.—Detail Measurements. 57 W

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Brought forward					5987	
Honours Mathematics room all round inside ..	2	84 $\frac{5}{8}$		16 $\frac{1}{2}$	2799	
Intermediate Mathematics room all round inside ..	1	121 $\frac{1}{2}$		16 $\frac{1}{2}$	2012	
Verendah front wall including top portion. ..	1	169 $\frac{1}{2}$		16	2716	
Rear wall of the building ..	1	169 $\frac{1}{2}$		5	849	
Side walls of the building ..	2	27 $\frac{1}{2}$		16 $\frac{1}{2}$	908	
Cable of cross walls ..	14	24		8	2688	
Cable of end walls ..	2	27 $\frac{1}{2}$		9	495	
Sides of arch including soffit	1	19	1 $\frac{1}{2}$		33	
Sides and soffit of doors	18	22 $\frac{1}{2}$	1 $\frac{1}{2}$		709	
Sides, soffit and sill of windows ..	4	18	$\frac{1}{2}$		36	
Sides, soffit and sill of ventilators ..	19	13	1 $\frac{1}{2}$		432	
Total					19664	
Deduct for doors ..	18 x 2	4 $\frac{1}{2}$		9	1458	
Deduct for ventilators ..	18 x 2	4		4	576	
Deduct for rectangular portion in arch-way ..	1 x 2	7		5 $\frac{1}{2}$	77	
Deduct for semi-circular portion of the arch in staircase ..	1 x 2	12 area			24	
Total deduction					Sq. ft. 2135	
Total plastering less deduction					Sq. ft. 17529	
Varnishing, 2 coats.						
Doors ..	729 x 2 $\frac{1}{2}$ times				1823	
Windows ..	456 x 1 $\frac{1}{2}$ times				798	
Carried over					2621	

ESTIMATE FORM.—Abstract.

59

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
Estimate for constructing an upper story building over the northern wing of the Lawley Hall attached to St. Joseph's College, Trichinopoly.					
----- LOWER FLOOR. -----					
<u>Earth work</u>					
497 cft	Excavating foundation and refilling in ..	10-0	1000cft	5	
<u>Concrete.</u>					
497 "	Concrete broken stone jelly in mortar ..	20-0	100 cft	99	
<u>&Brick work.</u>					
319 "	Basement brick in mortar ..	24-0	Do.	77	
969 "	Superstructure brick in mortar ..	26-0	Do.	252	
<u>Cutstone work.</u>					
19 "	Cutstone work including dressing etc., ..	2-0	cft.	38	38
<u>Iron work.</u>					
9.10tons	Rolled steel girders ..	200-0	ton	1820	
Do.	Hoisting and setting charges ..	10-0	"	91	
16153 lb.	Ornamental cast iron columns including brackets etc. ..	0-2	lb.	2019	
24 Rft.	Iron rails for staircase supports S.I.R. ..	1-4	Rft.	30	3960
<u>Roofing.</u>					
5683 sft	Best terracing with brick on edge 3" concrete 2 courses of flat tiles and plastering with chunam at bottom ..	31-0	100 sft	1762	
7140 "	Removing the existing Mangalore tiled roofing with the roof materials etc. ..	5-0	Do.	357	2119
Carried over				6550	

Grand Total of Estimate ...

Station _____ }
191 }

60

Station _____ }
Date _____ 191 ____ }

Grand Total of Estimate ...

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
	<u>UPPER FLOOR.</u> =====				
	<u>Brick work.</u>				
12030cft	Superstructure brick in mortar	.. 27-0	100 cft	3248	
568 "	Flat arch work brick in mortar	.. 28-0	Do.	159	
145 "	Circular arch work brick in mortar	.. 29-0	Do.	42	34
	<u>Cutstone work.</u>				
117 cft	Cutstone work including dressing etc.	.. 2-0	cft	234	
	<u>Iron work.</u>				
9379 lb.	Ornamental cast iron columns	.. 0-2	lb.	1172	
1	Providing new wooden truss with iron bars as per existing one	.. 75-0	each	75	
	<u>Roofing.</u>				
3962sft	Mangalore tiled roofing with flat tiles imbedded in mortar with teak reepers and iron nails etc., complete	.. 30-0	100 sft	1189	
5915 "	Re-roofing with Mangalore tiles with new country flat tiles imbedded in mortar with teak reepers and iron nails etc. (available old materials will be used) and the roof timber will be painted with chocolate colour	.. 20-0	Do.	1183	2372
	<u>Wood work.</u>				
178.80cft	Teak wood wrought and put	.. 5-8	cft	983	
669 sft.	Teak wood turned hand railings	.. 1-0	sft	669	1652
	<u>Doors</u>				
729 sft	Teak pannelled doors with frames etc. glazed shutters at top with iron bars and iron fittings	.. 1-8	sft	1094	1094
	<u>Windows.</u>				
456 sft.	Teak windows with frames and iron bars with glazed shutters and iron fittings	.. 2-0	sft	912	
304 "	Teak windows with frames thick ribbed glass shutters with iron fittings etc.	.. 2-0	Do.	608	
	Carried over.....			1520	10048

Grand Total of Estimate ...

 Station _____ }
 Date _____ 191 ____ }

ESTIMATE FORM.—Abstract.

62 9

Quantity.	Description of Work.	Rate.	Per	Amount.	TOTAL.
1	2	3	4	5	6
	Brought forward.....			1520	10048
152 sft	Teak ventilators with frames and glazed shutters with iron fittings ..	1-0	sft.	152	16
	<u>Flooring.</u>				
5916	"Paved with cement plastering, $\frac{1}{2}$ " thick ..	10-0	100sft	592	
	<u>Finishing.</u>				
432 "	Cornice work in mortar ..	0-6	sft.	162	
529 "	Plastering with chunam, 2 coats ..	2-8	100sft	438	
3305 "	Varnishing, 2 coats ..	2-8	Do	83	
190 "	Painting with light blue, 2 coats ..	3-0	Do.	6	
1004 "	Green paint, 2 coats ..	3-0	Do.	30	
1547 "	Painting with chocolate colour, 2 coats to roof timbers ..	2-8	Do.	39	
	<u>Miscellaneous</u>				
81 Rft	Earthenware pipe 6" Dia 9' long fixing in cement etc., complete ..	1-0	Rft	81	
176 "	Galvanized iron gutter with supports and nails etc., complete ..	0-8	Do.	88	
	Providing teak staircase with necessary fittings etc., complete ..			250	
	Preparation of Plans and estimate etc. ..			70	
	Clearing site and removing rubbish etc. ..			50	539
	Contingencies ..				600
	Petty supervision ..				600
	Total Rupees				14809

M. Antony. J. J.
College Architect.

Grand Total of Estimate ... 14809

Station Trichinopoly }
Date 191 . }

ESTIMATE FORM.—Abstract.

63 54

Quantity.	Description of Work.	Rate.	Per	Amount.	Total
1	2	3	4	5	6
1	Lower Flor as per separate estimate ..				
2	Upper Flor as per separate estimate ..				
Grand total of estimate Rupees					

B. Antony. S. J.
College Architect.

Station Trichinopoly
Date 28 August 1941

W. S. S. S.
Correspondent.

Grand Total of Estimate

W. S. S. S.
In Witness Whereof