

Law (1925) Department.
Education
Ordinary SERIES.

G.O. No. 589

DATED 24-4-1925

[Despatch Abstract.]

Grant.

Building--Sri Krishna College, Chidambaram--Additional
class rooms--list of approved works--included.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.


FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

G.F. 30-41,000-8-9-24.

Law (Education) DEPARTMENT.

2
Cor 980B



Received 192 . Registered 8-4-1925.

Subject.

Grant - Building - Honours classes - Sri Minakshi

College, Chidambaram

ENCLOSURES.	
No.	2162 D of 24
Spare copies	

R.O.C. No. 2162 D of 24

Station Madras, Dated the 7-4-1925. 192

From (Name) R. G. Grieve Esquire M. A.,
(Designation) Ag. Director of Public Instruction

To The Secretary to the Government of Madras,

Law (Education) Department.

Sir.

I have the honour to submit for the approval of Government plans and estimates amounting to Rs 13015/- for the construction of additional class rooms for the location of the Honours classes to be opened in the Sri Minakshi College, Chidambaram.

The plans and estimates have been accepted by the Deputy Consulting Architect at a cost of Rs 12732 subject to the carrying out of the suggestions made in his note dated 9th March 1925 - copy enclosed - The Correspondent has accepted the suggestions made by the Deputy Consulting Architect but as regards the reduction in the provision for contingencies he has requested that no reduction may

be

pp 3-4 CF

CW.

2
be made as the condition under which the work is to be carried on are the same as those of other works for which a provision of 15 per cent was allowed for contingencies.

I have the honour to recommend that Government will be pleased to include the scheme in the list of approved works at a cost of Rs 12732 only as advised by the Deputy Consulting Architect.

I have the honour to be,

Sir,

Your most obedient Servant

for Director of Public Instruction.

G.M.7.4.25

3
Office of the Deputy Consulting Architect to Government, Chepauk
Dated 6th/9th March 25

To, D.P.I.

From, Dy.C.A.

The plans and estimates have been examined with the following remarks:-

1. The rates are fair.

2. The lump sum amount of 15 per cent for contingencies, petty supervision, architect's fees and establishment for accounts and audit, was allowed by Government in the case of the several works carried out by Sir Annamalai Chettiar, but this should be reduced by $2\frac{1}{2}$ per cent in view of the fact that the amount for contingencies has since been reduced by Government (P.W.D.) to $2\frac{1}{2}$ per cent from 5 per cent a deduction of Rs 283-0-0.

3. The plans and estimate may be returned recommended for sanction subject to the carrying out of the following points during execution.

(a) Though doors and windows are proposed of teak, it is not advisable to keep them directly fixed to "brick in mud" masonry. As such the usual course 1 ft. deep round the doors and windows in brick in lime mortar should be allowed, as this will ensure a stronger bond of the frames in masonry and resist the impact of rough handling of shutters in closing as well as prevent white ant destruction.

(b) The wood work of roof is proposed to be of country wood. The sections are satisfactory for classes I and III. All sections have been treated as partly fixed and necessary precaution should be taken in execution to ensure this as ~~12-2-23~~. ~~fish plates~~ ~~for~~ explained in C.E.'s Circular Memo No. 1358-C dated 19-2-23. Fish plates for ridge, purlin and bressummers should in consequence be provided.

(c) Trusses. The following change of scantlings is recommended.

	Estimate	As proposed.
Principal rafter	3" x 6"	4" x 5"
Tie beam	3" x 6"	4" x 5"
Strut	3" x 3"	4" x 4"

(d) The provision for iron tie rods 1" diameter at 8 lbs. per truss should be 18 lbs. per truss. This appears to be typist's error.

4
(e) The roof timbers should be spaced at a maximum of 1'-8" centres instead of 2 ft. as ^{proposed} ~~proposed~~ as the 2" x 1/2" teak reepers 6" apart would not be suitable with the wider spacing. In section the front rafter is of the same length as the rear one but the estimate provides 12 ft. and 14 ft. respectively. It is suggested that the length 12 ft. only provided for the front main room rafter will admit rain water splashing into the rooms through the ventilators.

(Sd) H.E. Tasker Taylor
Deputy Consulting Architect
to Government.

(true copy)

W. C. Smith
for Director of Public Instruction

LAW (EDUCATION) DEPARTMENT. 4

Grant.

Building - Sri Minakshi college, Chidambaram - Addl. class rooms - List of approved works - Included.

Read the following papers.

[C. 980 B]



Law Department R:- No. 589 dated 14-4-25

(E) The Government sanction the inclusion, in the list of approved works maintained in pursuance of G.O. No. 572 Law (Education), dated 10th May 1922, ~~746 Law (Education) dated 17th June 1922~~ of the construction of additional class rooms for the location of the Honours classes to be opened in the Sri Minakshi ^(College) Chidambaram at an estimated cost of Rs. 12,732. While this approval does not convey any guarantee of grant, it will render the work eligible for a grant under the provisions of the ~~Code of Regulations for European~~ Grant-in-Aid Code if and when funds become available, provided that all the conditions prescribed in the code are duly complied with.

M2

8/4/25
CW
8/4/25

15/4/25
A

17.4
VTR

To the Director of Public Instruction
(with reference to his letter No. 2162 D/24 dated 7-4-25
(with plans to ref.))
To the Accountant-General.



unclassified information -

unclassified information -

[Group 5]

(E)

Additional clearance
for the location of the
to be opened in the
12.12.12

12/12/12
12/12/12
12/12/12

12/12/12
12/12/12
12/12/12



When given for copying
When copied
When examined
When signed

192

READ AGAIN G.O. No.
192

DATED

CURRENT No.

ENCLOSURES TO C. No.

ORDER OF GOVERNMENT

A A A A A A A

LETTER OF GOVERNMENT

STATEMENT WITH DITO.

PAPERS NOT FILED OF, BEING MEANT FOR DESPATCH
IN ORIGINAL.

N.B.—
A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only.