

Educational (1900) Department.

ORDINARY MS.

G.O., No. 503

DATED 13. 10. 00

INDEXED.

[Despatch Abstract.]

Approving + transferring to the P. W. D.
an estimate for Rs 1,930 for the construction
of a building for the host girls' school,
Paleole, Godamari district.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.


FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

1900 2
Educational (189) Department.

CURRENT No. 1347

76² 238²
77 98



From
The Director of Public
Instruction,
Madras.

Order

No. 9666

Dated 28 September 1900

Received

Registered 2. 10. 00

Enclosures 3

Spare copies

SUBJECT.

Regarding that the alter-
native estimate for the
construction of a building
for the Govt. girls' school,
Palace, be sanctioned

W 10/10

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

ESTIMATE FORM.—Detail Measurements.

Detail of Work.	Number.	MEASUREMENTS IN FEET.			Area or Contents.	Total Quantity of each description of work.
		Length.	Breadth.	Depth.		
1	2	3	4	5	6	7
Earth work for compound wall. Mud compound wall all round with 2 feet foundations	1	32.0 327 0	2.6	6.0	4800 4905	178 or 182 cyds
Tiled coping over mud compound wall Coping with big bamboos and pan tiles &c. complete	1	32.0 327	4.0			
Total Rft.						320 327 Rft.
Gate for compound wall	1	8.0				No. 1

ESTIMATE FORM.—Detail Measurements.

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount	TOTAL.
1	2	3	4	5	6
		RS.		RS.	RS.
178 + 52 cyds	Mud compound wall	0.4-0	cyd	45	
320 + 27 Rft	Coping with big & small bamboos and painted &c. complete	28 1/4-0	1000 ft.	44	
N.O. 1	Gate for compound wall 8' long			18	
				148	
	Petty supervision	3-0-0	cent	5	
	Contingencies			8	
					160

Division
Supy. Engineer
1st Circle
4/5/00.

Director of Public Instruction

Grand Total of Estimate *Rs 160* ✓

STATION _____
Date _____ 189 _____


 Marshall
 Executive Engineer.
 G. W. Orr

(E. No. 123.)

50,000-11 10-98.

CIRCLE—*First*

DIVISION—*Western*

DISTRICT—*Godavari*



TALUK (OR ESTATE IN CASE OF ESTATE WORKS).

ESTIMATE FORM.—Abstract.

Financial Head—*Provincial*

Service Budget Head—*Civil buildings*

Departmental Head—*Original works*

Main Head—*10 Educational*

Sub-Head—*2 Govt. Schools*

Project of which
the work forms part—

Section—

Name of Work—*Constructing compound
wall for Government Girls School
at Palacole*

Amount of Estimate, Rs. *160*

To be carried out by—*P.W.D.*

REFERENCES.

ESTIMATE FORM.—ABSTRACT—GENERAL (FOR MANY PARTS OF A WORK).

Description of Work.	RATES.		Girls' School Building		Compound Wall														TOTAL.	
	Unit.	Amount.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.	Quantity.	Cost.
		RS.		RS.		RS.		RS.		RS.		RS.		RS.		RS.		RS.		RS.
Excavating foundations 1000 cft	3-0-0		4	12	"	"	"	"	"	"	"	"	"	"	"	"	"	"	4	12
Sand filling base 100 cft	2-8-0		32	80	"	"	"	"	"	"	"	"	"	"	"	"	"	"	32	80
Burnt country brick in mud	do	15-12-0	42-6	702	"	"	"	"	"	"	"	"	"	"	"	"	"	"	42-6	702
Raw brick in mud	do	9-4-0	32	296	"	"	"	"	"	"	"	"	"	"	"	"	"	"	32	296
Flooring with burnt brick in mud 100 sft	5-10-0		16	90	"	"	"	"	"	"	"	"	"	"	"	"	"	"	16	90
*Chunam plastered on top	do	2-8-0	23	58	"	"	"	"	"	"	"	"	"	"	"	"	"	"	23	58
Plastering with chunam	do	1-0-0	16-5	17	"	"	"	"	"	"	"	"	"	"	"	"	"	"	16-5	17
Mud plastering	do	4-14-0	34	171	"	"	"	"	"	"	"	"	"	"	"	"	"	"	34	171
Roofing thatched	do	0-11-0	18	18	"	"	"	"	"	"	"	"	"	"	"	"	"	"	18	18
Cut stone under posts	cft	2-8-0	204	510	"	"	"	"	"	"	"	"	"	"	"	"	"	"	204	510
Country wood wrought and put up	cft	2-8-0	202	505	"	"	"	"	"	"	"	"	"	"	"	"	"	"	202	505
Country wood doors & windows battens	sft	0-8-0	322	161	"	"	"	"	"	"	"	"	"	"	"	"	"	"	322	161
Gravel	100 cft	6-9-0	11	72	"	"	"	"	"	"	"	"	"	"	"	"	"	"	11	72
Scaffolding	-	-		20	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	20
Mud compound wall cyd	0-4-0		"	"	178	45	"	"	"	"	"	"	"	"	"	"	"	"	178	45
Coping with big & small					320	92													320	92
bamboo & pantiles 100 cft	2-8-14-0		"	"	327	94	"	"	"	"	"	"	"	"	"	"	"	"	327	94
complete																				
Gate 8' long	"	"	"	"	11	8	"	"	"	"	"	"	"	"	"	"	"	"	11	8
Petty supervision	"	"	"	66	"	4	"	"	"	"	"	"	"	"	"	"	"	"	70	116
Contingencies	"	"	"	108	"	8	"	"	"	"	"	"	"	"	"	"	"	"	114	114
Total				2380		160													2440	2540

STATION _____
Dated _____ 189 . }

NOTE.—(1) All rates are to be given in Rupees, Annas and Pies.
(2) Quantities are to be entered as so many units; thus the unit for of Brick-work would be entered as 92-5 units.

Brick-work being 100 cubic feet, 9,250 cubic feet

45701
Raoja
Subg. Engineer, P. S. D. S. D.

Executive Engineer.
G. W. S. M.
5-4-00

To be employed where there are many parts
or sub-divisions of a work.



10,000-10-1-96.

(E. No. 125.)

CIRCLE.— *First*
DIVISION.— *Western*
TALUK.— *Narasapur*
DISTRICT.— *Godavari*



ESTIMATE FORM.—ABSTRACT—GENERAL (FOR
MANY PARTS OF A WORK.)

Fund
Financial Head— *Provincial*

Service
Budget Head— *Civil buildings*

Departmental Head— *Original works*

Main Head— *10 Educational*

Sub-Head— *2 Govt schools*

Project of which
the work forms part—

Section—

Name of Work— *Constructing Govern-
ment girls' school building
with compound wall at
Palacole*

Amount of Estimate— *2480*
2,540

To be carried out by— *P.W.D.*

REFERENCES.

1347
CURRENT NO. OFFICE OF THE DIRECTOR OF
PUBLIC INSTRUCTION, 6
Madras, *28* September 1900.
No. *9666*

From

THE HON'BLE MR. G. H. STUART, M.A., Barrister-at-Law,

DIRECTOR OF PUBLIC INSTRUCTION,

Madras,

To

THE SECRETARY TO GOVERNMENT,

Educational DEPARTMENT,

Fort St. George.

SIR,

In returning herewith the plan and estimates for
the construction of a building for the Government girls' school,
Palcole, Godavari District, received with memorandum No 2959 C,
Public Works, dated 14th July 1900, I have the honour to request
that the alternative estimate for Rs. 1930 may be sanctioned and
transferred to the Public Works Department.

I have the honour to be,

Sir,

Your most obedient servant,

G. H. Stuart

Director of Public Instruction.

EDUCATIONAL DEPARTMENT.

Papers to be read in Proceedings:—

Again G.O., No. , dated 190 .
Again G.O., No. , dated 190 .
Current No. 1347 of 190 , dated 28th September, from the D.P. I.
" " " 190 , " : "
" " " 190 , " : "

resp 13/10/00

ORDER. *his* No 503 d/13.10.00

The estimate for
Rs 1930 is approved, and
will be transferred to
the P. W. D.

7A
5-10-00
PW
5110/00
MA
10/10
8.10.00

To The D.P.I. 940
-- P.W.D.-ado
with plan & estimates
(Keep back the other estimate for P.W.D.)
d/15/10
Despatcher
Please show me before despatch
Sharon 18/10

When given for copying _____
 When copied _____
 When examined _____
 When signed _____

190 .

READ AGAIN G.O., No. _____, DATED
 190 .

CURRENT No.

ENCLOSURES TO C. No.

ORDER OF GOVERNMENT A A A A A A A

LETTER OF GOVERNMENT.

STATEMENT WITH DITO.

PAPERS NOT FILLED UP, BEING MEANT FOR DESPATCH
 IN ORIGINAL.

N.B.—

- A = Copy in full.
- B = Not to be copied.
- P = Copy abstract only.
- Q = Copy heading only.