M.R.O. 1—77,006—8-6-31.

(1) Number of pages 1-10

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Finance DEPARTMENT.

G.O. No. 212 Press / Mis.

92-93.

Dated 12-2-1873.

7/8

92-93

Not to be folded or roughly handled

No. 92. Read the following Proceedings of the Board of Revenue, dated 8th February 1873, No. 810 (Miscellaneous):—

Read the following letter from the President of the Local Fund Board, Coimbatore, to the Chief Secretary to Government, Fort St. George, through the Board of Revenue, dated Dimbum, 23rd January 1873, No. 1:—

The Local Board having, at a meeting held on the 15th instant, duly approved of a plan and estimate for reconstructing the Noyel Bridge at a cost of Rupees 6,230, which the District Engineer has reported he could not further reduce, I have the honour to forward these papers for the sanction of Government, through the Board of Revenue, with reference to my letter, No. 10, of 30th November 1872.

One plan.
One estimate.

2. The Government contribution due under G. O., No. 1513, of 13th November 1872, Financial Department, is Rupees 3,115, being half of the cost.

The estimate for restoring the Noyel Bridge, at a cost of Rupees 6,230, will be submitted for the sanction of Government.

2. In G. O., 13th November 1872, No. 1513, Financial Department, Government promised to give half the cost of the bridge, and in G. O., 30th December 1872, No. 1732, placed Rupees 3,000 at the disposal of the Local Fund Board. It remains for them to give Rupees 115 more. The whole should be placed at the disposal of the Public Works Department.

(True Copy and Extract.)

(Signed) J. GROSE,
Secretary.

No. 93. ORDER THEREON, 12th February 1873, No. 212.

Sanctioned.

2. The Accountant-General will arrange for transferring Rupees 3,115 from Provincial to the credit of the Coimbatore Local Fund Board.

(True Extract.)

W. HUDLESTON,
Chief Secretary.

To the Board of Revenue, with plan and estimate returned.
,, Public Works Department.
,, Accountant-General.

Exd. J. Wright.

Govt. of {1873} Madras

FINANCIAL.

To

THE BOARD OF REVENUE,

&c.,

&c.,

Dated February, 12th.

Read.

G.O, 12th February 1873, No. 212.

FEBRUARY.

Nos. 92-93.

Sanctioning the estimate for restoring the Noyel Bridge, and directing the Accountant-General to transfer the Government contribution of Rupees 3,115 from Provincial to the credit of the Coimbatore Local Fund Board.

MISCELLANEOUS No. 810. REVENUE DEPARTMENT.

3

PROCEEDINGS OF THE BOARD OF REVENUE.

Dated 8th February —— 1873.

Read the following

№ 1

From

A. Wedderburn Esqre,
President of the Local Fund Board
Coimbatore

To

The Chief Secretary to Government, Madras
through the Board of Revenue.

Sir,

Enclosures 2.
Plan — 1
Estimate — 1
2

The Local Board having at a Meeting held on the 15th Instant, duly approved of a plan and Estimate for reconstructing the Noyel Bridge at a cost of Rs 6230 which the District Engineer has reported he could not further reduce, I have the honor to forward these papers for the sanction of Government through the Board of Revenue, with reference to my letter № 10 of 30th November 1872.

2. The Government contribution due under G. O. № 1513 of 13th November 1872, Financial Department is Rs 3115 being one half of the cost.

Coimbatore Local Fund
Board's Office, Camp Dimbum
23d January 1873 ——

I have &c.
(Signed) A. Wedderburn
President

The

The estimate for restoring the Royal Bridge at a cost of Rs 6230 will be submitted for the sanction of Government.

In Government Order 13th November 1872 No 1513 Financial Department, Government promised to give half the cost of the bridge and, in Government Order of 30th December 1872 No 1732 placed Rs 3000 at the disposal of the Local Fund Board. It remains for them to give Rs 115 more. The whole should be placed at the disposal of the Public Works Department.

(True Copy & Extract)

J Gale
Secretary

To,
The Chief Secretary to Government
Financial Department
with 2 Enclosures

2296/21-11-73 Recd by post 3-12-73

54

Supplemental Estimate No 64 of 1873-74

6 District - Coimbatore Taluk - Coimbatore

No 1. Restoring the Royal Bridge at Coimbatore

Particulars	No.	Measurement in feet L	B	D	Contents
Tarwashing to woods of Royal Bridge					
Tie Beams	2	42	40	✓	3360
——— do	2	42	36	✓	3024
——— do	2	42	32	✓	2688
Tie Beams	6	13½	32	✓	2544
Principal Rafters	12	14	32	✓	5376
Queen Rods	18	6½	32	✓	3744
——— do	12	3½	32	✓	1344
Diagonals	24	8	22	✓	4224
——— do	12	6	22	✓	1584
Joists	12	25	18	✓	5400
——— do	38	18	18	✓	12312
Struts	12	6½	20	✓	1560
Pieces for struts	12	1½	17	✓	306
Planks above		125	212	✓	26500
——— do ——— below		108	212	✓	22896
Ballast board	2	129	14	✓	3612
Rails	2	127	10		2540
Posts for hand rails	20	4½	14	✓	1260
——— do ——— Short	12	25	3	10	✓ 1650
Diagonals	24	4½	10	✓	1020
Bearing blocks	4	3	44	✓	528
——— do ——— do	4	3	40	✓	480
——— do ——— do	4	3	36	✓	432
Total Cubical Contents					108414
Total Cubs of Tarwashing	8				or ✓ 9014

Copy Ramaswamy

Rail wood extra required for the Beams &c

Pedge Pier

Description of work	Number	Length	Breadth	Depth	Amount
Granite Stones Headers 1×9×9	No				11
do do Stretchers 1½×9×9	No				34
Total Stones dressed, delivered and fitted in the Building					45
Men Carlies for Cutting Pier & bailing out water	No				40
Women Carlies for Chunam work	No				13
Chunam Surah	No				12
Cart for Conveying the Same	No				1
Brick Layers	No				8
Earth work Removed that was put between Piers & abutments		20	4	2	160
		20	3	2	120
		12	3	3	108
		12	3	1	36
		8	6	1	48
		16	3	2½	112½
		15	3	2	90
					674½
Deduct					4½
Total Cyds of Earth work					670

Widening Bank

South west bank as far as Causeway	164	20	3	9840
North west do	36	30	2	2160
South East bank	150	15	2	3000
North East bank	100	12	2½	2460
				17460
Total Cyds of Earth work				646⅔
Retaining wall in chunam cast.	51	3	3	459
Bund chunam pointed apron.	40	30	1½	1800
Total removing Causeway	60	10	1	600
				2859 or 105⅔
Iron straps with bolts & nuts &c No				12
Carpenters No				2

Trimbatore
12th Novr 68/73

John Johnston
Asst Engr

M. N. Adam Madras
Asst Engr Overseeing Works

Checked MS

Extra Wood required for the Beams

Description of work | Number | Length | Breadth | Depth | Amount

Granite Stones Headers 1×9×9 No 11
do do Stretchers 1½×9×9 No 34
Total Stones dressed, delivered and fitted in the Building 45
Men Carlies for Cutting Pier & bailing out water No 40
Women Carlies for Chunam work No 13
Chunam Surah No 12
Cart for Conveying the Same No 1
Brick Layers No 8
Earth work Removed that was put between Piers & abutments 670
Deduct Total Cyds of Earth work 4½ 670
Retaining wall in chunam cast. 459
Bund chunam pointed apron. 1800
Total removing Causeway 600
Iron straps with bolts & nuts &c No 12 105⅔
Carpenters No 2

Abutments

Description of work | Number | Length | Breadth | Depth | Amount

Granite Stones Headers 1×9×9 No 11
do do Stretchers 1½×9×9 No 34
Total Stones dressed, delivered and fitted in the Building 45
Men Carlies for Cutting Pier & bailing out water No 40
Women Carlies for Chunam work No 13
Cart for Conveying the Same No 1
Brick Layers No 8
Earth work Removed (1/2 Cyds) 670
do do 140
Iron straps with bolts nuts &c 12
Carpenters 2
Retaining Causeway 105⅔

Abutments

Description of work | Number | Length | Breadth | Depth | Amount

Granite Stones Headers 1×9×9 No 225
do do Stretchers 1½×9×9 No 32
Total Stones dressed, delivered and fitted in the Building 257

No. 64.

Coimbatore Taluk R

Supplemental Estimate for Restoring the Royal Bridge at Coimbatore

Rs 584 - - -

In a letter from the President of the Local Fund Board, Coimbatore, to the Secretary to the Board of Revenue, Madras No. 5 of 31st January 1874.

G.O. 12th Feby/74 No. 92-93

Enclosure 1.

In G.O. No. 549/74

Supplemental Estimate for restoring the Royal Bridge at Coimbatore ——

Filed 7/7/74

Pm: 13th November 1872. No 36
" —30 December 1872. — 210-211.

Financial 1873 Sept.

PROCEEDINGS OF THE BOARD
OF REVENUE.

No 264

Dated 8th February — 1873.
Despatched 8th — " —
Recd 10th — "
en 2.
Mis: No 810.

SUBJECT.

Submitting for sanction of Govt letter from President L. F. Bd Coimbatore, forwarding plan & Estimate for restoring Noyil Bridge at Coimbatore —
With an Order

12 February 1873 No 212

Read Finance
Re despatch with answer per
Tuesday. D. 3/15. Proc. Financial Dept
Public Works Commerce Revenue Agriculture
To the Board of Revenue, with the usual
Public Trade Return —
Finance —

C 10/2/73
12-11

Govt. of {1873} Madras.

Financial

To
The Board of Revenue.
per

Dated Febᵏ 12.
Recd. [illegible]

G. O. 12 Febᵏ 1873, No. 212.

Nos. 92. 93.

Sanctioning the Estᵉ for restoring the North Bridge & directing the Accᵗ Genˡ to transfer the Govt. contribution of Rs. 3115 ~~be transferred~~ from Prov.ˡ to the credit of the Coimbatore L. F. Bᵈ