M.R.O. 1—77,000—3-6-37.

(1) Number of pages 20

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Financial DEPARTMENT.

G.O. No. 7 Press Mis.

12-14.

Dated 4-1- 1876.

Not to be folded or roughly handled

Municipal—Medical.

No. 13. Read the following letter from H. S. THOMAS, Esq., President of the Municipal Commission, Negapatam, to the Hon. W. HUDLESTON, Chief Secretary to Government, Fort St. George, dated Vallam, 20th December 1875, No. 298:—

I have the honor to forward a copy of a letter from the Vice-President of the Negapatam Municipality, requesting me to obtain the sanction of Government for laying out a portion, namely, Rupees 326-12-0 (*vide* copies of estimates and resolution enclosed), of the funded capital of the Negapatam Dispensary for providing the Hospital Assistant attached thereto with a dwelling-house.

2. As the Hospital Assistant is entitled to free quarters, it is necessary that he should be provided by the Municipality with a residence, which, if not in the dispensary, should be conveniently near it.

3. The building which had been the Apothecary's quarters before a Surgeon assumed charge has since been converted into a dispensing room. The Commissioners have, therefore, resolved to convert the coach-house into the Dresser's quarters. The lying-in ward, a detached building, has now been temporarily assigned to the Hospital Assistant for his residence.

4. The funded capital of the dispensary originally consisted of Rupees 7,000 in Government four per cent. paper, of which a portion (Rupees 2,000) was expended when the Apothecary's quarters were built. In addition to this there is a sum of Rupees 1,266-1-10 contributed by the Local Fund Board towards the above expenditure.

5. Copies of the estimates for the above work are herewith submitted.

No. 14. ORDER THEREON, 4th January 1876, No. 7.

The proposal is sanctioned.

(True Extract.)

W. HUDLESTON,
Chief Secretary.

To the President of the Municipal Commission, Negapatam.
,, Public Works Department.
,, Surgeon-General, Indian Medical Department.
,, Accountant-General.

Exd. J. W. Fischer.

Govt. of Madras

FINANCIAL.

To

The PRESIDENT of the
MUNICIPAL COMMISSION,
Negapatam

&c., &c.,

Dated January, 4th.

Issued

Recd.

Encl.

G.O., 4th January 1876, No. 7.

JANUARY.
Nos. 13-14.

Municipal—Medical.—The proposal to lay out a portion of the funded capital of the Negapatam Dispensary in building a house for the Hospital Assistant attached thereto, sanctioned.

Municipal Commrs Office
No. 75 Negapatam 15th July 1875

From

The Vice President
Municipal Commission
Negapatam

To

The President
Municipal Commission
Negapatam

Sir,

Owing to the building intended for the Warrant Officers' residence attached to the Civil Dispensary being diverted into a Consulting & dispensing room, the Commissioners resolved to convert the Coach-house into the Dressers Quarters. The Estimate & Plan were laid before the Local Fund Board of this Circle; but they refused to make a grant in aid for this object.

The amount of the Estimate is Rs 326-12-0, & I have the honor to request you will kindly obtain

obtain the sanction of Government to this sum being Expended out of the funded Capital of the Civil Dispensary.

I have the honor to be
Sir
Your most. obt. Servant
(Signed) Frank Oliver
Vice President.

(True Copy)

W. Thomas
President.

Encl. No. 1
to a letter
from
The President Municipal Commrs
Negapatam
to
The Chief Secretary
to Govt
Fort St George
Dated 20th Decr 1875
No. 298.

Extracts from the Proceedings of the Municipal Commissioners Dated 21st January 1875.

"Plan and Estimate for Dresser's quarters at Dispensary".

"Sanctioned estimate amounting to Rupees 290. The work to be put in hand at an early date".

Dated 8th July 1875.

"Read revised Estimate for Dresser's quarters at Dispensary."

"Passed Rupees 36-12-0 additional making the amount Rupees 326-12-0".

/True Extracts/
Negapatam
Mun. Comm. Office
3rd December 1875
/Signed/ Frank Oliver
Vice President

True

59

(True Copy)

Compd [illegible]

[illegible] Thomas.
President.

Encl. No. 2.

To a Letter
From
The President
Municipal Commr.
Negapatam
No. 298.

Copy of Estimate for the repairs of the Rest House attached to the Municipal Chairman's Office at Negapatam, forwarded with letter No. 298 dated 29th March 1875.

Estimate No. 9/1875
Tanjore District
Negapatam Taluq

Detailed Estimate for Converting the stables attached to Tehsildary at Negapatam into Quarters for a Dresser.

Particulars of Work	measurement No.	L	B	H	Contents
To Remove present interior wall	1	7	3/4	6	31 1/2
do do do Doors large	2	3	3/4	5	22 1/2
do do do do small	1	2 1/2	3/4	4	7 1/2
do do do rear window	1	2 1/2	3/4	3	5 5/8
Total removing present wall C. ft. (brick in Chunam)					67 1/8
Foundations & Basement to side walls	4	6 3/4	2	2 1/2	135
do do front walls	2	6 1/4	2	2 1/2	62 1/2
do do front & rear walls of visiting room	2	8 1/2	2	2 1/2	85
do do do Side walls do	2	16 1/4	2	2 1/2	162 1/2
Total foundation & basement C. ft. (brick in Chunam)					445
Side walls	4	7 1/2	1 1/4	6	225
Front do	2	7	1 1/4	8	140
do of hall	1	9	1 1/4	9 1/2	106 7/8
Side walls of visiting room	2	15	1 1/4	6	225
Front do do	1	11 1/2	1 1/4	7 1/4	104 7/32
Above Crosswalls inside	4	7 1/2	3/4	2	45
Total					846 (illegible)
Deduct for doors large	1	3	1 1/4	6	22 1/2
do do do small	1	3	1 1/4	5	18 3/4
do do do do	1	2 1/2	1 1/4	4	12 1/2
do Windows large	2	3	1 1/4	4	30

Deduct for windows small		2	2½ 1½ 3	18¾
do — do — do		1	2 1½ 2½	6¼
Total deductions				108¾
Total superstructure C.ft. (brick in mud)				737¼
Whitewashing interior side walls		2	17½ - 8½	297½
do — do — rear wall		1	9 - 11½	103½
do — do — front do		1	9 - 9½	85½
do — do — to bed room		1	55 - 7½	412½
do — do — Store & Cook rooms		2	32 - 7	448
do — do — front & rear walls of visiting room		2	9 - 7½	135
do — do — side walls — do		2	15 - 6	180
do — outside rear wall		1	30 - 9¼	277½
do — do — front wall		1	30 - 7	210
do — remaining side walls		1	70½ - 6	423
Total whitewashing Sq.ft.				2573
Gravel flooring to visiting room		1	14½ 8½ -	123¼
do — " — Hall		1	17 8½ -	144½
do — " — Bed room		1	17 8 -	136
do — " — Cook room		1	8¼ 8 -	66
do — " — Store room		1	8 7½ -	60
Total Gravel flooring Sq.ft.				529¾
Rough pointing to sidewalls		4x2	7½ - 6	360
do — " — front walls		2x2	7 - 6	168
do — " — front wall to hall		1x2	9 - 7½	135
do — " do — visiting room		1x2	10 - 7½	150
do — " — side walls — do —		2x2	15½ - 6	372
do — " — above sidewalls of hall		4x2	7½ - 2	120

Total				1305
Deduct for doors large		1	3 - 6	18
do — do — small		1	3 - 5	15
do — do — do		1	2½ - 4	10
do — windows large		2	3 - 4	24
do — do — small		2	(viz) 2½ - 3	21
do — do — do		1	2 - 2½	5
Total deductions				93
Total Rough pointing Sq.ft.				1212
Roofing to visiting room		1	17¼ 15 -	258¾
Total roofing Sq.ft.				258¾
Batten doors 3×5		2	- -	
do — do — 2½×4		1		
do — do — for front room		1		
Windows batten 3×4 with teak wood bars		2		
do — do — 2½×3 — do — do		2		
do — do — 2×2½ — do — do		1		
do — do — 2½×3 with iron bars		1		
Compound wall		1	72½ 1 5	362½
Total C. ft. (in mud)				362½
Total running feet of Coping on Compound wall		75		75
Honey comb tilework in front gable		1	13½ - 1½	20¼
do — do — between Cook & store room		1	7½ - 1¾	13⅛
do — do — Side walls of hall		4	8 - 1½	48
Total honey comb tilework Sq.ft.				81⅜

16th January 1875

(Signed) W. Leggat R.E.C.E.
Executive Engineer
4th Range
Mysapalaiam
True

(True Copy)

Negapatam
Municipal Commissioner's Office
3rd December 1875

(Signed) Frank Oliver
Vice President

(True Copy)

A. Thomas.
President.

Exam. JK

Encl. to No. 3.
of a letter
from
The President
Municipal Comm.
Negapatam
to
The Chief Secretary
to Government
Madras

Dated 20th Dec. 1875
No. 298.

Copy of a detailed Estimate for Converting the stables attached to the Civil Dispensary at Negapatam into Quarters for a Dresser

Copy of a detailed Estimate for Converting the Stables attached to the Civil Dispensary at Negapatam into Quarters for a Dresser. 119

Description of Work	Rate	Amount
	Rent	Rent
Sq. ft. removing present wall (brick in Chunam)	. . 3	1 . 9
Do. of (brick in Chunam)	. 2 6	69 8 6
Do. of (brick in mud)	. 2 .	92 2 6
Squares of white washing	. 4 .	6 7 .
Do. of gravel flooring	. 8 .	2 10 3
Do. of rough pointing in Chunam	. 12 .	9 3 .
Do. of roofing with Palmyrah Couples, Collar pins, reepers, Nails and pantiles &c Complete	18 . .	46 9 11
Pattan doors 3 x 5 at a. a. on plan	10 . .	20 . .
Do. Do. 2½ x 4 at b Do.	7 . .	7 . .
Do. Do. 3 x 6 for front-room	12 . .	12 . .
Windows batten 3 x 4 with teak wood bars.	5 . .	10 . .
Do. Do. 2½ x 3 Do. Do.	4 . .	8 . .
Do. Do. 2 x 2½ Do. Do.	3 . .	3 . .
Do. Do. 2½ x 3 with iron bars.	5 . .	5 . .
Sq. ft. Compound wall in mud 5 feet high	. . 9	16 15 9
Rt. ft. of tile Coping on Compound Wall	. 1 .	4 11 .
Square of Hondy Comb tile work	5 . .	4 1 .
Excavating foundations and Sundries and a bamboo mat door for Compound wall	. . .	8 6 4
Total Rupees.		326 12 .
Deduct amount previously sanctioned		290 . .
Now Sanctioned		36 12 0

Negapatam
1875

Passed
(Sign) F. Oliver
Vice President

(True Copy)

A. Thomas.
President

Compd JK

Abstract Estimate
Sanyasi District
Negapatam Taluq

Work. Estimate for Converting the stables attached to the Dispensary at Negapatam into Quarters for a Dresser.

Quantity	Description of Work	Rate	Amount	Total
67 1/8	C. ft. of removing present wall (brick in chunam)	"	3	1 9
445	Do of (brick in chunam)	"	2	5 5 10
737 1/4	Do of (brick in mud)	"	1	9 8 0 10 2
25 3/4	Square of whitewashing	"	4	" 6 7 "
529 3/4	Do of gravel flooring	"	8	" 2 10 3
13 1/4	Do of rough pointing in chunam	"	12	" 9 3 "
258 3/4	Do of roofing with palmyra couples Collar pieces, rupens, nails & pan tiles complete	"	18	" 46 9 11
2	Batten doors 3'x5' at a-a in plan	"	10	" " 20 " "
1	Do Do 2½x4 at b in plan	"	7	" " 7 " "
1	Do Do 3x6 for front room	"	12	" " 12 " "
2	Windows batten 3x4 with teak wood bars	"	5	" " 10 " "
2	Do Do 2½x3 Do Do	"	4	" " 8 " "
1	Do Do 2x2½ Do Do	"	3	" " 3 " "
1	Do Do 2½x3 with iron bars	"	5	" " 5 " "
362 1/2	C. ft. Compound wall in mud 5 ft high	"	3	5 10 7
75	R. ft of tile coping on Compound wall	"	1	" 4 11 "
81 3/9	Squares of Honey Comb tile work	"	5	" " 41 "
	Excavating foundations & Sundries & bamboo mat door for Compound wall	"	"	8 6 4
	Total Estimate Rs.			290 " "

16th January 1875.

(Signed) W. Leggatt A.M.I.C.E
Executive Engineer & Collr
Rance
Negapatam
(True)

Exd. Rs. 5

To a Estt.
From
The Executive
Municipal Comr &
Negapatam

2

The Chief Engr &
Secretary to Govt
Madras

Dated 2nd Octr 1875

No. 292

Copy of a signed
Estimate for Converting
the stable attached to
the Civil Dispensary at
Negapatam into Quarters
for a Dresser

Rs. 290

Rs. 290/-

Rs. 290/-

Negapatam
Municipal Commission
3rd Dec. 1875

/ Spare Copy /

/ Signed / Frank Olive
Vice President

6

(Spare Copy)

F. Thomas.
President

Compd H

Recd 20th Dec. 1875

Copy of an abstract Estimate for Construction of Dhobi attached to the Civil Dispensary at Negapatam with Quarters for a Peon.

R. Fuller 29/6/75

Encl. to No. 4
a Letter
from
The President
Municipal Commission
Negapatam
to
The Chief Secretary
to Government
Madras
Dated 20th Dec. 1875
No. 298.

No. 298

Presidency Office
Vellam, 20th Dec. 1875
Dispt 21st. — —

From

F. S. Thomas Esquire
President
Municipal Commission
Negapatam

To

The Honorable W. Hudleston
Chief Secretary
to Government
Madras

Sir,

I have the honor to forward a Copy of a letter from the Vice President of the Negapatam Municipality, requesting me to obtain the sanction of Government for laying out a portion, namely Rs 326-12-0 (Vide Copies of Estimates & resolution Enclosed), of the funded Capital of the Negapatam Dispensary, for providing the Hospital Assistant attached thereto with a dwelling-house.

2. As the Hospital Assistant

is

is entitled to free quarters, it is necessary that he should be provided by the municipality with a residence, which, if not in the dispensary, should be conveniently near it.

3. The building, which had been the apothecary's quarters before a surgeon assumed charge, has since been converted into a dispensing room. The Commissioners have therefore resolved to convert the Coach-house into the Dresser's Quarters. The Assistant-in-ward, a detached building, has now been temporarily assigned to the Hospital assistant for his residence.

4. The funded capital of the dispensary originally Consisted of Rs 7000 in Government 4 per cent paper, of which a portion (Rs 2000) was Expended when the Apothecary's quarters were built. In addition to this there is a sum of Rs 1266-1-10 Contributed by the Local Fund Board towards the above

above Expenditure.

5. Copies of the Estimates for the above work are herewith submitted.

I have the honor to be
Sir,
Your most obedient humble
servant
[illegible]
President

179

Financial (1875/Dep.
(Municipal - Medical)

From

The President
Municipal Commn
Negapatam

To

The Chief Secretary
to Government
Madras

Dated 20
Desp'd 21 } Dec. 1875
Recd 23?

No. 2996 / No. 298

Encls. 5

With. wds.

Forwarding copy of a letter from the Vice President, Negapatam Municipality, requesting to obtain Govt. sanction for laying out a portion of the funded capital of the Civil Dispensary there for the provision of a dwelling house to the Hospital Assistant attached thereto.

The proposal is sanctioned

4 Jany 76 No 7.

To the Presdt Ml. Commn Negapatam 5
" Pub Works Dept 6
" Surgn Genl I.M. Dept
" Accountant General

Despd 11/1/76

c27.12

6-5-13 B III ✓

Govt. of {1876} Madras.

Financial

G.O., 1st January 1876, No. 7

Nos. 13-14

Municipal-Medical

The proposal to lay out a portion of the Jeundah Capital of the Negaha stane Dispensary in building a house for the Hospital Assistant attached thereto, sanctioned.