S.S.P. 1—30,000—18-10-56.

MADRAS RECORD OFFICE.

Government of Madras.

Judicial DEPARTMENT

G.O. No. ~~327~~ 1167		Press ~~Mtr~~
27		
Dated	4-9-	~~19~~ 1957

Not to be folded or roughly handled

1
1118
27
1a2
1439

Fort St. George, Judicial Consultation, 8th September 1857.

No. 27. Read the following Extract from the Minutes of Consultation in the Military Department, dated 24th August 1857.

Read the following letter from the Quarter Master General of the Army; to the Secretary to Government, Military Department, dated 24th August 1857, No. 389.

Sir,

I have the honor by order of the Provincial Commander in Chief, to forward an estimate (Rupees 1,500) of the expense of levelling the site of the Pentaur lines at Trichinopoly, and to recommend that the necessary sanction may be granted.

These lines have been recently vacated by 25th Regiment N. I., and it has been for some time in contemplation to re-build them entirely on a better ventilated and more commodious plan.

(Signed) F. A. REID,
Quarter Master General.

Estimate of the expense of levelling the site of the Pentonr lines prepared with reference to a letter from the Major General Commanding, No. 188, dated 9th April 1857.

Measurements.														
L.	B.	D.	Superficial feet.	Cubic feet.										
						Rs.	A.	P.		Rate.	Rs.	A.	P.	Rs.	A.	P.
134	31	"	4,774	"												
253	67	"	16,951	"												
253	31	"	7,843	"												
252	60	"	15,120	"												
250	61	"	15,250	"												
164	46	"	7,544	"												
178	72	"	12,816	"												
188	71	"	13,348	"												
80	45	"	3,600	"												
330	28	"	9,240	"												
198	60	"	11,880	"												
190	70	"	13,300	"												
140	32	"	4,480	"												
33	24	"	840	"												
200	72	"	14,400	"												
75	28	"	2,100	"												
600	21	"	12,586	"												
422	66	"	27,852	"												
100	93	"	9,300	"												
351	63	"	21,963	"												
360	55	"	19,800	"	Blocks of huts.											
333	60	"	20,100	"												
299	60	"	17,940	"												
299	61	"	18,239	"												
280	60	"	16,800	"												
262	60	"	15,720	"												
292	60	"	17,520	"												
280	60	"	17,340	"												
282	30	"	8,610	"												
110	50	"	5,060	"												
67	37	"	2,479	"												
57	67	"	3,819	"												
70	70	"	4,900	"												
65	78	"	5,070	"												
133	87	"	11,571	"												
78	88	"	6,864	"												
109	65	"	7,085	"												
47	28	"	1,316	"												
71	53	"	3,763	"												
66	45	"	2,970	"												
65	65	"	4,225	"												
130	70	"	9,100	"												
Total			440,675		Demolishing and levelling mud walls.	0	6	0	@ 840 feet.		126	11	0			

L.	B.	H.														
300	215	2 6"	"	161,250	Filling up hollow in hutting ground opposite place of Arms.											
330	225	1 0	"	12,2250	Levelling mounds on south end of hutting ground.											
720	60	0 9"	"	32,400												
			Total	315,850	Earth work	0	3	6	@ 100 c. f.		1065	11	9			
700	10	1 6	"	10,500	Levelling clearings of channel.	0	2	0	do.		13	2	0			
					Sundries and Contingencies									1250	0	1
														254	6	7
														1500	0	0

Total Estimate Rupees

District Engineer's Office, Trichinopoly, 12th August 1857.

(Signed) J. G. RYVES, Lieut.
District Engineer.

Referred to the Judicial Department with a view to its being ascertained whether Convicts cannot be made available for the work in question.

Fort Saint George, 25th August 1857.

(Signed) R. HAMILTON, Major,
Ag. Dy. Secretary to Government.

No. 59. ORDER THEREON, No. 1147; dated 4th September 1857.

Referred to the Inspector of Prisons, who will report whether Convict labor can be afforded for the purpose required, and if so, to what extent.

(Signed) E. MALTBY,
Acting Chief Secretary.

Rud. F. Cartwright.

No 1147

Respecting the Inspector of Prisons
who would report whether Convict labour
can be applied for the purpose required
and if so to what extent

Gaol
Hobart Town
6th September 1847

Copy to Inspector of Prisons Dispatch