

MADRAS RECORD OFFICE.

Government of Madras.

Judicial DEPARTMENT.

G.O. No.

Press

Mis.

Back No 42-43

Dated

6-1-

1857

Not to be folded or roughly handled

21.10.24

From

Lieutenant C. Munnery
Civil Engineer of Cuddapah D.
Colonel C. O. Faber
Chief Engineer Dept. of L. & C.
Fort St. George

Judicial

Sir,

- 1 Estimate
- 1 Abstract
- 1 Specification
- 1 Plan

4

The accompanying Estimate amounting to Rupees (880) Eight hundred and eighty provides for a want much felt by the Sepoys composing the guard at the Jail in Cuddapah viz. a comfortable guard room.

The present building is in such a wretchedly dilapidated state, that during rainy weather the Sepoys are obliged to take refuge in the Verandah of the Sailors House.

The Walls are composed of unburnt brick and the roof of mud over planks but it is useless, attempting to patch up the old building, I have therefore prepared the accompanying Estimate for a new guard room to be constructed of the best materials.

The guard consists of one Munsiff & Naik and 12 Sepoys.

Civil Engⁿ Office
Cuddapah D.
28th November 56

I have the honor to be
Sir,
Your Most Obed^t Serv^t
C. Munnery
Civil Engⁿ of Cuddapah D.

Specification for a new Guard room proposed to be constructed for the accommodation of the Jail Guard at Cuddapah.

This building is to consist of one room 28' 6" in length by 12' in breadth and 12' in height up to the beams. The Verandah in front to be 8 feet broad including the pillars.

The foundations of the rear wall to be 6 feet in depth as the soil at that particular spot is loose earth the width at the base to be 6 feet and to decrease gradually in steps up to the top where the breadth will be 3 feet.

The foundations of the front wall to be 4 feet 6 inches deep and 3 feet broad and of the Verandah Wall 4 feet by 2 feet 9 inches.

The basement Walls of the Room to be 2 feet 6 inches broad by 1 foot 6 inches high. The basement of the Verandah to be 2 feet 3 inches by 1 foot 3 inches.

The main Walls to be 2 feet thick and 12 feet high up to the beams. The pillars of the Verandah to be 1 foot 6 inches square and 8 feet high. All the above to be built of brick in Chunnam.

The Roof of the room to be terraced with brick on edge 3 Courses of flat tiles and 3 Coats of Chunnam. The Roof of the Verandah to be made with Dalmyrosh rafters rakers, Nail 3 Courses of flat tiles and 3 Coats of Chunnam. The whole to be floored with Brick & Selly in Chunnam.

Prepared by
J. P. P. P.
1st December 56

W. H. H.
Civil Eng^r of Cuddapah

Volume 6 Doc 56 No 86662

11/14/93 P P P P

Form
and
specification
of
Cuddapah

Order 28th November
Dec 3 Dec 3

11/14/93

Foundations are to be made
for constructing a new Guard
Room for the Jail at Cuddapah.
The whole to be floored with Brick &
(588) by the Municipal Council.

11/14/93

11/14/93

Volunt. 6 Decy 56 No 8662

PPPPF 2

Enclosures in a letter
from the Civil Engineer
Guddarupak District
dated 28th November

No. 720.

To
The Chief Engineer
Department of O.
Fort Saint Charles

In fons.

Abstract Estimate for
constructing a Guard
Room for the Jail
at Cuddeposak among
W. H. Pax 1880 Nig 10
hundred and eighty

P.N. 2880/50

498568
In W 1918

Civil Engineer's Office
Caddapan District
28th November 1856

Sold Earth - - - - -
Foundation Brick in Chumam
Amount of Estimate Rs^{t} 580 - - -

PLAN
Elevation and Section
For
A New Guard Room
For the
Jail at Cuddapah

[illegible]

Elevation

Architectural drawing of a building elevation. The drawing shows a series of columns supporting a pediment. The columns are of different heights and are arranged in a row. The pediment is a triangular structure above the columns. The drawing is a black and white line drawing with some shading. The text "Scale of 8 Feet to an Inch" is written vertically on the left side of the drawing. The number "17" is written at the bottom left.

Scale of 8 Feet to an Inch

17

Scale of 8 feet - 60 in. Inch

Thurston
Lieut.

Civil Engineer Cassapaah Dist.

Enclosed in a letter from the
Civil Engineer (as above) D.
dated 28th November 1856 No. 72

To The Chief Engineer
D. P. W.
Fort Saint George

No. 2880/56

PLAN

Elevation and Section for
New Guard Room for the
Jail at Fort Saint George
Cuddapah District
Amounting to Rs. 880
Eight hundred and eighty.

£1856D
In 1856

PUBLIC WORKS DEPARTMENT. Judicial.

No. 2418.

Extract from the Minutes of Consultation under date the 23rd December 1856.

Read the following Report from Colonel C. E. FABER, Chief Engineer; to the Secretary to Government, D. P. W., dated 6th December 1856, No. 8662.

Report P. P. P. P. on an estimate prepared by the District Engineer for constructing a new Guard room at the Jail in Cuddapah, amounting to Rupees (880) eight hundred and eighty:

The District Engineer states, that the present guard room which is built of sun dried bricks with a mud roof, is in such a dilapidated state, that during the rainy weather, the guard, which consists of one Havildar, 2 Naigues and 12 Sepoys, is obliged to take shelter in the verandah of the Jailor's house. The bad materials of which the present building is constructed, prevent also the possibility of any substantial improvement or repair being made to it. Under these circumstances, the District Engineer recommends the erection of a new building, agreeably to the plan submitted with his letter of the 28th November 1856, which plan appears well suited for the purpose in view. Under these circumstances, the Chief Engineer solicits the sanction of Government to the amount of the estimate, which is framed on sufficient and moderate data, viz., Rupees eight hundred and eighty. The unusual depth of the foundations, being doubtless required by the nature of the soil (black cotton.)

Referred to the Judicial Department for consideration.

(A true Extract.)

J. H. Sandillon
Secretary to Government.

To The Judicial Department.
with 11 Rigs. Encl.

Recd 26th Dec 1856

1857-
 Camp near the fort of 1857

to 1857 Jan 6 - January 1857
 Judicial 1857

Extract from
 Public Works Report

1857

1857

1857

1857

1857

1857

42443

Referring for consideration
 and estimate for construction
 of a road at 1857. and road work
 for the year at 1857.
 1857. 1857. 1857.

1857

Referring for the report of the
 Inspector of Prisons.

1857

1857

1857