M.R.O. 1—38,000—16-10-20.

MADRAS RECORD OFFICE.

Government of Madras.

Judicial DEPARTMENT.

G.O. No. 1059 Press ~~Mis.~~

155-156

155-156

Dated 21.8.1860 ~~19~~ .

3/4

Not to be folded or roughly handled

1059

155
156

Proceedings of the Madras Government, Judicial Department,
21*st August* 1860.

No. 155. Read the following letter from Lieutenant Colonel W. H. HORSLEY, Chief Engineer, to the Secretary to Government, Department Public Works, Fort Saint George, dated 13th August 1860, No. 3,705.

Enclosures 5.
1 *Letter from District Engineer, No.* 326, *dated 28th June* 1860.
1 *Do. from do. No.* 479, *dated 24th July* 1860.
1 *Report.*
1 *Abstract Estimate.*
1 *Plan.*

28th June 1860, *No.* 326.

I have the honor to forward herewith for submission to Government a Plan and Estimate amounting to Rupees 2,720, received from the District Engineer of Madras, for repairing and improving the Jail Hospital at Chingleput.

2. Captain Moberly states that this Estimate was prepared at the request of the Sessions Judge, in consequence of the roof of the building being in a dangerous state, white-ants having eaten away the greater part of the reepers and also attacked the rafters.

3. It is therefore proposed to raise the main walls a foot and a half, so as to make a continuous slope in the roof, and to lay a granite stone on the top of each pillar, to prevent the white-ants getting access to the rafters. The roof is to be renewed and fitted up with ridge ventilators, and honey-comb tile work is to be provided for the partition walls to afford additional ventilation. The verandahs, and other places where required, are to be refloored with 8 inches square bricks in chunam, the building is to be re-plastered with chunam, and the doors and windows fresh painted.

4. As the Plan and Estimate now submitted have been countersigned by the Inspector of Prisons in token of his approval, and have also been duly examined in this Office, I have to request the sanction of Government to the same for execution from the general Funds at the disposal of the District Engineer. Captain Moberly states that he has no record of the date of the last repairs executed to this building.

24th July 1860, *No.* 479.

Transferred to the Judicial Department.

(Signed) C. G. MASTER,
Dy. Secy. to Govt.

13th August 1860.

No. 156. ORDER THEREON, 21st August 1860, No. 1,059.

Government sanction the Estimate for repairing and improving the Jail Hospital at Chingleput. The expense, Rupees (2,720) two thousand seven hundred and twenty, will be defrayed from the Repairs Fund of the District.

(Signed) T. PYCROFT,
Chief Secretary.

Exd. F. Cartledge.

No. 1059 - 21st August 1860.

Govt. sanction the Estimate for repairing & improving the Jail Hospital at Chingleput. The expense, Rs. 2,720 Two Thousand Seven Hundred & Twenty Rupees, will be defrayed from the Repairs Fund of the District.

The Public Wks. Dept. with Enclosures.
" Inspector Genl. of Jails.
" Acct. Genl.
" Collector of Madras.
" Sessions Judge of Chingleput.

Sept. 23d

Respr. ch. Sup. Cuthbertside

Your most Obedient Servant

Edwd Bowdler Lieut Colonel

Edwd Williams Lieutenant