M.R.O. 1—5,000—16-10-28.

MADRAS RECORD OFFICE.

Government of Madras.

Judicial **DEPARTMENT.**

G.O. No. 1726 Press Mis.

28-31

Dated 4—12—~~19~~ 1885

11/12

Not to be folded or roughly handled

Read the following papers :—

No. 28. From the Superintending Engineer, 7th Division, to the Secretary to Government, Public Works Department; dated Bhowany, 25th July 1865, No. 70.

I have the honor to submit, herewith, the Report (with Plan*) of the Committee on Coimbatore New Central and District Jail, appointed by paragraph 5 of Government Order, in the Judicial Department, No. 877, of 16th June.

* Forwarded by bangby.

REPORT.

In submitting the Report called for in paragraphs 5 and 6 of Government Order, in the Judicial Department, No. 877, of 16th June, the Committee on the New Coimbatore Central and District Jail desire, in the first place, to call attention to the fact that two of the blocks of Radial Cells originally planned, the Solitary Cells, the Female Cells, the Hospital Wards, the Police Guard House, Debtors Cells, &c., not having been commenced, they avail themselves of the opportunity of planning, for the additional accommodation required, in a less objectionable manner than by building upper stories to two Radial Blocks, as suggested in paragraph 11 of the Jail Report by Messrs. Rohde and Ellis.

2. The original plan of cells seems peculiarly inconvenient and wasteful of material and space. Neither in cubic capacity, nor in superficial area, are they commensurate with either of the standards lately laid down; the former being 2160 cubic feet, or enough for 3½ men, and practically for only three men, to whom the very unnecessary superficial area of 64 feet is thus averaged, whereas with 18 feet height of cells, the requisite capacity of 618 cubic feet per man is attainable with the regulation allowance of 36 square feet of standing room, *i. e.*, allowing for wall space saved, that two men can be accommodated on an area taken up by one man in the original cells.

3. Those cells, at three men to each, and 32 cells to each of the three blocks in progress, provide for 288 men, and may be reserved for prisoners of the more dangerous classes, requiring segregation. The remaining 276, out of the total estimated number of 564 long sentence men, in rooms 18 feet high and of the same width, will be accommodated in two blocks of exactly the same length as those they will supersede, but only three-fourths as wide, and two-thirds as high (supposing an upper story to be added to the latter.)

4. Taking the proportions shown in paragraph 16 of the Jail Report, the short sentence and other prisoners remaining to be accommodated would be as follows :—

Under one year.....	64	
Security prisoners...	7	47
Under trial.....	27	
Civil debtors.....	13	
State prisoners.....	0	
Total...	111	

But these are numbers liable to more fluctuations that the others, and (except the first noted) are made up of classes entitled to more space and better accommodation. It is accordingly proposed to provide for 90 short sentence prisoners in one block of five rooms, each 36 feet long. And in another block of seven rooms, 18 feet cube, to accommodate the non-criminals, of whom they will contain 63 at the convict standard of space, which, in practice, will generally be greatly exceeded; and three additional rooms of similar dimensions, for miscellaneous purposes, may be added, without encroaching more than originally intended on the ground space within the Jail precincts.

5. Under recent orders, the Jail Hospital—provision for which under the present sanction is utterly inadequate—must be without the walls, and as a Committee has been appointed at Madras, by paragraph 7 of the Order of Government under which we act, to settle a standard plan of proposed new Jails, it is proposed to delegate to them the planning of this building, with

all its accessories. There will then remain at the entrance of the prison, and touching its boundary wall, only a Guard house for the Police, a revised plan proposed for which is shown, with the other proposed alterations, in the accompanying paper, leaving it open to adopt any better suggestion of the Committee above alluded to. No provision whatever having been made for latrines in the original plans, we propose that the Madras Committee provide the general designs, recommending that one be allowed within each of the 12 yards of the prison, adapted by the Local Executive to the number, sex, and age of the persons likely to use each respectively. An adequate number of Solitary Cells may not have been provided in the new designs, with reference to which and to condemned cells, and special contrivances for such buildings, the Madras Committee may be able to instruct the Local Executive better.

6. The supply of water is another matter altogether neglected in the original plans, and hitherto most inadequately provided for by verbal orders of the Inspector General of Jails, on a requisition of the Executive Officer who wanted water for his works. One well has been sunk, in a very irregular manner, of large superficial dimensions, narrowing to about nine feet diameter at a depth of 62 feet, at which the average supply available each morning is stated to be about 1100 gallons; and if this were quickly pumped out there is reason to suppose that 1200 gallons more might be procurable throughout the day. It is not thought advisable to do more than increase the capacity of this well by deepening and perhaps widening it. Another in the same precincts is not likely to increase the supply; but we propose that one be excavated at the lowest corner of the ground taken up around the Jail, the labor of the Convicts being principally availed of in its excavation. But as to the total supply requisite, we require the instructions of the Madras Committee on authoritative grounds.

7. As to the other points mooted in the papers referred to in paragraph 6 of the Government Order under note, we record our opinion that, to the best of our judgment and information (bearing in mind the acknowledged imperfection of Jail statistics in this country) the Jail plans now submitted afford adequate means of classifying prisoners for every practical purpose; that the escape of prisoners is guarded against to the utmost possible; while the outer and divisional walls do not, at the favorable site selected, check the circulation of air to an extent likely to be prejudicial in the climate of Coimbatore. Excess of ventilation is indeed the fault to be found with the old pattern cells already built or in progress, to shield the upper part of the front of which we propose the addition of verandahs, with wooden half-doors, folding back against the outer walls, wherewith to shut up the lower halves of the open iron doors on damp and windy nights. Extra ventilation in the sides of these narrow cells is not required, and cannot be obtained, if it were, without opening communication from cell to cell.

8. We conclude by bringing to notice the fact of the very inadequate allotment of funds for carrying on this important work during the current official year. Out of an estimate (revised) of Rupees 2,57,000, which additions and alterations may probably raise to 2¾ lakhs, it appears that Rupees 1,06,583 were spent up to the end of last official year. In the past two months of the current year, Rupees 32,000, out of an allotment of only Rupees 67,166, have already been spent; at which rate the works must be stopped in September, if an additional grant is not forthcoming. Keeping in view the urgent necessity of increasing Jail accommodation as quickly as possible, we are of opinion that immediate application for an additional grant of one lakh of Rupees be made to the Government of India, on the strength of their assurance quoted in paragraph 8 of the Government Order. One block of cells will be ready for the reception of prisoners (96) within the current month, a second block in August, and a third in September, if it be thought fit to use them before the verandahs, half doors, latrines, guard rooms, &c., recommended in this report are set in hand.

COIMBATORE, *15th July* 1865.

(Signed) G. A. HARRIS.
(„) W. F. DAVIS, M. D.,
(„) G. W. WALKER, Lieut. Col., R. E.,
Superintending Engineer, 7th Division.

P. S.—Surface drainage of the Jail site will be provided for in the detailed Plans and Estimates to be drawn up by the Local Executive on receipt of the orders of Government on this

Report. Provision is also proposed to be made for a washing and bathing tank in each of the yards, to be supplied by channels running from the well inside; all surplus water being conducted outside, and utilized in a Prison Garden round the walls, or carried off beyond the ground attached to the Jail. Suggestions are requested from Madras as to any subsidiary accommodation to be provided outside the walls for Apothecaries, Dressers, Sub-Jailers, Writers, and Warders, or other attendants.

(Signed) G. W. WALKER, Lieut. Col., R. E.,
Superintending Engineer,

The other Members of the Committee having also seen and approved of the Postcript.

DESPATCHED FROM BHOWANY,
25th July 1865.

Referred to the Judicial Department, with reference to the orders in that Department, No. 1855, dated 3rd July 1865.

FORT SAINT GEORGE,
27th July 1865.

(Signed) C. A. ORR, Colonel, R. E.,
Secretary to Government,
Public Works Department.

Referred to the Committee appointed to prepare plans of Central Jails, for their opinion.

(Signed) A. J. ARBUTHNOT,
Chief Secretary.

4th September 1865.

No. 29. From the Central Jail Committee, Bangalore, to the Chief Secretary to Government, Fort Saint George; dated Bangalore, 18th September 1865, No. 18.

We have the honor to return the report upon the Prison at Coimbatore, referred to us on the 4th instant, and to state that, in our opinion, the requisite accommodation, viz., that for 675 persons, may be secured at a smaller expense than would be entailed by the plan of the Local Committee.

2. The two blocks of Workshops marked B X in the local plan are fine airy buildings with trussed roofs, which we consider to be ill-adapted for the purpose for which they were intended, but which may be easily converted into Barracks consisting of four wards, each ward to contain 24 men, after allowing space for a night latrine. Instead of the block of radial cells, which, according to the original plan, it was intended to build between the compartments lettered D and E, we would build a Barrack of six wards, each to contain 21 men, and allowing space for a latrine as in the others. These three Barracks would thus accommodate 318 convicts, and the three blocks of radial cells now nearly finished will contain 288, making a total of 606. The remaining 69 will consist of females, juveniles, civil debtors, and of a certain proportion in Hospital. In order to provide for the female convicts, we recommend that the cooking shed, C X in the local plan, should be removed, and that, in the compartment thus rendered available, a ward, with a small Hospital and out-houses, be erected as shown in the plan forwarded herewith. The wards proposed for the juvenile convicts and civil debtors are also shown in the plan, and do not appear to call for any particular description.

3. The vacant compartment B, with a small portion taken from those marked, respectively, A and C, will be sufficiently spacious and airy for the Hospital, and the out-houses attached thereto.

4. The Worksheds marked B Y in the local plan are terraced buildings, sufficiently large to admit of a portion of each being walled off as cooking sheds for the three radial cells, and for Barrack No. 2; while for the Barracks Nos. 1 and 3, small cooking sheds may be built in each compartment, as shown in the new plan. The terraced sheds require the addition of light verandahs to protect the prisoners from the weather. A Workshed for each of these last mentioned Barracks can be built against the radial walls.

5. The foundation and basement of the solitary cells having been already completed, we would proceed with them according to the original design, shutting off five or six cells for the reception of lunatics. A range of work-cells for prisoners sentenced to solitary imprisonment may be erected opposite, as shown in plan.

6. The palisading at the entrance has been completed, but appears to us somewhat low, being only six feet six inches in height, and we therefore recommend that it be headed with iron spikes.

7. All that has already been built will thus be utilised as much as practicable, and the expense attendant on the erection of a large extent of palisading, or wall, will be avoided. Should it, however, be considered by Government that it is essential to have the Hospital outside, the compartment B would in that case be available for the reception of another Barrack.

8. The Store and Tool-rooms, Office, Guard-rooms and gateway are shown in the plan, and do not require remark.

9. The Local Committee propose verandahs and wooden half-doors for the protection of the old pattern cells, but we think that, for the general wards, doors of the description recommended by us in our report on the proposed Central Jails—that is, iron barred doors, with the addition of half-venetian, half-panel, doors outside—would meet the end in view, without verandahs.

10. Another well should be sunk in the spot indicated by the Local Committee, and further measures for the supply of water may be held in abeyance, pending the result, but the existing well ought to be deepened and widened as proposed.

11. The existence of separate water-cisterns in each compartment has been found objectionable in the Bangalore Prison, and we should prefer to have two bathing cisterns at one convenient spot to be selected hereafter.

12. A latrine, according to the plan sent up with our former Report, may be constructed outside, with due reference to the prevailing winds. It should be enclosed by a palisading, and be accessible by means of a gateway through the enclosing wall. We are of opinion that this arrangement is preferable to that according to which separate latrines are placed in each compartment. It may be mentioned in this place that in the surplus space which will remain in each radial cell, after receiving the complement of three convicts, a night latrine may be placed as in the other wards.

13. Considering the distance of the Jail from the town, it may be desirable to build quarters for a Dresser and Warders; but this is a point which may be better disposed of after consultation with the Superintendent of the Jail, and it may be submitted hereafter by the Inspector General, if necessary.

14. A detailed statement, shewing the whole accommodation already provided, and also that proposed is forwarded herewith.

(Signed) W. J. WILSON,
Acting Inspector General of Jails.

(Signed) W. MACKENZIE, M. D.,
Acting Inspector General of Hospitals.

(Signed) J. C. ANDERSON, Lieut.-Col., R. E.,
Consulting Engineer for Railways.

P. S.—In the accompanying statement, provision is made for 21 juveniles and 20 debtors; but as, on a further examination, since the departure of my colleagues, of the returns of former years, I am of opinion that more limited accommodation will suffice, a Ward for 15 juveniles and 12 debtors is also shewn in the plan.

(Signed) W. J. WILSON,
Acting Inspector General of Jails.

BANGALORE,
23rd September 1865.

COIMBATORE JAIL.

Description of Buildings.	Inside dimensions. Length. Ft.	Ins.	Breadth.	Average Height.	Number in each Cell or Ward.	Number in each Block or Barrack.	Total.	Superficial area per man.	Cubical space per man.	Ventilation.	Doors. Number.	Doors. Height.	Doors. Width.	Windows. Number.	Windows. Height.	Windows. Width.
Three Radial Blocks, 32 Cells each... ...	24	0	8	11½	3	96	288	64	712	Wall.	1	6½	3	2	4	3
Two Barracks, four Wards each, Trussed Roofs... ...	43½	0	24	16½	24	96	192	43½	682	Ridge.	6	8	4			
One do. of six Wards do. ...	49	0	18	16½	21	126	126	42	683	Ridge and Eave.	8	8	4			
Six Work-sheds, { two...	134	7½	14	11½	...	...	...	...	...	Ridge.	...	...	...			
Six Work-sheds, { four...	134	7½	12½	11½	...	...	...	...	...	do.	...	...	...			
Six Cooking-sheds, { two...	46½	0	9½	10	...	...	...	...	...	do.	...	...	...			
Six Cooking-sheds, { four..	46½	0	12½	11½	...	...	...	...	...	do.	...	...	...			
One Barrack for Females, three Wards, Trussed Roof.....	29	0	18	16½	13	39	39	40	661	Ridge and Eave.	4	7½	4	4	4	3
Hospital for Females, do. do. ...	24	0	16	15½	8	8	8	48	744	do.	1	7	4			
One Barrack for Juveniles, single Ward, do. ...	49	0	18	16½	21	21	21	42	683	do.	8	8	4			
Work-shed, Cooking-shed, { do. under one Roof... ...	35	0	14	11½	...	...	...	...	...	Ridge and Eave.	4	8	4			
One Barrack for Debtors, two Wards, Trussed Roof... ...	23¾	0	18	16½	10	20	20	43	709	do.	1	6	3	1	14½	5
Cooking-shed, do.	20	0	9	10	...	...	...	...	...	Wall.	1	6	3	1	11	5
Fifteen Solitary Cells, Terraced Roof...	12	0	7½	12	1	15	15	90	1,080	do.	1	7½	4			
Fifteen Work-sheds for Solitary Prisoners...	12¾	0	6½	12	1	15	15	84	1,008	do.	1	7½	4			
Five Cells for Lunatics..	12	0	7½	12	1	5	5	90	1,080	do.	1	7½	4			
Hospital for Males, Trussed Roof, with two Wards each...	18	0	18	18	18	54	54	48	864	Ridge.	8	7½	4	4	4	3
One Ward for special cases...	24	0	18	18	9	9	9	43	861	do.	8	7½	4			
Stores, Grain, and Tools, three Rooms each	50	0	16	14½	...	...	...	...	...	.....	...	...	...			
Office...	24	0	16	14½	...	...	...	...	...	.....	...	...	...			
Gate, Outer, arched over, space above Gate to be filled in with planking...					...	...	...									
Do. Inner, two leaves...	...		...	...	...	...	...									
Palisading, Entrance...	...		...	...	...	...	...									
Do. dividing Hospital and Stores...	...		...	...	...	...	...									
Guard-rooms, two each...	...		...	8½	...	...	...									
	32	0	15	15												

(Signed) W. J. WILSON,
Acting Inspr. Genl. of Jails.

BANGALORE,
18th September 1865.

No. 30. From the Acting Inspector General of Jails, to the Chief Secretary to Government, Fort Saint George; dated Bangalore, 23rd September 1865, No. 310.

With reference to paragraph 10 of the Report of the Central Committee upon the Coimbatore Jail, and to my letter of this day's date, regarding the transfer of convicts to the new Jail at Coimbatore, I have the honor to request that orders may be issued, as soon as convenient, for the sinking of a new well at or near the spot indicated by the Local Committee, as I am informed that the supply of water from the present well is insufficient.

2. The convicts at present lodged in the new Jail will be available for the work.

No. 30A. MEMORANDUM.

With reference to our recent conversation regarding the expediency of building a Hospital outside the Central Prison at Coimbatore, and of providing increased accommodation within the walls, I herewith forward a tracing, showing the buildings as they now stand, and also the proposed additions, with reference to the objects abovementioned. The finished buildings are colored red, and the lettering is, as far as possible, the same as that in the plan submitted by the Committee.

2. Provision was made in the former plan for 675 convicts, that being the number given in the Proceedings of Messrs. Rohde and Ellis. The present plan shows accommodation for 1005 prisoners, debtors included, but it may possibly be thought that Barracks Nos. 1 and 4 are too near each other, and, if so, then, instead of these, a single Barrack might be built on the radial wall dividing the compartments C and B; this would reduce the accommodation to 829. Again two wards might be taken off the inner ends of these two Barracks where the space is most contracted; this would leave accommodation for 917.

3. The foundations and cross walls upon the radial wall between D and E being already built of the same dimensions as those in the blocks of radial cells. I have proposed the same dimensions for Barrack No. 2, in order to lose as little of the work as possible.

4. The situation of the juvenile ward has been changed, but in other respects it is the same as that in the former plan. I would not diminish the accommodation, as suggested in my postscript to the letter of the Committee, dated 18th September; for, although it may be somewhat greater than is required for Coimbatore, no separate juvenile wards have been proposed for Salem, and in event of the wards there being required for adults, the boys could be sent on to Coimbatore.

5. In the former plan, provision was made for 39 females. This was based on the Returns furnished to Messrs. Rohde and Ellis, but I find that, on the 9th instant, there were 44 female prisoners in the Coimbatore Jail, and I would, therefore, add another ward of the same size to the female barrack, which would thus contain 52. I would urge this, whatever plan may be determined upon. There is ample space for this addition in the compartment allotted to women.

6. The Hospital may be placed within an enclosure carried out in part of the side marked B, which is still unbuilt; the three outer sides to be walled; the fourth

and inner to be palisaded. If it is to be outside, then increased accommodation must be provided, in proportion to the number of convicts in excess of 675.

7. It will be seen from the former plan that the Committee proposed to extend the inner wall only a short way beyond the centre of the compartments C and K, but it has already been carried to the end of these compartments; and, having since been informed of the object for which it was designed, I think it ought to be carried on up to the gate-way as originally proposed. Mr. Rohde objects to the admission of the Police into the interior of the prison, and his intention was that the men on duty should patrol on the banquette at the foot of the inner wall, from which they could see over and command the compartments, without mixing either with the convicts or the Prison officers. As this wall has been very nearly completed, it would be a pity not to carry out the original design, the grounds for which appear to be substantial.

8. No workshed has been shown for Barrack No. 4, as in all probability a certain number of men will always be required for out-of-door labor of some kind. A cook shed could be built against the radial wall, if necessary.

9. The end of the trussed workshed, which it was proposed to convert into a barrack, might be walled off as a cooking shed, and the whole shut off from compartment D, by building up that side.

OOTACAMUND,
21*st October* 1865.

(Signed) W. J. WILSON,
Late Acting Inspector General of Jails.

To the Honorable A. J. Arbuthnot, Chief Secretary.

N. B.—The radial cells measure 24×8, which would give 48 feet of superficial area to each of four men. I am not certain as to the height, but I believe that, although the cubical space for four would be under 648 feet each, yet that four could be accommodated in each cell without any harm. In the Report of the Committee, only three are allowed to each cell, and accommodation is provided for 675

Add.....	96 for the 4th man.
	771
3 Blocks of 32 cells each, 3 in each cell.....	288
Barrack No. 3.....	96
„ Nos. 1, 2, and 4, 176 each...	528
Female barrack, 4 wards of 13 each.....	52
Juvenile „	21
Debtors' „	20
	1005
Deducting one Barrack.....	829
Cutting off two wards from proposed Barracks 1 and 4	917

No. 31. ORDER THEREON, 4th December 1865, No. 1726.

The Governor in Council approves generally of the measures suggested by the Central Jail Committee, in their letter above recorded, for improving the plan of the Central Jail now under construction at Coimbatore; but he is of opinion that the arrangement recommended by the late Acting Inspector General of Jails, who made a second inspection of the site of the new Jail, after the report of the Committee was laid before Government, of placing the Hospital outside the Jail enclosure, and so providing space for an additional Barrack, which will raise the number of prisoners which the Jail will accommodate to 829, or to 1005 if four convicts be confined in each cell, may with advantage be adopted. The addition of a single Barrack, is, His Excellency in Council thinks, preferable to the other alternative suggested in Colonel Wilson's Memorandum, which indeed is that entered in the plan submitted by him of building two barracks in the spaces marked B and C. The change proposed by Colonel Wilson in the situation of the juvenile ward may also be carried out, and provision should be made for the addition of a ward capable of holding 13 prisoners to the Female Barrack.

2. Orders will be issued in the Public Works Department for the preparation of the necessary revised plans and estimates, and also for the sinking of an additional well, as recommended in the Acting Inspector General's letter of the 23rd September last.

(True Extract).

Chief Secretary.

To the Inspector General of Jails.
„ Public Works Department, with 3 Plans.
To Lieutenant Colonel W. J. Wilson.
„ the Deputy Inspector General of Hospitals W. McKenzie.
„ Lieutenant Colonel J. C. Anderson, R. E.

Exd. J. H. Burns.

The stereotyped form of radial blocks of cells or wards may be made to answer very well for Prisons, but there is no earthly reason why the boundary wall should be made Semicircular or Octagonal - it would in all cases be far better to have it square or rectangular as at Bangalore - Space is often afforded at the angles for supplementary buildings. Female and debtor wards &c &c - While if the boundary walls are put at a greater distance from the Blocks the watchmen have a much better chance of seeing over the whole area of the Prison and detecting any attempt to escape - therefore as far as regards the general Plan for such I think it would be better to adopt the rectangular form for the general

inclosure and to keep the
wall at a greater distance
from the buildings say
30 or 40 feet - the additio-
=nal expense will be
but trifling in compa-
=rison with the advantages
gained -
2 Next to the Cells, they
present no advantages as
regards discipline - and
are in every respect more
costly than wards - Should
therefore do away with
the Cells - by removing 3
or four partition walls -
I do not mean that I should
pull down walls already
built - though I am by no
means certain that it
would not be Economical
to do so - but that I should
discard them from the
general Plan - a few
single solitary cells
will be required for
punishment - say 20
for a far less number that I
contemplate -
With reference to the Lay
I think the suggestion
made by the committee

I what Col Wilson was
President seem to be very
judicious & likely to
answer every purpose

I quite concur in the
views taken by the Post
WOR

Proc. no. 136. 162
16.6.65
127. 128
14.11.62
179-199
21.7.62

12-8

Judicial Department.

PROCEEDINGS of the MADRAS GOVERNMENT.

Read the following papers:-

From the Supdg Engr & Wks Hon Ord — } Hon ble 25th July 1865 No 70.

— Central Jail Committee Bangalore. } — 18th Sept — 18.

— Ag Supr General of Jails — } — 23d — 310.

Order thereon 4th December 1865-No 1726.

The Governor in Council approves generally of the measures suggested by the Central Jail Committee in their letter above recorded for improving the plan of the Central Jail now under construction at Coimbatore, but

but he is of opinion that the arrangement recommended by the late Acting Inspector General of Jails, who made a second inspection of the site of the new Jail after the report of the Committee was laid before Government, of placing the hospital outside the Jail Enclosure and so providing space for an additional Barrack which will raise the number of prisoners which the Jail will accommodate to 829 or to 925, if four convicts be confined in each cell, may with advantage be adopted. The addition of a single Barrack, is, His Excellency in Council thinks, preferable to the other alternative suggested in Colonel Wilson's

Wilson's memorandum, which indeed is that entered in the plan submitted by him of building two barracks in the spaces marked B and C. The change proposed by Colonel Wilson in the situation of the juvenile ward may also be carried out, and provision should be made for the addition of a ward capable of holding 13 prisoners to the Female Barrack.

2. Orders will be issued in the Public Works Department for the preparation of the necessary revised plans and estimates and also for the sinking of an additional well as recommended in the

Acting

Acting Inspector Generals
letter of the 23d September
last

Inspector General of Fails.
Public Works Dept. with Sketch
dept 11/12 by Lt Col Gibson
Lt Col Anderson R. E.

Prod. Secy

Judicial 1865. Department.

No. 726.

PROCEEDINGS OF GOVERNMENT.

Feb. 11 to 4/Dec
" —1547—

Dated 4th December 1865

Press No. 2755, G. M.—14-11-65—500.

28c

C/Accn 12.