

MADRAS RECORD OFFICE

Government of Madras.

Judicial DEPARTMENT.

G.O. No. 481	<u>Press</u> <u>Mis.</u>
Dated 23.3.1867	

Not to be folded or roughly handled

11-15-23

Proceedings of the Madras Government, Judicial Department,

23rd March 1867.

No. 271. Read the following Proceedings of Government in the Public Works Department, dated 18th March 1867, No. 826.

Authorizing the enclosure wall of the Trichinopoly Central Jail being built with brick and stone in chunam, instead of sun-dried bricks in clay. (Vide Proceedings, Public Works Department, dated 18th March 1867, Nos. 403 & 404).

No. 272. ORDER THEREON, 23rd March 1867, No. 481.
Communicated to the Inspector General of Jails.

(Signed) A. J. ARBUTHNOT,
Chief Secretary.

To the Inspector General of Jails.

Exd. J. Tulloch.

N^o. 403. Read the following letter from the Superintending Engineer, 6th Division, to the Secretary to Government, Department Public Works, dated Covilady, 9th March 1867, No. 1,487 :—

1. With reference to paragraph 2 of G. O. No. 621, dated 28th ultimo, I have the honor to inform you that I have revised the estimates for the wall round the Central Jail, omitting the buttresses in the wall of sun-dried bricks in clay, and building three feet out of every fifteen feet of wall of stone in chunam. I have not deemed it prudent to alter the section of the wall, and the estimate now becomes Rupees 37,500.

2. In the revised estimate for the brick in chunam wall, I have provided for building only the eleven upper feet of brick in chunam and the lower five feet of roughly dressed stone in chunam, and I have proposed to point the brick work instead of plastering it; these changes reduce the estimate to Rupees 31,500, being Rupees 6,000 in favor of the pukka wall, this is due to the large section required for the brick in mud wall.

3. Colonel Greenaway assures me that he will be able to build the pukka wall quite as rapidly as that of sun-dried bricks in clay.

4. The foundations of the outer wall have been completed, with the exception of those of the northern recess, which are in abeyance, pending a reply to paragraph 1 of my letter No. 1,355 of the 15th ultimo.

5. The temporary barracks are being pushed on rapidly, and will probably be completed by the end of April.

No. 404.

ORDER THEREON, 18th March 1867, No. 826.

CIVIL WORKS, No. 42.

1. Under the explanation afforded in this letter, and on the assurance of the Superintending Engineer of the 6th Division that the enclosure wall of the Central Jail at Trichinopoly can be built with brick and stone in chunam more cheaply, and quite as rapidly, as with sun-dried bricks in clay, the Government sanction the use of the former description of material as proposed by Captain Oakes.

2. Paragraph 1 of the Superintending Engineer's letter, No. 1,355 of the 15th February 1867, is under consideration in the Judicial Department.

(no Extract.)

Colonel, R. E.,

Secretary to Government.

To the Superintending Engineer, 6th Division.

„ Judicial Department.

Lrd. S. T. Augustin.

Richard R. D. Phil

Oct 14 1853.

London Oct 1853. W. G. L.

From W. G. L. to W. G. L.

W. G. L. to W. G. L. No 826

W. G. L. to W. G. L.

W. G. L.

As the signing was a common
mode of the W. G. L. to W. G. L.
contact had being built
with W. G. L. to W. G. L.
= common instead of W. G. L.
- W. G. L. to W. G. L.

Oct 1853 letter 23 W. G. L.

Communication to the
W. G. L. to W. G. L.

W. G. L. to W. G. L.
W. G. L. to W. G. L.