

Local & Munl. (1898) Department.

MISCELLANEOUS.

G.O., No. 2352. Mis.

DATED 8th Feb. 1898.

INDEXED.

DESPATCHED

[Despatch Abstract.]

Tuvur - Harinarakundu Road:—

Communicating to the District Board
Malabar, G.O. P. W. Deptt., sanctioning
with remarks supplemental estimate
of Rs. 2,100 for constructing masonry
works on the —, in the Malabar
district.

8/2

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.


BUILDINGS AND ROADS.
CIVIL WORKS.

Government (1898) of Madras. PUBLIC WORKS.

247L

Recd. } 1898. Enclosures
Regd. } Spare copies 6

G.O., No. 90 W., 14th January 1898 W. 1898



n Order No. 235 *hms* 8/2/98

Communicated to the District Board, Malabar.

JANUARY.

V.A 8/2/98 *C.L.H* 8/2/98

To The Dist Bd Malabar
supd 9/2/98

Tuvur-Karivarakundu Road

Supplemental estimate of Rs. 2,100 for constructing masonry works on the —, in the Malabar district, sanctioned with remarks.

8/2/98
8/2/98

No. 90 W., 14TH JANUARY 1898.

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.Buildings and Roads.
Civil Works.

READ—the following papers :—

From J. HANNAN, Esq., Superintending Engineer, IV Circle, to the Chief Engineer, Public Works Department, dated Camp Coonoor, 20th October 1897, No. 576/W.

In continuation of this office endorsement, No. A./1, dated 22nd September last, on the Executive Engineer, West Coast Division's letter, No. 648/S.E., dated 18th idem, I have the honour to submit a plan and an estimate amounting to Rs. 2,050 for constructing masonry works on Tuvur-Karivarakundu road in Ernad taluk, Malabar district, and to request that you will be good enough to obtain the sanction of Government to the same as second supplemental to the estimate of Rs. 7,040 sanctioned in G.O., No. 1862 W., dated 12th July 1897.

Note by the Chief Engineer, Public Works Department.

The Chief Engineer considers that the depth of the rough stone apron of 10' culvert should be increased from 1½' to 2', and that the abutments and wings of 6' and 10' culverts should be given a batter. By these alterations the estimate has been raised from Rs. 2,050 to Rs. 2,100.

2. The depth of the soil in each case should have been mentioned. The thickness of foundations allowed in each case, viz., 1' for laterite and 2½' for loam, is sufficient.

8th January 1898.

(Signed) W. B. DEWINTON,
Ag. Chief Engineer.

ORDER—No. 90 W., dated 14th January 1898.

The estimate amounting to Rs. 2,100, as altered by the Chief Engineer for constructing masonry works on the Tuvur-Karivarakundu road, in the Malabar district, is sanctioned as supplemental to the estimates aggregating Rs. 12,190 sanctioned in G.Os., No. 1862 W., dated 12th July 1897, and No. 879 W., dated 29th March 1897.

2. There is a provision of Rs. 43,000 in the current year's budget for the road in question.

3. Attention is drawn to the Chief Engineer's note recorded above.

4. The sanction accorded in paragraph 1 has been registered as Provincial No. 76 W. of 1897-98 and classified as Communications—Original Works.

(True Extract.)

Summary
Under Secretary to Government.

To the Superintending Engineer, IV Circle, with five enclosures.

- " Examiner, Public Works Accounts.
- " Judicial Department.
- " Revenue Department.
- " Local and Municipal Department. ✓

Ed T. K. Narayana Aiyangar.

When given for copying _____
When copied _____
When examined _____
When signed 9/2 _____

189

READ AGAIN G.O., No. _____
189

DATED

CURRENT No.

ENCLOSURES TO C. No.

ORDER OF GOVERNMENT

LETTERS OF GOVERNMENT.

STATEMENT WITH DITTO.

PAPERS NOT FILED UP, BEING MEANT FOR DESPATCH
IN ORIGINAL.

N.B.—

- A = Copy in full.
- B = Not to be copied.
- F = Copy abstract only.
- Q = Copy heading only.