[L. & M.
2,000—13-6-98.]

Local & Munl. (1898) Department.

MISCELLANEOUS.

G.O., No. 788-P. Mis

DATED 12-8-98

[Despatch Abstract.]

evised Estimates Sanctioning the ____ of the Tungabhadra Camp and requesting that similar estimates for the Hospet camp may be submitted for the orders of Govt.

BACK PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.
7 LMd 637/06 C							

[L. & M. / 300-16-2-98.]

Papers to be read in Proceedings:—

Again G.O., No. dated 189 ,
Again G.O., No. dated 189 ,
Current No. of 189 , dated , from
,, ,, ,, 189 , ,, , ,,
,, ,, 11578 ,, 1898, ,, 1-8-98 , ,, Coll^r of Bellary

ORDER. No 788 P. mis. d/ 12-8-98

The revised estimates of the Temporary Labor camp are sanctioned. The plan of the camp is returned for revision and ~~return~~ resubmission.

2. Similar Estimates should be prepared for the Hospital camp and submitted for the orders of Gov

(Formaders)

12 8 98.

To the Coll^r of Bellary. with plan

9/8/98

Despd 13-8-1898.

12/8

Total 1,320

Again G.O., dated 189 , No.

Current No. of 189 , dated from the

Current No. 1187 P of 1898, dated 1-8-98 from the Collr of Bellary

SUBJECT

Cost of erecting Tungabhadra Camp

FOR ORDERS.

H.m. for favour of sanction

H.1
6.8.98

× These are marked × below

Sanctioned —
I see the shedding has worked out much cheaper than originally estimated. This is what I expected

9/8/98

The original estimate as framed by the Dt Board Engineer amounted to Rs 23,105. Some reductions were ordered by Govt & the Collr has made certain additions which were necessary. The total *actual* expenditure incurred on the camp is Rs 17,388. This includes the

Cost of disinfecting apparatus	—	Rs 2000
" of pumps & tanks for 2 wells	} —	1400

Grand Total — Rs 20,788

2. The following is an abstract of the detailed estimates:—

— ~~Works sanctioned by Govt~~

A. Commissioned medical officer's Camp

×	1. Shed (40'×32') ~~[illegible]~~ with punkah & cloth ceiling —	~~Rs [illegible]~~ Rs 820
×	2. Clerks' Shed —	132
×	3. Stables —	158
×	4. Kitchen —	130
×	5. Servants' Shed —	88
	Total	1,328

19.	Dispensary & medicine stores (16'×18')	105 ✓
20.	Store room (18'×16')	105 ✓
21.	Well	370
22	Miscellaneous	61
		7,156

Summary

A.	Commissioned medical officers camp	1,328
B.	Ry ~~Di~~ Inspection staff camp	2,641
C.	Disinfecting camp	1,894
D.	European Suspect camp	1,318.
E.	Native Suspect camp	2,871
F.	Plague Hospital camp	7,156
		16,908

Add

Levelling & clearing camp ground	200 ×
2 Sheds for storing dry earth	50 ×
1 Store shed	100 ×
2 Provision shops	50 ×
1 Butcher's shop	15 ×
1 Moveable latrine	20 ×
1 Incinerator	10 ×
Sundries	35 ×
	480
Total	17,388

3. The Estimates may be passed. The Coll: may be asked to send a revised plan of the camp for record in this office and to forward similar estimates for the camp at Hospet.

Leuy.
6/8/98

H.T.
6-8-98

Plague

Local & Munl. (1898) Department.

CURRENT No. 1187 P

SECRETARY TO GOVERNMENT LOCAL & MUNICIPAL DEPARTMENT
5.-AUG.-1898

Bellary Collector's Office,
Reg. No.................
3- AUG. 1898

Order

From the acting Collector of Bellary

Ref. on C No. 875-P.

Dated 1-8-1898
Received 5-8-1898
Registered 6-8-1898
Enclosures 8.
Spare copies

SUBJECT.

Submitting revised Estimates for the camps attached to the Plague Inspection Station at Tungabhadra

BACK PAPERS.

G.O.	No.	Department.	Date.

FURTHER PAPERS.

G.O.	No.	Department.	Date.

BELLARY COLLECTOR'S OFFICE.

No.

Dated 1 – 8 – 1898.

FROM E. A. Elwin Esquire

Acting COLLECTOR OF
BELLARY.

To

THE Secretary to Government Local
and Municipal Department

SIR, Ootacamund.

With reference to G.O 284 P/28.3.98, I have the honour to submit revised estimates, prepared by the Tahsildar of Adoni, for the Camps attached to the plague inspection station at Tungabhadra. The estimates are based on actual expenditure.

2. The Variations in the rates given for jungle wood posts, bressemers, thatching, and Concrete in Chunam are due to the fact that owing to the speed with which the Camps were constructed it was found impossible to obtain materials and labour for each particular sort of work at uniform

uniform rates. The rates entered for bamboo matting vary according to the thickness of the matting.

3. A comparative statement showing how the total of Rs 17,388 was arrived at is enclosed. It will be observed that in respect of the sheds originally estimated for by the Local Fund Engineer a saving of Rs 5,143 has been effected. As remarked in the statement, the revised estimates do not include the cost of the disinfecting boiler and of the pumps and tanks required for the 2 wells, which will amount to about Rs 3,400 in all.

4. The delay in the submission of the revised estimates is chiefly due to my desire to furnish estimates based as far as possible on actual expenditure.

I have the honour to be
Sir,
Your most obedient Servant.

Acting Collector

92/1-8-98

Statement showing the differences between the original and the revised estimates and the additional cost for erecting extra sheds not provided for in the Estimate.

No.	Name.	According to the original estimate submitted to Government	According to the present Estimate	Difference	Additional work not provided for in the original Estimate but now done —	According to the present Estimate	Total of Columns 4 & 7.	Remarks.
1	2	3	4	5	6	7	8	9
		Rs	Rs	Rs		Rs	Rs	
1	Disinfecting camp excluding cost of boiler	1745	1249	−496	Boiler shed	645	1894	In order to arrive at the total cost of the camps etc the following have to be added: — Rs
2	Native observation camp excluding cost of pump and tank	3440	2428	−1012	Shed over the bathing platform Police guard shed Shed for dry earth	106 37 25	2596	
3	European observation camp	1460	1318	−142	"	"	1318	Cost of boiler etc sanctioned in G.O. $\frac{352\text{ A P. mis}}{16-4-98}$ } 2,000
4	Railway inspection staff camp	3504	2641	−863	Moveable latrine	20	2661	
5	Plague hospital camp excluding pump and tank	9411	7156	−2255	Incinerator Shed for dry earth	10 25	7191	Approximate cost of pumps and tanks for the two wells, ordered but not received from Bombay, at Rs 700 for each well } 1400
6	Levelling and clearing	545	200	−345	"	"	200	
7	Sundries	55	25	−30	"	"	25	
8	"	"	"	"	Commissioned medical officer's camp	1328	1328	
9	"	"	"	"	Butcher's shop	15	15	
10	"	"	"	"	2 Provisions shops	50	50	
11	"	"	"	"	Boundary channel for the burning and burial ground	10	10	Rs 3,400
12	"	"	"	"	Store shed	100	100	
	Total	20160	15017	−5143		2371	17388	

Bellary Collector's Office
1-8-98

1-8-98

Acting Collector

REVENUE DEPARTMENT.

From
THE COLLECTOR OF
BELLARY.

To
THE

No.

Dated
Despatched
Received
189 .

Enclosures.
Abstract.

Memorandum of Abstract.

No.	Description of work	Amount		
1	Disinfecting Camp	1894	"	"
2	Native observation Camp	2571	"	"
3	European Observation Camp	1318	"	"
4	Railway Inspection staff Camp	2641	"	"
5	Plague Hospital Camp	7156	"	"
6	Commissioned medical officers Camp	1328	"	"
		16908		
7	Levelling & clearing the Camp ground	200	"	"
8	Sundries	25	"	"
9	Two Sheds for storing dry earth	50	"	"
10	Store Shed	100	"	"
11	Two provisions shops	50	"	"
12	one Butchers shop	15	"	"
13	Movable latrine	20	"	"
14	Incinirator	10	"	"
15	Digging boundary channel around the burning & burial ground	10	"	"
		480		
	Total Rupees	17388	"	"

25/7/98

Camp
Yemmiganuru
25-7-98
Fs

Tahsildar

1/1187 of 1898

District -- Bellary

Taluk --- Adoni

Memorandum of Abstract

Rupees 1738--"

6/1187

[illegible] Officers Camp

Estimate Form Detail Measurements.—(Continued) 40×32.

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Jungle wood posts 16 feet long -	12	-	-	-	12	12 No.
— Do 10 feet long	23	-	-	-	23	23 No.
Bressemmers including cross pieces -	-	312	-	-	312	312 R. feet
Bamboo mats threefold in jungle wood frames for walls						
Main building --	-	80	-	12	960	
Side (Gables) --	-	40	-	9	360	
Ends --	-	48	-	6	288	1608
Deduct for doors in front hall	2	7	4	-	56	
Bath room door --	1	6	3	-	18	
Windows --	4	4	3	-	48	
— Do	4	2½	2	-	20	142 1466 sqr. feet
Thatched roof with bamboos & bamboo mats complete -	2	25½	23	-	1173	
Ends --	2	17½	23	-	805	
Gable --	2	8	10	-	160	2138 sqr. feet
Raising floor with gravel -	-	46	38	¾	1311	1311 C. feet
Concrete for Bath room --	9	9	¾		60¾	61 C. feet
Brick in chunam wall	-	10	9	1	90	90 c ft.
Plastering with Portland cement -	-	10	10	-	100	100 sqr. ft.
Tarring posts --	35	4	2	-	280	
— Do mats --	2	168	¾	-	252	532 sqr. ft.
Punkah complete --	2	7	-	-	14	14 sqr. ft.
Ceiling cloth ---	-	32	16	-	512	512 sqr. ft.
Clerks shed (24 x 15) 1½ times of servants quarters in European observation camp	-	-	-	-		
Servants shed same as servants quarters -- do						
Stables 1½ times of clerks shed						
Kitchen —						
Carried over ...						

Estimate Form Detail Measurements.—(Continued)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Carried over ...						

Estimate Form Abstract.

Bellary

Construction of medical officers quarters 40 ft × 32 ft

Quantity.	Description of work.	Rate. Rs.	A.	P.	Per.	Amount. Rs.	A.	P.	Total. Rs.	A.	P.
35 No.	jungle wood posts										
312 R.ft.	Bressummers — —	1	12	-	each	61	-	-			
1466 sq. ft.	Bamboo mats three fold	-	4	-	R.ft.	78	-	-			
	in junglewood frames for walls }	10	-	-	100	147	-	-			
56 sq. ft.	jungle wood doors for front wall	-	9	-	sq. ft.	32	-	-			
68 do	— do — windows — —										
2138 do	Thatched roof with bamboos etc	-	7	-	do	30	-	-			
1311 cft.	Raising floor with gravel	11	12	-	100	251	-	-			
61 cft.	Concrete broken stone in chunam }	1	6	-	100	18	-	-			
90 cft.	Brick in chunam — —	15	-	-	do	9	-	-			
100 sq. ft.	Plastering with Portland cement }	15	-	-	do	14	-	-			
532 do	Tarring posts & mats — —	5	4	-	do	5	-	-			
14 R.ft.	Punkah Complete — —	1	4	-	do	7	-	-			
512 sq. ft.	Ceiling cloth — — —	1	-	-	R.ft.	14	-	-			
18 sq. ft.	Bath room door —	3	15	-	100	20	-	-			
	Total	-	4	-	sq. ft.	5	-	-			
						691	-	-	691		
	Sundries & superintendence at 10 per cent —					69	-	-			
	Double varandah — — —	-	-	-	-	60	-	-			
						820	-	-	820	-	-
	Clerks shed 24 × 15 ft 1½ times of servants quarters in European observation camp — — — — }	-	-	-	-	132	-	-	132	-	
	Servants shed same as servants quarters — do }	-	-	-	-	88	-	-	88	-	
	Stables 1⅕ times of clerks shed	-	-	-	-	158	-	-	158	-	
1	Thibetian — — — —	130	-	-	each	130	-	-	130	-	

Station Hissar

Dated 22-7-1898 }

Grand Total of Estimate Rs. 1328

Tahsildar

Local Fund Engineer.

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

Rev. Inspector
25-7-98

Plague

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

L. F. P. W.
Form No. 45.

District.— Bellary

Taluk.— Adoni

ESTIMATE FORM—ABSTRACT.

Rs 1328-"-"

No.—— (To accompany the Detailed Estimate of 189 9 for*)

Commissioned Medical Officer & Camp

*Here enter the Name and Description of work in full

1187

Estimate Form Detail Measurements—(Continued)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Assistant surgeons sheds	32×32 ft					
jungle wood posts 16 ft long	10	-	-	-	10	10 No
Bressemmers	-	232	-	-	232	R ft
jungle wood posts 10 ft long	16	-	-	-	16	16 No
Bamboos and bamboo tatty walls						
Main room	-	64	-	12	768	
Side pieces	5	8	-	9	360	
Varandah pieces	4	8	-	6	192	
Do	1	16	-	6	96	
					1416	
Deduct for doors	6	6	-	3	108	1308 sqr ft
Bamboo tatty doors	6	6	-	3	108	
Thatched roof with bamboos, bamboo mats &c Complete	4	17½	-	23	1610	1610 sqr ft
Raising floor with gravel	-	38	38	¾	1083	1083 c ft
Stone in chunam for bath room	-	9	9	½	40½	40½ C ft
Plastering with Portland cement	-	9	9		81	81 s ft
Tarring posts	26	4	2		208	
Do - mats all round	2	136	-	1	272	480 Sqr ft
General store shed 25 ft diameter						
jungle wood posts 21 ft long	1	-	-	-	1	1 No
Do 12 ft long	14	-	-	-	14	14 No
Bressemmers	-	78	-	-	78	78 R ft
Bamboos and bamboo mats all round	3	78		8½	663	
Deduct for doors	2	6	-	3	36	
Do windows	2	2½	-	2	10	617 sqr ft
Bamboo tatty doors	2	6	-	3	36	
Do windows	2	2½	-	2	10	46 sqr ft
Carried over ...						

NOTES.

Plague

NOTES.

L. F. P. W.
FORM No. 45.

DISTRICT.— Bellary

TALUK.— Adoni

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

ESTIMATE FORM—ABSTRACT.

Rs 2661

(To accompany the Detailed Estimate No. of 189 . for*)

Railway Inspection Staff Camp

*Here enter the Name and Description of work in full.

Disinfecting Camp

Estimate Form Detail Measurements.—(*Continued.*)

Date of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Waiting sheds (Two) 32 ft Diameter						
Jungle wood posts 21 ft long	1	.	.	.	1	No 1
Do 11 ft long	17	.	.	.	17	No 17
Bressemmer all round	-	100½	-	-	100½	Rft 100½
Bamboos and bamboo mats all round	.	100½	.	7	703½	
Deduct for door	1	6	.	3	18	685 Sqr ft
Bamboo tatty doors	1	6	.	3	18	
Do windows	8	2½	.	2	40	58 Sqr ft
Thatched roof with bamboo rafters and complete.	.	50	24	.	1200	1200 Sqr ft
Wooden circular perforated piece for the top.	1	.	.	.	1	No 1
Tin cap to cover the perforated piece of wood at top	1	.	.	.	1	No 1
Raising floor with gravel	.	area 1134	¾	.	850½	850 C ft.
Tarring posts	18	4	2	.	144	
Do mats all round	2	100	1	.	200	344 Sqr ft.
Bathing sheds (Two) 25 ft Diameter						
Jungle wood posts 19 ft long	1	.	.	.	1	No 1
Do 11 ft long	14	.	.	.	14	No 14
Bressummers all round	.	78	-	.	78	Rft 78
Bamboos & bamboo mats	.	78	-	7	546	546 Sqr ft
Bamboo tatty door.	1	6	-	3	18	
Do windows	7	2½	-	2	35	53
Thatched roof with bamboo Etc, complete.	-	44	17	-	748	748 Sqr ft
Carried over ...						

Estimate Form Detail Measurements.—(*Continued.*)

Detail of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Wooden Circular perforated piece at top	1	-	-	-	1	1 No.
Tin cap to cover the perforated piece at top	1	-	-	-	1	1 No.
Concrete broken stone in chunam	-	area 594	-	3/4	445 1/2	
For drain	6	1 1/4	1	7 1/2		
					7 1/2	453 cft.
Brick in chunam for cistern 3 ft sq. inside						
Foundation	-	5	5	1	25	
Superstructure	-	16	1	3	48	73 cft
Plastering with portland cement 1/4 inch thick for the floor of shed	-	area 594	-	-	594	
Drain to cistern	-	12	3	-	36	
Cistern floor	-	3	3	-	9	
Side walls of cistern	-	12	3	-	36	
do top	-	16	1	-	16	664 Sq. ft
Earth work excavation Cistern	-	5	5	4	100	
Drain	-	6	2	1	12	112 cft.
Iron bucket for emptying Cistern	1	-	-	-	1	No. 1
Tarring posts	15	4	2	-	120	
Do mats all round	2	78	1	-	156	276 Sq. ft
Shed for boiler						
Jungle wood posts 20 ft long	5	-	-	-	5	No. 5
Do 12 ft long	10	-	-	-	10	No. 10
Do Bessummers	-	238	-	-	238	Rft 238
Screen with Corrugated iron with rivets, bolts, Etc Complete	1	26	-	6	156	
Do ~~Carried over~~ ...	1	15	-	6	90	246 Sq. ft

Estimate Form Detail Measurements.—(*Continued.*)

Date of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Roofing with Corrugated iron sheets over jungle wood trusses. 10 ft apart, purlins Etc, complete with rivets, bolts, ridging Etc, complete front and rear.	2	38	16 1/2	-	1254	
Do ends	2	22	-	6/2	132	1386 Sq. ft
Raising floor with gravel	1	42	32	2	2688	2688 cft
Tarring posts	15	4	2	-	120	120 Sq. ft
Digging & concreting the foundation for keeping the sleepers beneath the boiler	4	4	2	1 1/2	48	48 cft
Pillars with burnt stone in chunam for keeping the iron stand	8	1 1/2	1 1/2	2	36	
Do beneath the disinfecting boiler	2	4	1 1/2	2	24	
Do for keeping the pipe	2	1 1/2	1 1/2	2	9	
Walls with burnt stone in chunam for the wheels of the disinfector to slide on	2	4	1 1/2	2	24	93 cft
Bamboos and bamboo mats for two sides of store room	2	15	-	6	180	180 Sq. ft
Carried over ...						

Estimate Form Detail Measurements.—(*Continued.*)

Detail of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward …						
Driver and fireman quarters 24×18						
Jungle wood posts 13½ ft long	6	.	.	.	6.	6 No
do 10¾ ft long	3	.	.	.	3	3 No
do Bressummers	-	120	-	-	120	120 Rft
Bamboos & bamboo mats Etc,	-	84	.	10	840	
Gables	3	6	.	5	90	
					930	
Deduct for doors	2	3	.	6	36	894 Sqrft
Bamboo tatty doors	2	3	.	6	36	
do windows	2	2½	-	2	10	46 Sqrft
Thatched roof with bamboos & bamboo mats Etc, complete front with verandah	1	26	18	.	468	
Rear	1	26	9	.	234	702 Sqrft
Tarring posts	9	4	2	.	72	
do mats	2	84	.	1	168	240 Sft
Raising floor with gravel	-	30	24	¾	540	540 Cft
Corrugated iron latrines	-	-	.	.	.	5 seats
Iron pans	-	-	-	-	.	5 No
Earth work excavating channels round the block (hard soil)	-	1500	2	2	6000	6000 Cft.
Kitchen for driver and fireman						
Jungle wood posts	6	.	.	.	6	6 No
Cross bars	-	58	.	.	58	58 Rft
Corrugated iron sheets for sides top with rivets &c Complete	-	area 270	-	-	270	270 Sqrft
Carried over …						

Estimate Form Detail Measurements.—(*Continued.*)

Date of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward …						
Tarring posts	6	4	2	.	48	48 Sqft
Forming rial oven of stone in mud	-	9	2½	3	67½	67½ cft
Tin chimney	1	.	.	.	1	1 No
Bamboo tatti door	1	6	.	3	18	18 Sqrft
Raising the floor with gravel	-	12	8	¾	72	72 cft
Carried over …						

Estimate Form Detail Measurements.—(*Continued.*)

Detail of Work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Carried over ...						

Estimate Form Abstract.

Quantity.	Description of work.	Rate. Rs.	A.	P.	Per.	Amount. Rs.	A.	P.	Total. Rs.	A.	P.
	Waiting sheds 32 ft diameter each.										
No 18	Jungle wood posts - . .	1 each	.	.	one	18	.	.			
Rft 100	Bressummers - . .	-	2	.	Rft	13	.	.			
Sqft 685	Bamboos & bamboo mats &c	3	8	.	100 Sqft	25	-	-			
58	Bamboo tatty doors & windows	5	2	-	100	3	.	.			
1200	Thatched roof with bamboos bamboo mats rafters &c complete - - -	10	.	.	100	120	.	.			
No 1	Tin Cap to cover perforated piece of wood at top	2	-	.	each	2	.	.			
No	Wooden circular perforated piece - - - - - -	4	.	.	do	4	.	.			
Cft 850	Raising floor with gravel	1	6	.	100	11	.	.			
Sqft 344	Tarring posts & mats	1	4	.	100	4	.	.			
						200					
	Sundries & Superintendance @ 5 per cent	-	-	-	-	10	.	.			
						210	.	.			
	Total for one shed -					210	.	.			
	Total for two sheds - - -					420	.	-	420	.	.
	Bathing sheds 25 ft diameter each.										
15	Jungle wood posts -	1	.	.	each	15	.	.			
Rft 78	Bressummers . . .	.	2	-	Rft	10	.	.			
Sqft 546	bamboos & bamboo mats	5	11	.	100 Sqft	31	.	.			
Sqft 53	bamboo tatty doors & windows	5	2	-	100 do	3	.	.			
748	Thatched roof with bamboos, bamboo mats &c complete	10	-	.	do	75	-	-			
						134	.	.	420	.	.

Grand Total of Estimate Rs

Station ________ }
Dated ________ 189 . }

Local Fund Engineer.

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

NOTES.

L. F. P. W.
Form No. 45.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

District.—

Taluk.—

ESTIMATE FORM—ABSTRACT.

(To accompany the Detailed Estimate No. — of 189 9 for*)

*Here enter the Name and Description of work in full.

Estimate Form Abstract.

Quantity.	Description of work.	Rate. Rs.	A.	P.	Per.	Amount. Rs.	A.	P.	Total. Rs.	A.	P.
	B - F1.					134	..	..	420	.	.
No. 1	Wooden circular perforated piece for the top	4	.	.	each	4	.	.			
No. 1	Tin cap to cover perforated piece at top	2	-	-	do	2	-	-			
C.ft 453	Concrete broken stone in chunam	13	.	.	100	59	.	.			
C.ft 73	Brick in chunam	15	.	.	100	11	.	.			
S.ft 664	Plastering with portland cement ¼ inch thick	5	4	.	100	35	-	-			
C.ft 112	Earth work	3	2	.	1000	.	.	.			
No. 1	Iron bucket for emptying cistern	2	.	.	each	2	.	.			
S.ft 276	Tarring posts & mats	1	4	.	S.ft 100	3	.	.			
						250	.	.			
	Sundries & Superintendence	-	-	-	-	13	.	.			
	Total for one shed					263	.	.			
	Total for two sheds	...				526	.	.	526	.	.
	Shed for boiler.										
No. 15	Jungle posts	1	8	.	each	23	.	.			
R.ft 238	~~B Do~~ Bressummers	.	3	.	R.ft	45	.	.			
S.ft 246	Screen with corrugated iron sheets with rivets bolts Etc complete	3	-		16 S.ft	46	.	.			
						114	.	.			
									946	.	.

Grand Total of Estimate Rs.

Station }

Dated 189 . }

Local Fund Engineer.

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

DISTRICT.—

TALUK.—

L. F. P. W.
FORM No. 45.

ESTIMATE FORM—ABSTRACT.

No. (To accompany the Detailed Estimate of 189 for*)

*Here enter the Name and Description of work in full

Estimate Form Abst

Quantity.	Description of work.	Rate. Rs.	A.	P.	Per.	Amount. Rs.	A.	P.
	B.7.				8 Sqft	114	..	9
Sqft 1386	Roofing with Corrugated iron sheets over jungle wood trusses 10ft apart purlins Ets with rivets bolts ridging Etc, Complete		5		each	433	—	—
Cft 2388	Raising floor with gravel	1	6	.	Cft 100	37	.	.
Sqft 120	Furring posts	1	4	.	Sft 100	1	.	.
180	Bamboos, & bamboo mats for sides of store room	5	–	–	100	9	.	.
Cft 48	Concrete in chunam	13	.	.	Cft 100	6	.	.
Cft 93	burnt stone in chunam	15	.	.	100	14	.	
	Sundries & Superintendance @ 5 per cent	—			—	31		
	Total:							
	Driver and Fireman Quarters—							
No 9	Jungle wood posts—	1	.	.	each			
Rft 120	do Bressummers	–	2	–	Rft			
Sqft 894	Bamboos & bamboo mats	5	–	–	100			
46	Tatty doors &c	5	2	–	100	2	.	.
702	Thatched roof with bamboo bamboo mats complete	10	–	–	100	70		
240	Furring posts Etc.	1	4	.	100	3		
540	Gravel flooring	1	6	.	100	0	.	.
	Sundries & Superintendance @ 5 per cent	—			—	994	.	.

G.

STATION
Dated 189

ate Rs

Fund Engineer.

NOTE. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and
3—Annas and Pice are to be excluded from the ost of each item being brought to the nearest Rupee. Totals of e to round numbers.

ors of Estimates should be prepared under
heads as are to be separately shown in the
Register of works, Work Vouchers, &c.)

DISTRICT.—

TALUK.—

L. F. P. W.
FORM No. 45.

ESTIMATE FORM—ABSTRACT

No. (To accompany the Detailed Estimate of 189 for*)

*Here enter the Name and Description of work in full.

Estimate Form Abstract.

Quantity.	Description of work.	Rate. Rs. A. P.	Per.	Amount. Rs. A. P.	Total. Rs. A. P.
	Latrines B 7				1751 . .
5 seats	Corrugated iron latrines	5 8 .	each	28 . .	
No 5	Iron pans	1 . .	do	5 . .	
					33 . .
	Kitchen for driver and fireman.				
6	Jungle wood posts	1 . .	do	6 . .	
Rft 58	Cross bars	. 2 6	do	9 . .	
Sqft 278	Corrugated iron sheets with rivets &c.	. 4 .	do	68 . .	
cft 72	Raising the floor with gravel	1 6 .	100	1 . .	
6 7½	Forming the fire oven of stone in mud	1 . .	each oven	1 . .	
No 1	Tin chimney	1 . .	each	1 . .	
sft 18	Bamboo tatty door	5 2 .	100	1 . .	
				87 . .	
	Sundries & Superintendence @ 5 per cent	—	—	3 . .	
					90 . .
500	Channelling hard soil	3 2 .	cft 1000	19 . .	
	Sundries & Superintendence @ 5 per cent	—	—	1 . .	
					20 . .
	Total.				1894 . .

STATION Ganjam
20 July 1898. Tahsildar 25/7/98

Grand Total of Estimate Rs

Local Fund Engineer.

NOTE. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

Plague

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

L. F. P. W.
Form No. 45.

District.— Bellary

Taluk.— Adoni

ESTIMATE FORM—ABSTRACT.

Rs1894-"-

(To accompany the Detailed Estimate No.—— of 189 -9 for*)

Disinfecting camp

*Here enter the Name and Description of work in full

European Observation Camp

60×28 ft

Estimate Form Detail Measurements.—(Continued)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Sheds for males mails 60×28 ft						
jungle wood posts 16 ft. long	13	–	–	–	13	13 No
Do 12 ft. long	28	–	–	–	28	28 No
Bressemmers all round	1	344			344	344 R.ft
Bamboo tatties all round	1	144	–	10	1440	
Do Gables	1	8	–	7	56	
Do Varanda rooms	–	48	–	9	432 1928	
Deduct for tatty doors	6	6	3	–	108	
Do Windows	3	6	3	–	54 162	1766 Sqr. ft.
Thatched roof with bamboo couples, reapers Etc reepers te Complete						
ront and rear	2	50	24½	–	2450	
Sides	2	15½	24½	–	759	3209 Sqr. ft.
amboo tatty doors	6	6	–	3	108	
Do windows	6	3	–	3	54	162 Sqr. ft.
ising floor with gravel	1	66	34¾	–	1683	1683 C.ft.
Laying posts	41	4	2	–	328	
Do mats all round	2	192	–	1	384	712
Shed for females 36×28 ft						
gle wood posts 16 ft. long	9				9	9 No
Do 12½ ft. long	20	–	–	–	20	20 No
ressemmers all round	1	244			244	244 R.ft
mboos and bamboo ts all round	1	156		12	1872	
luct for doors	8	6	–	3	144	1728 Sqr. ft.
Carried over ...						

Tl

Estimate Form Abstract.

Quantity		Rate.	Per.	Amount.	Total

Estimate Form Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Bamboo tatty doors - - -	8	6	-	3	144	
— do windows -	8	6	-	3	144	198 Sqr ft
Thatched roof with bamboos Etc Complete	2	25½	18	-	918	
Sides	2	16	18	-	576	1494 Sqr ft
Raising floor with gravel	-	42	34	¾	1071	1071 C ft
Tarring posts -	29	4	-	2	232	
— do mats	2	156	-	1	312	544 Sqr ft
Two sheds for two servants	24×10 ft					
jungle wood posts 10½ ft long -	6	-	-	-	6	No 6
Bressummers - - -	1	78	-	-	78	78 Rft
Bamboos & bamboo mats Etc	-	78	-	6½	509	
Deduct for doors	2	3	-	6	36	471 Sqr ft
Bamboo tatty door	2	6	-	3	36	
— do windows -	4	2½	-	2	20	56 Sqr ft
Thatched roof with bamboos Etc						
Front & rear	2	26	8½	-	442	442 Sqr ft
Raising floor with gravel	1	30	16	¾	360	360 C. ft
Tarring posts	6	4	-	2	48	
— do mats	2	78	-	1	156	204 Sqr ft
Excavating boundary channel	-	1840	2	2	7360	7360 C
Kitchen	12½ ft × 20					
jungle wood posts 12 ft long	2	-	-	-	2	No 2
— do 9 ft long	4	-	-	-	4	No 4
Cross bars - -	50 ft	-	-	-	50	50 Rft
Carried over ..						

Estimate Form Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Corrugated iron Sheets for sides & top with revets Etc Complete -	-	-	-	-	402	402 Sqr ft
Tarring posts - - -	6	4	2	-	48	48 Sqr ft
Raising floor with gravel	-	16	9	¾	108	C. ft
Forming pyal oven of stone in mud	-	12	2½	3	90	90 cft
Tin Chimney - - -	1	-	-	-	1	1 No
Bamboo tatty doors - -	1	6	-	3	18	18 Sqr ft
Corrugated iron latrines	2	-	-	-	-	2 seats each
Carried over ..						

Estimate Form Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of work.
		L.	B.	D.		
Brought forward ...						
Carried over ...						

Estimate Form Abstract.

Quantity.	Description of work.	Rate.			Per.	Amount.			Total		
Quantity.	Sheds for males	Rs.	A.	P.		Rs.	A.	P.	Rs.	A.	P.
No.	jungle wood posts	1	10	-	Each	67	-	-			
41 40 Rft.	Bressummers - - -	-	2	6	Rft.	54	-	-			
766 sq ft.	Bamboo tatties all round	5	11	-	100	100	-	-			
2	Bamboo tatty doors & windows	5	2	-	do	8	-	-			
73609	Thatched roof with bamboos Etc complete - - - -	10	-	-	do	321	-	-			
c ft.	Raising floor with gravel	1	6	-	do	23	-	-			
sq ft.	Tarring posts & mats -	1	4	-	do	9	-	-			
6 No.	Total					582	-	-			
50 Rft.	Sundries & superintendence at 5 Per cent					28	-	-	610	-	
	Total										
402 sq	Shed for females										
o.	jungle wood posts - - -	1	-	-	Each	29	-	-			
108 c ft.	Bressummers - - -	-	2	-	Rft.	31	-	-			
90C sq ft.	Bamboos & bamboo mats Etc	5	11	-	100	98	-	-			
No.	Bamboo tatty doors & windows -	5	2	-	do	10	-	-			
182 sq	Thatched roof with bamboos Etc complete -	10	-	-	do	150	-	-			
48 c ft.	Raising floor with gravel	1	6	-	do	15	-	-			
	Tarring posts & mats	1	4	-	do	7	-	-			
4 seat						340	-	-			
	Sundries & superintendence at 5 Per cent					17	-	-			
4	Total								357	-	
	Lean-Sheds for servants										
No.	jungle wood posts	1	[illegible]	0	Each	6	-	-			
Rft.	Bressummers - - -	-	2	-	Rft.	10	-	-			
1 sq ft.	Bamboos & bamboo mats Etc	3	8	-	100	16	-	-			
2	Bamboo tatty doors & windows -	5	2	-	do	3	-	-			
3	Thatched roof with bamboos Etc	9	-	-	do	40	-	-			
4	Raising floor with gravel	1	6	-	do	5	-	-			
5	Tarring posts & mats	1	4	-	do	3	-	-			
8	Total for one shed					83	-	-	967	-	C.O

Grand Total of Estimate Rs

STATION ____________ 189 }

Dated ____

Local Fund Engineer.

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

Tr

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

L. F. P. W.
FORM No. 45.

DISTRICT.— Bellary
TALUK.— Adoni

ESTIMATE FORM—ABSTRACT.

Rs 1318-..-..

No.—— (To accompany the Detailed Estimate of 189 .9 . for*)

European Observation Camp

*Here enter the Name and Description of work in full.

No. Observation Camp

Estimate Form Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Police guard huts (Two) 22 × 18 ft						
Jungle wood posts 15 ft long	12		-	-	12	No 12
Do 10 ft long	6		-	-	6	No 6
Bressummers to rooms & Varandas	-	228	-	-	228	Rft 228
Bamboos & bamboo mats	-	80	-	10	800	
Gables	2	6	-	5	60 860	
Deduct for doors	4	3	-	6	72	788 sft
Bamboo tatties for walls	:	80	:	10	800	
Gables	2	6	:	5	60	860 sft 1648 do
Bamboo tatty doors	4	3	-	6	72	
Do Windows	4	2½	-	2	20	92 sft
Thatched roof with bamboos &c complete. main room	2	24	18	..	864	
Varandah	2	24	9½	..	456	1320 sft
Raising floor with gravel	7	60	23	3/4	1035	1035 cft
Larring the posts	18	4	2	..	144	
Do mats all round in & out	2	160	1	-	320	464
Well 9 ft diameter	1					
1st lift of 6 feet hard soil & gravel soil		area 63½	-	6	381	381
2nd lift of 6 feet gravel soil & stony soil	-	63½	-	6	381	381
3rd lift of 6 feet Racy soil	-	63½	-	6	381	381
4th lift of 6 feet Do		63½	-	6	381	381
5th lift of 6 feet Do		63½		6	381	381
Excavating step way hard soil 1st lift	-	22	6	3	396	396
Carried over ...						

Estimate Eorm Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet. L.	B.	D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Excavating foundation ordinary soil						
Plat form	1	30	5	$\frac{3}{4}$	$112\frac{1}{2}$	
Drain	1	6	2	1	12	
Cistern	1	7	7	4	196	$321\frac{1}{2}$
Jungle wood posts	10	—	—	—	10	10
Bressemmers	1	68	—	—	68	68
Bamboos & bamboo mats	2	34	8	—	544	
do	2	10	8	—	160	
partition matting wall	1	10	8	—	80	784
Thatched roof	1	34	12	—	408	
Corrugated iron latrin						
Males, 10 seats ~~including~~ masonry and corrugated	10	seats	—		10	10 seats
Females — do — do	10	do			10	10 seats
Carried over ...						

Estimate Abstract.

Quantity.	Description of work.	Rate. Rs.	A.	P.	Per.	Amount. Rs.	A.	P.	Total. Rs.	A.	P.
—	Police Plague guard huts (two) 224/18 ft										
18 No	Jungle wood posts — —	1	—	—	Each	18	—	—			
228 sft	Bressemmers — —	—	2	—	sft	29	—	—			
1648 sft	Bamboos & bamboo mats &c	5	—	—	100	84	—	—			
92 do	Bamboo tatty doors & windows	5	2	—	100	5	—	—			
2184 do	Thatch roof with bamboos &c	9	—	—	do	119	—	—			
1035 cft	Raising floor with gravel	1	4	—	do	13	—	—			
464 sft	Tarring posts & mats	1	4	—	do	6	—	—			
						274	—	—			
	Sundries & superintendence at 5 per cent					14	—	—			
	Total Rs								288	—	
	Well 9 ft diameter										
777 cft	Earth work hard soil & gravel soil lift 6 ft lead 45 ft — —	5	5	—	1000 cft	4	—	—			
831 do	do Gravel soil & ~~Strong~~ Stony soil lift 12 ft lead 45 ft — — —	10	1	—	do	8	—	—			
381 do	do Rocky soil lift 18 ft	78	—	—	do	30	—	—			
381 do	do Rocky soil 24 ft lift	156	—	—	do	59	—	—			
381 do	do Rocky soil 30 ft — do	312	—	—	do	119	—	—			
112 do	Concrete broken stone in chunam	15	—	—	100	17	—	—			
123 sft	Plastering with port land cement ¼ inch thick — — — —	5	4	—	do	6	—	—			
	Refilling the well with filtering materials	—	—	—	—	75	—	—			
						318	—	—			
	Sundries & Superintendence at 5 per cent					52	—	—			
	Total Rs								370	—	
	Carried over								658	—	—

Grand Total of Estimate Rs

Station }

Dated 189 }

Local Fund Engineer.

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

Estimate Eorm Detail Measurements.—

NOTES.

MEA

DISTRICT.—

TALUK.—

L. F. P. W.
FORM No. 45.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

ESTIMATE FORM ABSTRACT.

(To accompany the Detailed Estimate No. of 189 , for)

Here enter the Name and Description of work in full.

Estimate Form Abstract.

Quantity.	Description of work.	Rate.			Per.	Amount.			Total.		
		Rs.	A.	P.		Rs.	A.	P.	Rs.	A.	P.
	Batting plat form 15×5 — —								2264	-	3.4
31 cft	Concrete broken stone in chunam	13	-	-	100	10	-	-			
130 do	Brick in chunam — —	15	-	-	100	20	-	-			
220 sft	plastering with portland cement	5	4	-	do	12					
321 cft	Earth work hard soil	3	2	-	1000	1	-	-			
1 No.	Iron bucket for emptying cistern — —	2	-	-	Each	2	-	-			
						45	-	-			
	Sundries & superintendence					2	-	-	47	-	
	Total										
10	jungle wood posts — —	1	-	-	Each	10	-	-			
8 cft	Bressummers — —	-	2	-	Do	9	-	-			
784 sft	Bamboos & bamboo mats for sides	5	11	-	100	45	-	-			
408 do	Thatch roof — — —	9	-	-	do	37	-	-			
						101	-	-			
	Sundries & superintendence at 5 per cent					5	-	-	106	-	-
	Total Rupees										
20 seats	Corrugated iron latrines	5	8	-	Each	110	-	-			
20 No.	Iron pans — — — —	1	-	-	Do	20	-	-	130	-	
	Total Rs										
7360	Earth work hard soil	3	2	-	1000	23	-	-			
	Sundries & superintendence at 5 per cent					1	-	-	24	-	
	Total Rs										

Grand Total of Estimate Rs 2571-

STATION Yemmiganuru

Dated 24-7- 1898.

Tahsildar

Local Fund Engineer.

NOTE. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each item being brought to the nearest Rupee. Totals of estimates need not be brought to round numbers.

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

Plague

DISTRICT.— Bellary

TALUK.— Adoni

L. F. P. W.
FORM No. 45.

ESTIMATE FORM—ABSTRACT.

No. of 189 . The Detailed Estimate for*

*Here enter the Name and Description of work in full.

Plague Hospital and Staff Camp

Estimate Form Detail Measurements.—(Continued)

Detail of work.	Number.	Measurements in Feet L.	Measurements in Feet B.	Measurements in Feet D.	Area or Contents.	Total Quantity of each description of work.
Brought forward ...						
Hospital Assistants shed 28×24 ft						
Jungle wood posts 15 ft long	6	-	-	-	6	6 No
do 10 ft long	14	-	-	-	14	14 No
Bressummers	1	208	-	-	208	208 Rft
Bamboos and bamboo mats around the main building	1	68	-	10	680	
Sides	4	6	-	8	192	
Varandha room	1	48	-	6	288	
					1160	
Deduct for doors	10	6	3		180	980 sft
Bamboo tatty doors	10	6	-	3	180	
do windows	4	2½	-	2	20	200 sft
Thatched roof with bamboos bamboo mats etc complete						
Front & rear	2	19	16½		627	
Ends	2	13½	16½		445½	1073 S.ft
Raising floor with gravel	1	34	30	¾	765	765 Cft
Tarring posts	20	4	2		160	
do mats all round	2	130	-	1	260	420 sft
Nurses Shed same as Hospital Assistants shed						
Shed for Assistant surgeon 32×32 ft						
Jungle wood posts 16 ft long	10	-	-	-	10	10 No
do 10 ft do	16	-	-	-	16	16 No
Bressummers	1	232	-	-	232	232 Rft
Bamboos & bamboo mats etc						
Main building	-	64	-	12	768	
Sides	5	8	-	9	360	
					1128	
Carried over ...						

Estimate Form Detail Measurements.—(*Continued*)

Detail of work.	Number.	Measurements in Feet.			Area or Contents.	Total Quantity of each description of work.
		L.	B.	D.		
Brought forward ...						
Drain	1	6	1/2	–	3	
Cistern floor	1	5	5	–	25	
Cistern side walls all round	1	20	3	–	60	
Do top do	1	24	1	–	24	112 sft
Excavating foundation						
Platform	1	24	12	3/4	216	
Drain	1	6	2	1	12	
Cistern	1	7	7	4	196	424 cft
Iron bucket	1	–			1	
Shed over the disinfecting platform						
jungle wood posts	8					
Bressemmers	1	60			60	60
Bamboos & bamboo mats	2	30	–	8	480	
do	2	14	–	8	224	704
Thatched roof	1	30	–	16	480	480
Excavating temporary channel to the Camp						
North of road	–	1984	2	2	7936	
do South of road	–	2660	2	2	10640	18576 cft
Carried over ..						

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount	Total.
1	2	3	4	5	6
	Hospital Assistants Shed	RS.		RS.	RS.
20 No	jungle wood posts — — —	1-0-0	each	20-0-0	
208 Rft	Bressemmers —	0-2-0	Rft	26-0-0	
980 sft	Bamboos & bamboo mats &c —	5-11-0	100	56-0-0	
200 do	Bamboo tatty doors & windows	5-2-0	do	10-0-0	
1073 do	Thatched roof with bamboos &c —	10-0-0	do	107-0-0	
765 cft	Raising floor with gravel	1-6-0	do	11-0-0	
420 sft	Tarring posts & mats —	1-4-0	do	5-0-0 235-0-0	
	Sundries & superintendence at 5 Percent			12-0-0	247-0-0
	Total Rs				
	Nurses shed same as Hospital				
	Assistants shed —				247-0-0
	Assistant Surgeons shed				
26 No	jungle wood posts — — —	1-0-0	each	26-0-0	
232 Rft	Bressemmers — — —	0-2-0	Rft	29-0-0	
1308 sft	Bamboos & bamboo mats &c	5-11-0	100	74-0-0	
138 do	Bamboo tatty doors & windows	5-2-0	do	7-0-0	
1610 do	Thatched roof with bamboos &c	10-0-0	do	161-0-0	
1083 cft	Raising floor with gravel — —	1-6-0	do	15-0-0	
41 cft	Concrete broken stone in chunam	18-0-0	do	5-0-0	
81 do	Plastering with port land cement	5-4-0	do	4-0-0	
460 Sq ft	Tarring posts & mats —	1-4-0	do	6-0-0 327-0-0	
	Sundries & superintendence at 5 Percent			16-0-0	
	Total Rs				343-0-0
	Carried over				837-0-0

Grand Total of Estimate ..

STATION——
Date—— 189 .

Executive Engineer.

10,000—20-3-95.

(E. No. 123).

Circle—

Division—

District—

Taluk (or Estate in case of Estate Works)—

ESTIMATE FORM.—Abstract.

Financial Head—

Budget Head—

Departmental Head—

Main Head—

Sub-Head—

Project of which the work forms part—

Section—

Name of Work—

Amount of Estimate, Rs.—

To be carried out by—

REFERENCES.

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount	Total.
1	2	3	4	5	6
		Rs.		Rs.	Rs.
	Plague Hospital camp Europeans Police guard sheds (2)				837-0-0 B F
18 No	jungle wood posts	1-0-0	Each	18-0-0	
234 Rft	Bressummers	0-2-0	Rft	29-0-0	
1668 Sq. ft	Bamboos & bamboo mats Etc	4-0-0	100	66-0-0	
98 Sq. ft	Bamboo tatty doors & windows	5-2-0	do	5-0-0	
1430 Sq. ft	Thatched roof with bamboos Etc	10-0-0	do	143-0-0	
1035 c ft	Raising floor with gravel	1-6-0	do	14-0-0	
468 Sft	Tarring posts & mats	1-4-0	do	6-0-0	
				281-0-0	
	Sundries & superintendence at 5	Percent		14-0-0	
	Total Rs				295-0-0
	European Hospital for males 3 wards				
30 No	jungle wood posts	1-0-0	Each	30-0-0	
312 Rft	Bressummers	0-2-0	Rft	39-0-0	
1576 Sft	Bamboos & bamboo mats Etc	5-11-0	100	90-0-0	
174 do	Bamboo tatty doors & windows	5-2-0	do	9-0-0	
[illegible] do	Thatched roof with bamboos Etc	10-0-0	do	284-0-0	
226 c ft	Brick in chunam	15-0-0	do	34-0-0	
1217 do	Concrete broken stone in chunam	13-0-0	do	158-0-0	
1622 Sft	plastering with portland cement	5-4-0	do	85-0-0	
124 c ft	Earth work	3-2-0	1000	1-0-0	
608 Sft	Tarring posts & mats	1-4-0	100	8-0-0	
				672-0-0	[illegible]
	Sundries & Superintendence at 5	Percent		34-0-0	
	Total Rs				706-0-0
	Carried over				1838-0-0

Grand Total of Estimate ..

Station—
Date— 189 .

Executive Engineer.

10,000—20-3-95.

(E. No. 123).

CIRCLE—

DIVISION—

DISTRICT—

TALUK (OR ESTATE IN CASE OF ESTATE WORKS)—

ESTIMATE FORM.—Abstract.

Financial Head—

Budget Head—

Departmental Head—

Main Head—

Sub-Head—

Project of which the work forms part—

Section—

Name of Work—

Amount of Estimate, Rs.—

To be carried out by—

REFERENCES.

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount	TOTAL.	
1	2	3	4	5	6	
		RS.		RS.	RS.	
	European Hospital for females (2) wards ¾ of European male Hospital	-	-	-	1838— 530—	B. 4
	Two Sheds for servants ⅛th more than servants shed in Railway Inspection Staff Camp	-	-	-	200—	
	Duty Room and food store					
15 No.	jungle wood posts	1—	each	15—		
144 rft.	Bressemmers	0-2-0	rft.	18—		
1054 sft.	Bamboos & bamboo mats etc	5-11-0	100	60—		
56 sft.	Bamboo tatty doors & windows	5-2-0	do	3—		
912 sft.	Thatched roof with bamboos etc	10-0-0	do	91—		
320 do	Tarring posts & mats	1-4-0	do	4—		
684 do	Raising floor with gravel	1-6-0	do	9— 200—		
Contingencies & Superintendence at 5 Percent				10—	210—	
	Total Rs.					
	Dispensary & medicine store ½ of duty room & food store				105—	
	Store room half of duty room and food store				105—	
	Carried over				2988—	

Grand Total of Estimate ..

STATION—
Date— 189

Executive Engineer.

(E. No. 123).

Circle—

Division—

District—

Taluk (or Estate in case of Estate Works)—

ESTIMATE FORM.—Abstract.

Financial Head—

Budget Head—

Departmental Head—

Main Head—

Sub-Head—

Project of which the work forms part—

Section—

Name of Work—

Amount of Estimate, Rs.—

To be carried out by—

REFERENCES.

ESTIMATE FORM.—Abstract.

Quantity.	Description of Work.	Rate.	Per	Amount	Total.
1	2	3	4	5	6
		RS.		RS.	RS.
	Shed over bathing plat form				5051-..-.. B. 4
8	jungle wood posts	1-..-..	Each	8-..-..	
36 rft	Bressemmers	0-2-0	do	5-..-..	
444 sft	Bamboos & bamboo mats	5-..-..	100	24-..-..	
216 sft	Thatched roof	9-..-..	100	20	
				57-..-..	
	Sundries			3-..-..	
				60-..-..	60-..-..
	For two sheds				120-..-..
	Bathing plat form for females same as above				45-..-..
	Relation sheds same as Police Guard Shed in Railway inspection Staff Camp				328-..-..
	Servants sheds do				328-..-..
9 seats	Corrugated iron latrine for males & females	5-8-..	Each	50-..-..	
9 No.	Iron pans	1-..-..	Each	9-..-..	
	Total				59-..-..
5 No.	Corrugated iron kitchen	120-..-..	Each	600-..-..	600-..-..
	one well	—	—	—	370-..-..
	Disinfecting plat form				
260 cft	Concrete work in stone in chunam	13-..-..	100	33-..-..	
219 cft	Brick in chunam	15-..-..	do	33-..-..	
406 sft	plastering with Portland cement	5-4-..	do	21-..-..	
424 cft	Earth work hard soil	3-2-..	1000	1-..-..	
1 No.	Iron bucket	2-..-..	Each	2-..-..	
	one shed over the disinfecting plat form				
8 No.	jungle wood posts	1-..-..	Each	8-..-..	
60 rft	Bressemmers	0-2-0	do	8-..-..	
704 sft	Bamboos & bamboo mats	5-..-..	100	36-..-..	
	Carried over			142-..-..	6901-..-..

Grand Total of Estimate ..

Station——

Date—— 189 .

10,000—20-3-95.

Executive Engineer.

(E. No 123).

Circle—

Division—

District—

Taluk (or Estate in case of Estate Works)—

ESTIMATE FORM.—Abstract.

Financial Head—

Budget Head—

Departmental Head—

Main Head—

Sub-Head—

Project of which the work forms part—

Section—

Name of Work—

Amount of Estimate, Rs.—

To be carried out by—

REFERENCES.

Estimate Form Abstract.

6

Quantity.	Description of work.	Rate.			Per.	Amount.			Total.		
		Rs.	A.	P.		Rs.	A.	P.	Rs.	A.	P.
80 sft ”	Thatched roof — — —					142	–	–	6901	–	–
		9	–	–	100	43	–	–			
	Sundries at 5 percent —					185	–	–			
						9	–	–			
	Total —								194	–	”
576 cft ”	Earth work hard soil	3	2	–	1000	58	–	–			
	Sundries at 5 percent —					3	–	–			
	Total Rs —								61	”	”

tion Yemmigaanur
d 24-7- 1898.

Grand Total of Estimate Rs 7156

Tahsildar

Local Fund E

Note. 1—Quantities are to be entered as so many units.
2—All rates are to be quoted in Rupees, Annas and Pies.
3—Annas and Pies are to be excluded from the Abstract Estimates, the cost of each ite
brought to the nearest Rupee. Totals of estimates need not be brought to round n

Plague

NOTES.

Abstracts of Estimates should be prepared under such sub-heads as are to be separately shown in the Accounts (Register of works, Work Vouchers, &c.)

L. F. P. W.
FORM No 45.

DISTRICT.— Bellary

TALUK.— Adoni

ESTIMATE FORM—ABSTRACT.

Rs 7156-0-0

No.——(To accompany the Detailed Estimate of 189 .9 . for*)

Plague Hospital Camp — — — —

*Here enter the Name and Description of work in full.

1/7/8/1898

gineer.

a being
umbers.

& M.
-13-6-98.

opying ——
ined ——
189 .

AGAIN G.O, No. , DATED
189 .

NCLOSURES TO C. No

OF GOVERNMENT .. .. .. A A A A A A A

GOVERNMENT.

WITH DITTO.

FILED UP, BEING MEANT FOR DESPATCH
ORIGINAL.

A = Copy in full.
B = Not to be copied.
P = Copy abstract only.
Q = Copy heading only.