M.R.O. 1—23 400—23-11-89

MADRAS RECORD OFFICE.

Government of Madras.

Political DEPARTMENT.

Cons. 16 6 5 1

G.O. No. 1112 Press Mis.

Dated 16 6 18 93

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 16th June 1857.

No. 7. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 29th May 1857, No. 770.

SIR,

I have the honor to submit under Clause II, Extract Minutes Consultation, No. 696, dated 18th October 1855, an estimate amounting to Rupees (65) sixty-five, for renewing the boundary pillars of Tondiarpett, and under the circumstances set forth by the Collector of Madras in a letter No. 32, dated 17th March last, to the Revenue Board (the data upon which the estimate has been prepared being moderate but sufficient) I recommend that the expense be borne by Government, and that the estimate amounting to Rupees (65) sixty-five receive early sanction.

No. 8. ORDER THEREON, No. 1112; dated 10th June 1857.

The Right Honorable the Governor in Council sanctions, on emergency, the estimate submitted with the foregoing letter, amounting to Rupees (65) sixty-five, for renewing the Boundary pillars of Tondiarpett.

(Signed) H. FORBES,
Acting Secretary to Government.

Buildings (Revenue) (New Work) 2

Abstract of Estimate № of 185 5

District. Madras.

Work. Reconstructing Masonry Boundary Pillars between the limits of the Madras Collectorate in Tondiarpett in 1857.

Quantities	Description of Work.	Rate. Rs	a.	P.	Amount. Rupees.	Amount of each part. Rupees.
C. Yds.						
16	Laterite Stones engraved with two letters, each, including carriage hire ____ of Stone	1	1	"	17	17
123/4	Cubic Ft. Brick in Chunam ₹/ft	"	1	8	1	
	Carriage hire and excavating foundation ____				1	
25	Superficial Ft. Plastering ₹/100 ft	2	"	"	1	
	Total for 1 Pillar ____				3	
	For 15 of the above ____				37	
	Superintendence ____				8	
						48
					Total Company's Rupees	65

Central Office of P. W.
Fort St. George
29 May 1857

A. Taylor Colonel
Chief Engineer D. P. W.

Enclosure.

In Letter

From

The Chief Engineer
P. P. W.

To

The Secretary to Govt.
P. P. W.

Dated 29th May/57
Received 3rd June/57

No. 770

Abstract Estimate of the expense of Reconstructing Masonry Bound Pillars to show the limits of the Madras Collectorate in Jondiarpet in Madras.

Amt. to Co's Rupees. 65—0—

P.W. 1102/57

15 June No. 7

Public

Enclosures Three
One A. Pro. of Nov. 6th
One Letter
One Estimate

No. 770

From Colonel E. C. Fenton
The Chief Engineer
To
The Secretary to Government F.P.W.

Sir,

I have the honor to submit under Clause II Ext. Mem. Con. No. 696 dated 18th October 1853, an Estimate amounting to Rupees 65 sixty five, for renewing the Boundary pillars of Jondiarpet, and under the circumstances set forth by the Collector of Madras in a letter No. 32 dated 17th March last, to the Revenue Board, the date upon which the Estimate has been prepared being moderate but sufficient, I recommend that the Expense be borne by Government, and that the Estimate Amounting to Rupees 65 sixty five receive early Sanction

I have the honor to be
Sir
Your Most Obed Servant
E. C. Fenton Colonel
Chief Engineer

Fort St. George
29th May 1857

Compd. D. Gray

Pub: Works 1857 Department.
Dº to Cons 16th June.
Nº 1102

From. The Chief Engineer D.P.W.
To. The Secretary to Government Public Works Depart.

Dated 2d May 1857.
Rec'd
Encs: 3 R. 7.7.0

Submitting for sanction an Estimate amounting to Rupees 65 for renewing the Boundary Pillars of Pondicherry.

Sanction order
Nº 1112. 10th June

Nº 1112

The Right Honorable the Governor in Council sanctions on emergency, the Estimate submitted with the foregoing letter, Amounting to Rupees 165/ sixty five, for renewing the Boundary pillars of Pondicherry.

J. W. St. George
10th June 1857

To Copies to the Chief Engr with 2 Encls. Dept. - 11

1748.

C4 June R8