8
18.7.37

M.R.O. 1—82 406—22-11-30

MADRAS RECORD OFFICE.

Government of Madras.

Revenue 1945 DEPARTMENT.

Conv. 23-2-57

G.O. No. 1192 Press Mis.

Dated 20-6-18 57

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 23rd June 1857.

No. 59. Read the following Report from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 2nd June 1857, No. 863.

Report A. on an estimate prepared by Supervisor Porter for building Barracks for 10 married Soldiers at Ramandroog.

Amount of Estimate Rupees (16,200) sixteen thousand, and two hundred, comprising the following items, the details of which are given in the accompanying abstract.

	Rs.
Barrack	12,067
Cookroom	1,089
Necessary for women	588
Covered passage to do.	693
Necessary for men	588
Superintendence and Sundries	1,175
Total ...	16,200

1. The Barrack is to be raised on a basement 2 feet in height above foundations, which are to be sunk 3 feet, the principal walls are to be 18 feet high, and the verandah walls 12 feet 6 inches supporting a terraced roof.

2. The Barrack is to contain 20 Rooms.

10 Rooms each	16′ long,	by 14′ broad
8 Bath do.	14′ ,,	by 8′ ,,
2 do. do.	26′ ,,	by 8′ ,,

with an open verandah in front, and in part at the ends, in all 222 feet long, by 10 feet broad.

3. The Cookroom is to be 36 feet long, by 14 feet broad, and the walls, resting on foundations to be sunk 3 feet, are to be 13 feet high, supporting a terraced roof.

4. The Necessaries are to be 20 feet long, by 10 feet broad, with the same depth of foundations, and height of walls as the Cookroom; the roof being also terraced.

5. The covered passage leading to the women's necessary, is to be 50 feet long, by 9 feet broad, the terraced roof being supported on pillars, with screen walls between 13 feet high, the foundations being 3 feet in depth.

6. In Extract Minutes Consultation No. 2115, dated 12th November 1856, para 2. Government observed, that the married men's quarters at Ramandroog were very insufficient, and incomplete, and called for the immediate preparation of an estimate for building a separate set of rooms. The present buildings to be given up to the unmarried Non-Commissioned Officers, a communication by an archway being made from each through the partition wall, into the large Barrack rooms adjoining.

7. The above order was communicated to the Collector, and District Engineer of Bellary, with Extract from Proceedings No. 8142, 17th November 1856, and in a letter No. 10918, 13th March 1857, the Officer Commanding Ceded Districts, was requested to be good enough to call upon the District Engineer to expedite the submission of the Plan and Estimate.

8. The Plan and estimate called for, were forwarded by the District Engineer with a letter No. 35, 20th January 1857, and were returned with Extract from Proceedings No. 9973, 2nd February 1857 to be revised in accordance with the orders from the Honorable Court of Directors, as conveyed in Extract Minutes Consultation, No. 162, 22nd January 1857.

9. The revised Plan and Estimate were returned by the District Engineer with his letter No. 275, 21th March 1857, and were forwarded to the Quarter Master General for the opinion of His Excellency the Commander in Chief, with a letter No. 12082, 25th April 1857.

10. To the estimate received from the District Engineer, a sum of Rupees five hundred and eighty-eight (588) has been added for constructing a separate Necessary for the men, as proposed in the accompanying copy of letter No. 1233, 27th April 1857, from the Quarter Master General signifying His Excellency the Commander in Chief's approval of the Plan.

11. The rates allowed for the work are moderate and sufficient, and the Chief Engineer recommends the estimate for entry in the Budget of 1858-59.

12. The two smaller estimates which accompany this report, and which have been laid before His Excellency the Commander-in-Chief, are recommended by the Chief Engineer for immediate sanction viz. Rupees (150) one hundred and fifty, for opening§ 8 archways in the present Barracks at Ramandroog, and

§ In Extract Minutes Consultation No. 2115, 12th November 1856.

Rupees (225) two hundred and twenty-five, for putting up arm racks, and accoutrement shelves in the same.

No. 60. ORDER THEREON, No. 1198; dated 20th June 1857.

Referred to the Military Department for consideration with reference to Extract Minutes Consultation in that Department dated 21st October 1856, No. 2714.

(Signed) H. FORBES,
Acting Secretary to Government.

Central Office of P.W.D.
Fort St George 2nd June 1857.
No 863
3

Belgaum District

"Military"
Barracks

Report on an Estimate prepared by Superintendent Porter for building Barracks for 10 Married Soldiers at Ramandroog.

Amount of Estimate Rupees (16,200) Sixteen Thousand and two hundred, comprising the following items, the details of which are given on the accompanying Abstracts.

Barracks	Rs 12,067
Cook Rooms	" 1089
Necessary for Women	" 588
Covered passage to do	" 693
Necessary for Men	" 588
Superintendence and Sundries	1175
Total Rupees	16,200

1.- The Barracks is to be raised on a basement 2 feet in height above foundations, which are to be sunk 3 feet, the principal walls are to be 18 feet high, and the Verandah walls 12 ft. 6 in supporting a terraced roof.

2.- The Barracks is to contain 20 Rooms

10 Rooms each - 16' long, by 16' broad
8 Baths do — do — 16' — " — by 8' — " —
2 — do — do — 26' — " — by 8' — " —

with an open Verandah in front and in part at the ends, in all 222 feet long, by 10 feet broad.

The

3.- The Cook Room is to be 36 feet long, by 14 feet broad, and the walls, resting on foundations to be sunk 3 feet, are to be 13 feet high, supporting a terraced roof.-

4.- The necessaries are to be 20 feet long, by 10 feet broad, with the same depth of foundations, and height of walls as the Cook Room: the roof being also terraced.-

5.- The covered passage leading to the Women's necessary, is to be 30 feet long, by 9 feet broad, the terraced roof being supported on pillars, with screen walls between 3 & 4 feet high: the foundations being 3 feet in depth.-

6.- In Extract Minutes Consultation No 2115, dated 12th November 1836, para 2nd, Government observed, that the Married Men's Quarters at Vaniambaddy were very insufficient, and incomplete, and called for the immediate preparation of an Estimate for building a separate set of rooms- the present buildings to be given up to the unmarried Non-Commissioned Officers, a communication by an Archway being made from each through the partition wall, into the large Barrack rooms adjoining.-

7.- The above Order was communicated to the Collector, and District Engineer of Bellary with Extract from Proceedings No 8142- 17th November 1836, and in a letter No 1098- 13th March 1837, the Officer Commanding Ceded Districts, was requested to be good enough to call upon the District Engineer to expedite the submission of the Plan and Estimate.-

The

8.- The Plan and Estimate called for, were forwarded by the District Engineer with a letter No 35- 20th January 1837, and were returned with Extract from Proceedings No 9973- 2nd February 1837 to be revised in accordance with the orders from the Honorable Court of Directors, as conveyed in Extract Minutes Consultations No 162- 22nd January 1837.

9.- The revised Plan and Estimate were returned by the District Engineer with his letter No 275- 24th March 1837, and were forwarded to the Quarter Master General for the opinion of His Excellency the Commander in Chief, with a letter No 1208- 25th April 1837.-

10.- To the Estimate received from the District Engineer, a sum of ~~Five hundred~~ Eight Hundred & Eighty Eight (588) has been added for constructing a separate necessary for the mess, as proposed in the accompanying Copy of letter No 1233- 27th April 1837, from the Quarter Master General signifying His Excellency the Commander in Chief's approval of the Plan.-

11.- The rates allowed for the work are moderate, and sufficient, and the Chief Engineer recommends the Estimate for entry in the next Budget of 1838/39.-

12.- The two smaller Estimates which accompany this Report, and which have been laid before His Excellency the Commander in Chief, are recommended by the Chief Engineer for immediate sanction &

Rupees (150) One hundred and fifty, for

opening

opening Archways in the present Barracks at Ramandroog, and

Rupees (225) two hundred and twenty five for putting up Arm Racks, and accoutrement Shelves in the same.

To Govt. Engrs Letter No. 215. 12 Nov. 56.

Central Office of P.W.D.
Fort St. George 2nd Jan. 1857.

Chief Engineer

A.W. Sep. Engr. N.C.

To The Secretary to Government P.W. Department.

List of Enclosures

1 Letter from the Asst. Engineer Bellary, dated 24th March 1856. - No. 275 - with Estimate A.
1 Copy of a letter from the Dy. Adjt. Genl. of the Army dated 27th April 1857. No. 1233 A.
1 Abstract Estimate for Rs. 16200 A.
1 — do. — do. — for Rs. 150 A.
1 — do. — do. — for Rs. 225 A.
1 Revised Plan A.

149

Cons 27th Jany 57. Nos 47. 48
" 18th Nov 56 " 13.
" 4th " " " 83 & 84

Public Works 1857 Dept II
Do to Cons 23rd June
No 1140 A

Sir,
The Chief Engineer
&c &c &c
The Secretary to Government
&c &c &c
Public Department

No 1198.

Referred to the Military Department for consideration with reference to Exct Mins: Cons: in that Department dated 21st October 1856 No 2714.

Dated 2nd June 1857.
No 874

5 Enclosures
Exd: from Mr. Asst Dept. 3rd June 4th
4 Nos 148 Inclosures 28

Forb 3rd Geo:
20th June 1857

No 863

Respecting the Public Dept.
with 5 Enclos
Dispt 22nd

Respecting an Estimate of Rupees 11,960 for building Barracks for 10 Dooried Companies at Ramandroog in the Bellary District recommended for entry in the Budget of 1858/59.

Also recommends two Estimates for immediate Sanction.

Rupees 150 for opening 8 Archways in the present Barracks at Ramandroog and.

Rupees 225 for putting up Arms Racks and accoutrement Shelves in the same.

No 59 & 60.

William Oliver
No 1198 - 20th Cons