1. Number of pcs. 6
2. Date of receipt 29.4.57
3. Initials & reference

M.R.O. 1—82,400—23-12-50

# MADRAS RECORD OFFICE.

---

## Government of Madras.

Public Works DEPARTMENT.

Cons. 18-8-57

G.O. No. 1500 Press Mis.

(565)

Dated 18 — 8 — 1857

***Not to be folded or roughly handled***

No. 56. Read the following Report from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 3rd August 1857, No. 2615.

Report F, on an estimate prepared by the late Acting District Engineer of Ganjam, for constructing Moonsiff's Court Houses at Berhampore, and Palasah.

Amount of estimate, Rupees (2,300) two thousand, and three hundred, comprising the items shown in the accompanying Abstract, being Rupees (1,150) one thousand, one hundred and fifty, for each Court House.

1. The buildings are to be raised on basements 2 feet in height above foundations, which are to be sunk 3 feet, the principal walls and pillars are to be 12 feet high, and the Verandah walls and pillars 6 feet, supporting tiled roofs.

2. The buildings are, each to contain 4 rooms;
   1 Middle room, 15 feet square.
   1 Court room 38 feet long, by 25 feet broad, including front, and side Verandahs.
   1 Verandah room 15 feet long, by 10 feet broad.
   1 do. 19 feet long, by 10 feet broad.
   and open Verandahs measuring in length 34, 6 long, by 10 feet broad.

1. No. 466, dated 7th May 1857.
2. Dated 22nd June 1857.

3. The letters noted in the margin, from the late Acting District Engineer,[1] and Court of Sudder Udalut,[2] are submitted with his Report, and the estimate being framed on moderate and sufficient data, is recommended by the Chief Engineer for entry in the Budget of 1858-59.

4. The standard plan for Moonsiff's Courts is also submitted, from which it will be seen that in the revised plan, prepared at the requisition of the Sudder Udalut, the dimensions of the rooms have been somewhat increased, but as they are still very moderate, the Chief Engineer recommends that the present plan be adopted as the future standard, as having received the special approval of the Judges of the higher Court. The plan will on sanction be lithographed for general adoption.

---

No. 57. ORDER THEREON, No. 1600; dated 18th August 1857.

Referred to the Judicial Department for consideration.

(Signed) H. FORBES,
*Acting Secretary to Government.*

Ganjam District

Judicial

Moonsiffs Court Houses

No. 2615

R 3

Report on an Estimate prepared by the Actg. District Engineer of Ganjam for constructing Moonsiffs Court Houses at Berhampore, and at Palacahd.-

Amount of Estimate, Rupees [2,300.] Two thousand and three hundred, comprising the items shown in the accompanying Abstract, being Rupees [1150] One thousand One hundred and fifty, for each Court House.-

1. The Buildings are to be raised on basements 2 feet in height above foundations, which are to be sunk 3 feet; the principal walls and pillars are to be 12 feet high, and the Verandah walls and pillars 6 feet, supporting tiled roofs.-

2. The Buildings are, each to contain 4 rooms.

1. Middle room, 15 feet Square.

1. Court room 38 feet long, by 25 feet broad, including front, and side Verandahs.-

1. Verandah room 15 feet long, by 10 ft. broad.

1. do 19 feet 1 in. by 10 feet broad.

and open Verandah measuring in en
length 34 - 6 in. by 10 feet broad.-

3. The letters noted in the Margin, from the late Acting District Engineer and Court. of Sudder Adalut, are submitted with this Report, & the Estimate being framed on moderate and sufficient data, is recommended by the Chief Engineer for entry in the Budget of 1858/59.—

4. The Standard plan for Reconstruction Courts is also submitted, from which it will be seen that in the revised plans, prepared at the requisition of the Sudder Adalut, the dimensions of the rooms have been somewhat increased, but as they are still moderate, the Chief Engineer recommends that the present plans be adopted as the future Standard, as having received the special approval of the Judges of the higher Court. The plans will on sanction be lithographed for general adoption.—

Central Offices of P.W.
Fort St. George
3 August 1857

Alexander Colonel
Chief Engineer

To
The Secretary to Government
Public Works Dept.

List of Enclosures

F1 1 Letter from the Actg. Supdt. Engr. dated 22nd June 1857. with Enclosure

F2. 1 Abstract Estimate

F3 & 4 2 Plans.

F6. 1 Revised do (Lithographed)

No. 1600

Referred to the Judicial Department for consideration —

[illegible]

Fort St. George 18th Augt. 1857

2 Copies to the Judl. Dept. with 2 Encls. & 19 Papers

Public Works 1857. Aug. 18 F
From Chief Engineer
No. 1558 Dated 18th August
To Secy. to Govt. Dated 3 Dec. 4 Leaves August 1857
Enclosures 5.
No. 2615
L. Last Dft. 15. Oct. 57 6 No. 2070 - 6 - 19

Forwards and Estimate of Charges 2503. Pagodas required for Establishg. Public Engineer & Salaries for Executive Engineer Civil Court House and Assistant Engineer and Salaries for establishg. in Budget of 1858/59. -

No. 56 & 57.

Write an Order -
No. 1600. 18th August
L