1. Number of pages.

7

M.R.O. 1—52,400—28-11-50.

MADRAS RECORD OFFICE.

Government of Madras.

Judicial Works DEPARTMENT.

Cons 25-8-57

G.O. No. 613 Press Mis.

Dated 19 — 8 — 18 57

Not to be folded or roughly handled

No. 16. Read the following Report from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 3rd August 1857, No. 2615.

Report G on an estimate prepared by the District Engineer Godavery Division, for improvements to the Staff Serjeant's Quarters at Samulcottah, in the Rajahmundry District. Amount of estimate Rupees (1,310) one thousand, three hundred and ten, comprising the items, shewn in the accompanying Abstract.

1. The improvements consist of 2 additional rooms to the main building 22½ feet long, by 10 feet broad, with an open verandah in front of the building 7′ 6″ broad, the whole to be raised on a basement of 1′ 6″ in height above foundations, which are to be sunk 3 feet. The walls are to be 14¾ feet high, and the verandah pillars 6′ 6,″ of 1 additional room to the Cook room, 14 feet long, by 10 feet broad, and of 1 additional room to the Privy, 9 feet long, by 6 feet broad, with a screen wall in front of the door.

2. The letters noted in the margin from the Brigadier[1] at Samulcottah, the Quarter Master General,[2] and the District Engineer[3] are submitted with this Report, and the estimate being framed on moderate and sufficient data, is recommended by the Chief Engineer for entry in the Budget of 1858-59.

1 dated 10th January 1857.
2 No. 506 18th Feby. ,,
3 No. 303 8th June ,,

No. 17. ORDER THEREON, No. 1613; dated 19th August 1857.

Referred to the Military Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

No 2615

Rajahmundry District.

Military Staff Sergeants Quarters.

Report on an Estimate prepared by the District Engineer Godavery Division for improvements to the Staff Sergeants' Quarters at Samulcottah, in the Rajahmundry District.

Amount of Estimate, Old Rupees (1310) One Thousand three hundred and ten, comprising the items shown in the accompanying Abstract.

The improvements consist of

1 additional room to the main building 24 feet long, by 10 feet broad, with an open verandah in front of the building 9 feet broad, the whole to be raised on a basement 2 feet high above ground level, which are to be 9 feet. The walls are to be 14 feet high, and the verandah pillars 6-6.

1 of 1 additional room to the Cook Room 14 feet long, by 10 feet broad,

and 1 of 1 additional room to the Privy 9 feet long, by 6 feet broad, with a screen wall in front of the door.

The letters noted in the margin from the Brigadier at Samulcottah, the Quarter Master General, and the Chief Engineer, are

1 dated 19th January 57
2 Recd 19th February "
3 " 3rd June "

acc

are submitted with this Report, and the Estimate being framed on moderate and sufficient data, is recommended by the Chief Engineer for entry on the Budget of 1858/59.-

Central Office of Fortn
Fort St. George
3rd August 1857

Col. Engrs
Chief Engineer

W. Corps Engrs A.C.

To
The Secretary to Government
Mily Department

List of Enclosures

G1 1 Letter from the 2nd Brigr Genl of the Army dated 18th Feby 1857 - No 506 - with Enclosure

G2 1 Do from the Asst Engr Cudy Dr dated 8th June 1857 - No 303 -

G3 1 Abstract Estimate

G4 1 Plan.

Public Works 183[illegible] Sept[illegible]
Do do Circs 25th Augt
No 1559

G

No 1613

From
The Chief Engineer
To
The Secretary to Government
Ordnance Department

Referred to the
Military Department
for consideration -

[illegible]

Dated 3rd August 183[illegible]
Rec'd 4th

Enclosure 4.

Ex. My Dept 22nd Augt 57 6 No 1680 incl
15th Sept

Fort St George
19th Augt 1857

I have the Duty &c
with Enclos
Rec'd 21st

No 2615

Forwards an Estimate of
1[illegible] Rupees (1310) One Thousand
three hundred and ten, prepared
by the District Engineer Cudapah
Division. for improvements to the
Staff Sergeants Quarters at Ca:
mules-Nad in the Rayalseemah
Province, for Entry in the Estimate
1858-59

No 1613. 19th Aug

No 1617.