6
13-8-37
4
M.R.O. 1—52,409—28-11-30.

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Con. 22-9-37

G.O. No. 1799 Press Mis.

Dated 22-9-1837

Not to be folded or roughly handled

No. 86. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 15th September 1857, No. 3687.

SIR,

With reference to Extract Minutes of Consultation No. 102, dated 15th January 1857, I have the honor to forward a Plan and Estimate for erecting a wall round the new Burial ground at Dowlaishweram in the Rajahmundry District, and to observe, that the same have been prepared by the District Engineer Godavery Division, in accordance with the suggestions contained in the Venerable the Archdeacon's letter No. 406, dated 8th July last.

2. The estimate amounts to Rupees (1,010) one thousand and ten, comprising the items shewn in the accompanying abstract, and provides for enclosing an area of 40,000 square feet, with a wall 7 feet in height, 6 feet to be of rough stone in clay, with a coping of 1 foot of rough stone in chunam, and the whole plastered, with 1 coat of chunam, and for building a small tiled room of 14 feet square at the entrance gate.

3. The rates allowed for the work are moderate and sufficient, and I recommend the estimate for entry in the Budget of 1858-59.

No. 87. ORDER THEREON, No. 1799; dated 22nd September 1857.

Ordered to be referred to the Ecclesiastical Department with reference to Extract Minutes of Consultation in that Department dated 7th January 1857, No. 8.

(Signed) H. FORBES,
Acting Secretary to Government.

Central Office of R.W.

No. 3687 ... Fort St. George 15 September 1837.

3

From

The Chief Engineer

To

The Secretary to Government

R.W. Department.

Ecclesiastical Burial grounds

Sir,

With reference to Extract Minutes of Consultation No. 102, dated 15 January 1837. I have the honor to forward a Plan and Estimate for erecting a wall round the new Burial Ground at Dowlaiswerum in the Rajahmundry District, and to observe that the same have been prepared by the District Engineer Godavery Division, in accordance with the suggestions contained in the Venerable the Archdeacon's letter No. 406, dated 8th July last.

Encls. 4 (vide at the foot of the letter for particulars)

2.- The Estimate amounts to Rupees 1010/. One Thousand and ten, comprising the items shewn in the accompanying Abstract, and provides for enclosing an area of 40000 sq: feet, with a wall 7 feet in height, 6 feet to be of rough stone in clay, with a coping of 1 foot of rough stone in Chunam, and the whole plastered, with 1 Coat of Chunam, and for building a small tiled room of 14 feet square at the entrance Gate.-

3.- The rates allowed for the work

are

[illegible] and sufficient and [illegible]
[illegible] the Estimates for ensuing year [illegible]
Budget of 1858/59.

[illegible]

[illegible]

[illegible]

1799

Ordered to be referred
to the Commissioners of Supply
and with reference to the
Road Committee of Commissioners
in that Department to report
forthwith.

[illegible]
2nd Sept. 1837

[illegible]
Road Committee
Sept. 1837

[illegible]
1836.

[illegible]
The Chief Engineer
for the Information of
the Commissioners of Supply

[illegible]
[illegible]
[illegible]

[illegible]

Ordered.

[illegible]