1. Number of pages. 14
2. Date of repair. 7-7-83
3. Initials of Reference
CL

M.R.O. 1—32 400—23-11-50

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cons. 29-9-57.

G.O. No. 1889 Press Mis.

5-8-57

Dated 28—9—1857

Not to be folded or roughly handled

No. 58. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 23rd September 1857, No. 3922.

SIR,

1. I have the honor under Clause 2 of Extract Minutes of Consultation No. 696, dated 18th October 1855, to forward to Government, the following Estimates prepared by the District Engineer of Bellary.

No. 1. For constructing a Cookroom to the Coffee room of the new European Barracks in the Cantonment of Bellary.

Amount of Estimate Rupees (410) four hundred and ten, comprising the items shown in the accompanying abstract.

2. The building is to contain one room 20 feet long by 10 feet broad, raised on a basement 1 foot in height above foundations, which are to be sunk 2 feet, the walls are to be 13 feet high, supporting a terraced roof.

No. 2. For constructing 9 Urinals to the new European Barracks at Bellary.

Amount of Estimate Rupees (675) six hundred and seventy-five, as per accompanying abstract.

3. The building is to be 6 feet square, raised on basements 6″ in height, above foundations, which are to be sunk 2′ 6″, the walls are to be 9 feet high, supporting terraced roofs. The screen wall in front of each building is to be 5 feet high.

4. The Plans have received the approval of his Excellency the Commander in Chief as signified in the accompanying letter, No. 2265, of the 10th Instant, from the Deputy Quarter Master General, and the Estimates being framed on moderate and sufficient data, I beg to recommend the works for immediate execution.

No. 59. ORDER THEREON, No. 1839; dated 28th September 1857.

Ordered to be referred to the Military Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

Buildings (.....) (New Work)

Abstract of Estimate No. ..... of 1855

District Bellary

Work. Constructing a Cookroom to be attached to the Coffee Room at the New European Barracks in the Cantonment of Bellary

Quantities.	Description of work.	Rate. Rs.	Rate. A.	Rate. P.	Amounts. Rupees.	Amount of each part. Rupees.
C. Yds						
209¼	Cft. Stone in Chunam — Cft.	"	1	"	131	
32	do Arch work in Chunam — do	"	2	"	4	
72	Rft. Cornice work in Chunam — Rft.	"	2	6	11	
2319	Sft. Plastering with 2 Coats Chunam — do	2	1	"	48	
220	do Paving with Square Stones — do	7	8	"	16	
264	do Terracing with Teakwood Joists Brick on edge Jelly 3 Courses of Flattiles & plastering with 3 Coats Chunam — do	34	"	"	90	
	2 Pairs Battened Doors & Fs Complete — Each	15	"	"	30	
	4 Wooden barred Ventilating — Each	7	"	"	28	
	Dogons —	"	"	"	10	
	2 Attic windows — Each	5	"	"	10	
	4 Wooden water Spouts — do	1	4	"	5	
250	Sft. Wood Oil 3 Coats — do	1	8	"	4	
175	do Green paint 3 Coats — do	2	11	"	5	
793	Cft. Excavating for foundation & filling up the Basement with Earth — Cft.	"	"	1	4	
	Sundry & Scaffolding &c. —	"	"	"	14	
				Total Company's Rupees		410

Central Office of P.W.
Fort Saint George,
23rd September, 1855.

(Signed) Thos. Taber Colonel
Chief Engineer P.W.

Enclosure

In a Letter

From The Chief Engineer
Dt. 23rd Sept. 1857

To
The Secretary to Govt.
Dt. 1/10/57

No. 3922
dated 1st/10/57.
Recd 1979/57.

Abstract Estimate for Constructing a Cook room to be attached to the Coffee Room at the New European Barracks in the Cantonment of Bellary Amounting to Co's Rs 110

Sanctioned
Dt. 1st Oct. 1857
No 1264 of 1857

Buildings ( ) (New Work)

Abstract of Estimate No ... of 1855

District Bellary

&c. Constructing 9 Urinals to be attached to the New European Barracks in the Cantonment of Bellary

Quantities.	Description of works	Rate. Rs.	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
	One Urinal					
	Cft. Stone in Clay	"	11	8	30	
	Sft. Pointing with Chunam	"	12	"	5	
	Sft. Terracing with Bricks on edge in Chunam & jelly laying 2 Courses of flattitis & Plastering with 2 Coats of Chunam Sft.	17	8	"	11	
	4 Joists 8 feet	Each 1	8	"	6	
	1 Door battened with frame shoes & hinges &c.	"	"	"	12	
	Green painting Do.	"	"	"	1	
	Air holes in the walls	"	"	"	3	
	Excavating for foundation	"	"	"	1	
	Sundries including Gravelling the floor &c.				6	
	For One Urinary				75	
	For nine Do.					675
	Total Company's Rupees					675

Office of C.E.
Saint George
September, 1857

Wd Fisher Colonel
Chief Engineer Dt. C.E.

Dimensions	Description of work	Rate.			Amount.	Amount of each part
&c &c		R.	A.	P.	Rupees.	Rupees.

Enclosure

Via Letter

From

The Chief Engineer
P.W.

To

The Secretary to Govt
P.W.

Central Office of P.W.
Fort St. George 23rd September 1837.

No. 3922

From The Chief Engineer

To The Secretary to Government
P.W. Department.

Military Barracks.

Sir,

Enclosures 5

1.- I have the honor under Clause 2, of Extract Minutes of Consultations No. 69, dated 18th October 1835, to forward to Government, the following Estimates prepared by the District Engineer of Bellary.-

No. 1. For constructing a Cook Room to the Coffee room of the new European Barracks in the Cantonment of Bellary.-

Amount of Estimate Rupees 110/

Four hundred and ten, comprising the items shown in the accompanying abstract.

2.- The building is to contain one room 20 feet long by 10 feet broad, raised on a basement 1 feet in height above foundations, which are to be sunk 2 feet, the walls are to be 13 feet high, supporting a terraced roof.-

No. 2.- For constructing 9 Arinals to the New European Barracks at Bellary.-

Amount of Estimate Rupees 675/

Six hundred and seventy five, as per accompanying abstract.-

3.- The buildings are to be 6 feet square raised on basements 6 in height above foundations

Dated 23rd Oct/br/37.

J. M. Dec/br/37

No. 3922 dated 19/9/37.

Estimate for Constructing 9 Urinals to be attached to the New European Barracks in the Cantonment of Bellary.

Amounting to Company's Rs. 675-0-0

Sd/-

Rs. 675 of 1837.

foundations which are to be sunk 2. 6. the walls are to be 9 feet high, supporting a terraced roofs. the screen wall in front of each building is to be 5 feet high..

4.. The Plans have received the approval of His Excellency the Commander in Chief, as signified in the accompanying letter, No. 2265. of the 18 instant, from the Deputy Quartermaster General, and the Estimate being framed on moderate and sufficient data, I beg to recommend the works for immediate execution.

I have the honor to be

Sir,

Your most Obt Servant

Central Office 1st Div
Fort St George
23 September 1837

H. Ed. Fanshawe Colonel
Chief Engineer

To
The Right Hon. H. C.

Y 52

D. N. 1837 Bettitt
Dr to Ans 29th Sept.
No 1887

From
The Chief Engineers
To The Secretary to Government
Mily Department

Dated 25th
Read 27th September 1837.

No 3922
Encl 5.

Forwards under Clause 2 of Gl. Orders Cons. No 595 dated 18th October 1835 five Estimates prepared by the Executive Engineer of Bellary. Nos 1 of Rupees 416 for constructing a Cook room to the Cavalry recruits of the new Sandfarm Barracks in the Cantonment of Bellary.
and No 2 of Rupees 675 for erecting 9 Urinals to the new Barracks and recommends the same for immediate [illegible]

No 1839

Ordered to be referred to the Military Department for consideration.

28th Septr 1837.

Referred to the Military Auditor. Rupees 27
Wm Prinsep

Mily Dept 5th Oct 37 Estimate No 1975 = 630

1 to 58 & 59