1. Number of pages.
2. Date of [illegible] 28.3.37
3. Initials of Reference

M.R.O. 1—82,400—23-11-30.

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cons. 13-10-37

G.O. No. 1412 Press Mis.

46-65

Dated 12 — 10 — 18 37

Not to be folded or roughly handled

5.31

1 H

Fort Saint George, Public Works Consultation of 13th October 1857.

No. 44. Read the following Extract from the Minutes of Consultation in the Military Department, dated 5th October 1857, No. 3461.

Read the following Extract Minutes Consultation Public Works Department.

Communicating a letter from the Chief Engineer, forwarding with correspondence an estimate amounting to Rupees 10,350, for thoroughly repairing and reforming the tiled roof of the European Infantry Barracks at Trichinopoly. } (Here enter 28th September 1857, No. 1841.)

The estimate for Rupees (10,350) ten thousand, three hundred and fifty, is sanctioned for immediate execution as emergent.

(Signed) R. HAMILTON, Major,
Ag. Dy. Secretary to Government.

No. 45. ORDER THEREON, No. 1912; dated 12th October 1857.

Ordered to be communicated to the Chief Engineer with reference to his letter dated 23rd September 1857, No. 3916.

(Signed) H. FORBES,
Acting Secretary to Government.

Canada Corp — 20466

Buildings (.....) (New Work) 5 H

Abstract of Estimate No. ..... of 1855

Trichinopoly District

Work. Renewing & Improving the roof of the Tiled Portion of the European Infantry Barracks occupied by the 2 Troops of Horse Artillery at Trichinopoly.

Quantities.	Description of work.	Rate. Rs	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
C. Yds						
43212	Sqft. of Taking down the tiled roof Sq.	"	4	10½	132	
4576	Cft. of Demolishing top of walls — Cft.	"	"	1¼	30	
11776	Cft. of Brickwork in Chunam — Cft.	"	1	2⅞	1174	
312	do of Cornice work in Chunam — do	"	2	3	48	
22287	Sqft. Plastering with 1 Coat of Chunam — Sq.	1	6	11	319	
30934	do Roofing with teakwood Couplies & Sleepers flat Spantiles & Chunam borders Sq.	3	9	9	1163	
13546	do Roofing Verandah with teakwood Rafters Sleepers flat Spantiles & Chunam borders Sq.	2	6	"	3556	
9645	do Roofing Ridge Ventilators with teakwood Couplies and Sleepers flat and Spantiles & Chunam borders Sq.	3	"	3	2835	
255	Cft. Teakwood Bressummers — Cft.	1	11	9½	444	
55	Punkahs Taking down and re-Hanging — Each	1	12	8	99	
1907	Sqft. Whitewashing with fine Clay to Punkahs — Sq.	"	3	"	9	
36681	do Whitewashing inside & Cornice — do	"	1	2	27	
35342	do Bluewashing outside & pillars — do	"	1	7½	36	
1010	do Taking down Pandal in front of Verandah and renewing with fresh Cocoanut leaves white and Coir rope and wild Canes — Sq.	1	3	3	129	
					Carried Over	2466

Quantities	Description of work.	Rate.			Amount.	Amount of each part.
C. Yds		Rs	As	Ps	Rupees.	Rupees.
	Brought Over				20466	
	122 Large Jungle wood posts for Pandal ——— Each	"	7	"	53	
	119 Small do — do — do — do —	"	3	"	22	
	Petty Repairs to Doors & windows —	"	"	"	20	
	Sundries ———				205	
						20766
	Deductions					
30½ 2%	1½ ft. Flat Quantities of proof under Ridge Ventilators ——— ½	5	"	6	153	
	132000 Pantiles ——— per 1000	2	"	"	861½	
55%	31 Old teak Brest Summers ——— C.ft.	1	2	8	65	
8000	C.ft. Teak Timber available from the Stock in Store ——— C.ft.	3	1	2 8	9331	
						10416
	Total Company's Rupees					10350

Central Office of P.W.
Fort Saint George,
23rd September, 1857

Executive Engineer
Chief Engineer D.P.W.

Enclosure

Ina Letter

From.

The Chief Engineer

S.P.W.

To The Secretary to Govt

S.P.W.

12th October 57

Date Recd 23 Oct 57

P.W. 1890/57

P.W. 1984/57

No 3916.

W.D.

In No 1262 of 1857.

Abstract Revised Estimate for Renewing & Improving the roof of the Tiled Portion of the European Infantry Barracks Occupied by the H. Troops of Horse Artillery at Trichinopoly

Amounting to Company's Rs 10350 — —

7H

To The Military Department

No 3461.

Extract from the Minutes of Consultations

Under date the 5th October 1857.

Read the following

Extract Minutes Consultations
Public Works Department

Communicating a letter from the Chief Engineer forwarding with correspondence an Estimate amounting to Rs 10,350, for thoroughly repairing and reforming the tiled roof of the European Infantry Barracks at Trichinopoly.

(Here enter 28 Letter 57 No 1841)

The Estimate for Rupees 10350 — — Ten thousand three hundred and fifty is sanctioned for immediate execution as emergent.

(Signed) R. Hamilton Major

Actg Depy Secy to Govt

To The Department Public Works

Quarter Master General.

5

Lt Smith

5

P.W. Cons: 29 Sept 1857 No. 6263

Public Works 1857 Dept.
Do to Cons 13th October.
No. 1984

Extract from the Minutes of Cons: in the Military Department

Dated 5th } October
Received 6th }

Enclosure 2 Sketches
From the Offg Chief Engr 21st Oct 1857 No. 2506 inc: 5 Mm
Sanctg. for imme: diate execution, an Estimate of Rs 10,350 for thoroughly repairing & preserving the tiled roof of the European Infantry Barracks at Trichinopoly &c.

With an order No. 1912. 12th Octr

No. 1912.

Ordered to be communicated to the Chief Engineer with reference to his letter dated 23d September 1857 No. 3916.

Fort Saint George 12th Octr. 1857

J Cpnl to the Chief Engr Offg 13th