M.R.O. 1—22 doc—23-11-05

MADRAS RECORD OFFICE.

Government of Madras.

DEPARTMENT.

G.O. No.	Press Mds.
Dated ____ / ____ / 18	

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 10*th November* 1857.

No. 48. Read the following Extract from the Minutes of Consultation in the Military Department, dated 3rd November 1857, No. 3874.

Read the following Extract from the Minutes of Consultation in the Public Works Department.

Referring for consideration a letter from the Chief Engineer, submitting for entry in the Budget of 1858-59 an estimate amounting to Rupees 25,000 for adequate accommodation for the families of Artillery Soldiers at the Mount. } (Here enter 30th October 1857, No. 2039.)

Approved for entry in the Budget 1858-59.

(Signed) R. HAMILTON, Major,
Acting Dy. Secretary to Government.

No. 49. ORDER THEREON, No. 2081 ; dated 9th November 1857.

Ordered to be communicated to the Chief Engineer with reference to his letter dated 20th October 1857, No. 4593.

(Signed) H. FORBES,
Acting Secretary to Government.

Military Department

No 3871

Extract from the Minutes of Consultation
Under date the 3d November 1857.

Read the following Extract
from the Minutes of Consultation in the
Public Works Department:

Referring for consideration a letter from the Chief Engineer, submitting for entry in the Budget of 1858/59 an Estimate amounting to Rupees 25,000 for adequate accommodation for the families of Artillery Soldiers at the Mount (Vide under 30th Feb: 1857 No 2039)

Approved for entry in the budget 1858/59.

(Signed) R. Hamilton, Major
Actg Depy. Secy. to Govt

To

The Department Public Works
" Quarter Master General

E

(New Works)

(Military Department)

Abstract of Estimate No. 1 of 1857/58.

District Chenigleput

Taloor Sydapet Village Saint Thomas's Mount

Work. For Constructing a Range of Married Men's Quarters for the Artillery at Saint Thomas's Mount

Quantities	Description of Work	Rate Rs.	A.	P.	Amount Rupees	Amount of each part Rupees
Cubic Yards						
2157		2	13	0	7173	
~~2156~~	Brick work in Chunam	~~3~~	~~8~~	~~0~~	~~7368~~	
42	Arch do in do	4	12	0	200	
118	Cubic feet of Cornice work in Chunam	0	2	10	21	
			~~3~~	0	~~22~~	
170	Squares of Roofing with Palmyrah Rafters, Teakwood Rafters, Nails, Flat Pantiles and Chunam borders	16	0	0	2720	
139	Squares of Flooring with 10 inches Square Bricks and Chunam	6	13	6	749	
		~~7~~	0	0	763	
278	Running feet of Ridge Ventilators 15" complete	2	0	0	556	
704	Squares of Plastering with 2 Coats of Chunam	~~3~~	~~0~~	~~0~~	~~2178~~	
20	Teakwood Beef Summers for Verandah each 16 feet long	~~6~~	0	0	~~120~~ 110	
80	Pairs of Teakwood Venetian Doors with frames Hinges bolts &c. complete	32	0	0	2560	
80	Pairs of Glazed Shutters with Hinges bolts &c. Complete	22	0	0	1760	
		~~28~~	0	0	~~2240~~	
20	Pairs of Teakwood batten Doors with frames Hooks Hinges bolts &c. Complete	15	0	0	300	
20	Pairs of Teakwood batten Doors with frames Hooks Hinges bolts &c. complete	10	0	0	200	
40	Pairs of Teakwood Venetian Windows with frames &c. complete	17	8	0	700	
40	Pairs of Teakwood Glazed Shutters with Hinges &c. complete	15	0	0	600	
160	Green painting the Doors and Windows and Sides	2	12	0	440	
~~6~~ 5	~~Do~~ of the Summers &c.	1	2	0	~~007~~	
20	Bring Seats complete	~~6~~ 5	0	0	100	
					~~120~~	
~~2722~~ 2727	Earth for Excavating foundation and filling in	0	1	~~8~~ 3	213	
					~~198~~	
	Sundries at 5 per Cent				1005	
					~~2139~~	
	Total for the Range				21050	
					~~23,510~~	

Carried forward ~~23,510~~ 21050

Quantities Cubic Yards	Description of Work	Rate Rs. A. P.	Amount Rupees	Amount of each part Rupees
	Partitioned Cook Room			
	Brought forward		~~23510~~	21050
205	Brick in Chunam	~~2~~ 2 13 "	~~615~~ 577	
5	Flat Arch work in Chunam	~~4~~ 4 8 "	~~22~~ 22	
54	Cubic feet of Cornice work in Chunam	" ~~2~~ 2 10	~~9~~ 10	
20	Squares of Roofing with Palmyrah Rafters Teak wood Rafters, Nails, Battens and Chunam borders &c.	15 " "	300	
56	Squares of Plastering with 2 Coats of Chunam	~~2~~ 1 14 "	~~112~~ 105	
12	Squares of Flooring with 10 inches Square Bricks and Chunam	~~7~~ 6 13 6	~~84~~ 82	
8	Pairs of Teakwood Batten Doors with Frames Hooks, Hinges bolts &c. complete	18 " "	144	
2	Pairs of batten Windows with frames and Iron bars &c. complete	13 " "	26	
8	Grating Windows with frames Iron bars &c. complete	~~4~~ 2 8 "	~~32~~ 20	
	Constructing fire Places & Pipes &c. Complete as per plan	5	40	
	Painting the Doors & Windows &c.		15	
	Excavating foundation and raising the floor		~~35~~ 20	
	Sundries at ~~10~~ 5 per Cent		~~153~~ 70	
	Total for the Partitioned Cook Room		~~1510~~ 1130	~~1510~~ 1130
	1 Bath for Mens & Womens			
76	Brick in Chunam	~~3~~ 2 13 "	~~304~~ 214	
2	Flat Arch in Chunam	~~8~~ 8 "	~~32~~ 16	
24	Cubic feet of Cornice work in Chunam	" ~~3~~ 2 10	~~5~~ 3	
6	Squares of Roofing with Palmyrah Rafters Teak wood Rafters, Nails Flat and Battens and Chunam borders	16 " "	96	
9	Squares of Flooring with Granite Cut Stones	18 " "	162	
20	Squares of Plastering with Chunam	~~2~~ 1 13 "	~~60~~ 36	
	Carried forward		~~561~~ 521	~~25180~~ 22180

Quantities Cubic Yards	Description of Work	Rate Rs. A. P.	Amount Rupees	Amount of each part Rupees
	Brought forward		~~561~~ 521	~~25180~~ 22180
1	Pair of Teakwood batten Door with frames Hooks Hinges bolts &c. complete		~~25~~ 21	
16	Running feet of wooden Shelves with Brackets &c. complete	" 12 "	35	
2	Pinches Teakwood	5 " "	10	
16	Running feet of Gutters	" 2 "	12	
	Honey comb tile work		7	
9	Basons or Tubs	3 " "	27	
	Constructing a Masonry Cesspool for Refuse water Complete		65	
2	Large Wooden Tubs	10 " "	20	
	Painting the Doors		3	
	Excavating the foundation and raising the floor		5	
	Sundries about 5 per cent		~~110~~ 54	
	Total for the Bath Room		~~880~~ 760	
	Extra Establishments &c.a		1760	
	Total Estimate Rupees		~~20,000~~ 24,680	

Distt. Engrs Office
Camp Guindy
19th November 1856

Wm. Mobray Capt
District Engineer of Chingleput

Est. No 1
" 1/5

Chargeofficer N.B.S.

1360/5

Sandy

PWD-
B.
In No. 4857 of 1851-

~~PW 2105/67~~

PW 2163/67

Abstract Estimate
for Constructing a Range
of Married Men's Quarters
for the Artillery at
Saint Thomas's Mount
Amounting to Rs. 25000-

P.R. Cons: 5th Nov/57 No 6-7.

Public Works 1857 No 1st
Fo Cons: 10th do No 2163

Extract from the Mins: of Cons: in the Military Department.

Dated 3d } Nov 1857
Recvd 4th }

No 3874

2 Enclosures

Approving for entry in the Budget of 1858/59, an Estimate amounting to Rs 25,000 for adequate accommodation for the families of Artillery Soldiers at the Mount.

No 2081. 9th Nov
With an order &c

No 2081

Ordered to be communicated to the Chief Engineer with reference to his letter dated 20 Oct 1857 No 4593.

JG

Fort St George
9th Nov 1857

2 Copies to the Chief Engr
with 3 Encls Desp Cons

No 48 + 49.