16.9.37

M.R.O.—1—82 400—29-11-80

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Con. 1.12.57

G.O. No. 2207 Press Mis.

26.75

Dated 25.11. 18 57

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 1st December 1857.

No. 74. Read the following Extract from the Minutes of Consultation in the Military Department, dated 21st November 1857, No. 4160.

Read the following Extract from the Public Works Department.

Referring for consideration the recommendation of the Chief Engineer that an estimate, amounting to Rupees 5,650 for constructing out-houses to the European Hospital at Bellary, be included in the Budget for 1858-59. } (Here enter 19th November 1857, No. 2127.)

Approved for entry in the Budget of 1858-59.

(Signed) R. HAMILTON, Major,
Ag. Dy. Secretary to Government.

No. 75. ORDER THEREON, No. 2207; dated 28th November 1857.

Ordered to be communicated to the Chief Engineer with reference to his letter dated 9th November 1857, No. 5065.

(Signed) H. FORBES,
Acting Secretary to Government.

Quantities	Description of Work	Rates			Amount	Amount of each part
C. Yds		Rs	As	P	Rupees	Rupees
	Brought Over				1697	
	6 Pairs of Teakwood windows with barred frames Hooks and Hinges &c. ___ Each	17	8	-	105	
	Green Painting 3 Coats ___				12	
	Wood Oiling 3 Coats ___				23	
	Excavating for foundation and raising the floor ___				25	
						1862
	Store rooms and Hospital Serjeants Quarters As detailed above for Guard room &c. &c. ___					
	Dead Room					1862
2560	Stone in chunam ___ ₹C.		1	-	160	
201	Semicircular arch work Stone in C.		3	1	39	
2347	Sup.ft Plastering 2 Coats of chunam ₹sq.	2	1	-	48	
76	R.ft Cornice work Stone in chunam ₹		2	6	12	
280	Sup.ft Terracing with Beams Joists Jelly 2 Courses of flat tiles and plastering with 3 coats of chunam ___ ₹sq.	34			95	
252	" Paving with Square Stones pointed with Chunam ___ "	7	8	-	19	
	1 Pair of Teakwood Venetian & Glazed Door with frames Hinges &c. &c. ___				28	
	Carried Over				1611	3724

Quantities	Description of work	Rate			Amount	Amount of each part
	Brought Over				401	3724
	5 Pairs of Double windows Venetian Outside and Glazed inside with frames Hinges &c. &c. Each	36	-	-	180	
	Green Painting 3 Coats ___				15	
	Wood Oiling Do. ___				5	
	Excavating for foundation and raising the floor ___				5	
						606
	2 Cook Rooms.					
2150	Stone in chunam ___ ₹C.		1	-	134	
41	Semicircular arch work Stone in Ch.m		3	1	8	
2355	Sup.ft Plastering 2 Coats of chunam ₹sq.	2	1	-	48	
324	" Terracing with Joists brick on edge Jelly 2 Courses of flat tiles & Plastering with 3 Coats of chunam ___ "	34	-	-	110	
175	" Paving with sq.re Stones pointed with chunam ___ "	7	8	-	13	
82	R.ft Cornice work Stone in chunam ₹		2	6	13	
	2 Pairs of Batten Doors with frames Hooks Hinges &c. Each	21	-	-	42	
	3 Barred windows with weather boards &c. ___ "	7	-	-	21	
	Green painting 3 Coats ___				4	
	Wood Oiling 3 Coats ___				5	
	Carried Over	398				4330

Quantities	Description of works	Rate	Amount	Amount of each bar
	Brought Over		398	4330
	Excavating for foundation & raising the floor		3	
	Fogongs		10	
	For one Cook room		411	
	D° two D°		"	822
	For planting trees		"	250
	Sundry charges Vcs Vca		"	248
	Total Company's Rupees			5650

Central Office of P.W.
Fort Saint George
9th November 1857.

W.E. Baker Colonel
Chief Engineer D.P.W.

Enclosure
In a Letter

From

The Chief Engineer
D. F. W.

To

The Secretary to Govt.
D. F. W.

MM 228/57

Dated 9th Nov 57
Recvd
Exd -
In Rs 5204 of 1857-
No 5865.

Abstract Estimate for constructing Out Offices to be attached to the new European Hospital in the Cantonment of Bellary.

Amounting to Company Rs 5650-

Report to Accompany the Estimate of the expense of Constructing Out Offices to be attached to the New European Hospital recently commenced at Bellary - - 9th

Amount of the Estimate Rupees 5650 Comprising the following items. -

Guard Room and Quarters for the Medical Subordinates

9854	Cft. of Stone in Chunam at 1 - - ₰ Cft.	615	14 - -
342	Do. of Semicircular Archwork Do. at 3 - 1 ₰ Do.	65	14 - 6
8035	Sup. Ft. Plastering 2 Coats of Chunam at 2 - 1 - ₰ Sft.	165	11 - 6
184	Rft. Cornice work Do. at 2 - 6 ₰ Rft.	28	12 - -
1152	Sft. Terracing with Beams Joists Brick wedger Selly laying 2 Courses of flat tiles and Plastering with 3 Coats of Chunam at 3 - - - ₰ Sft.	391	10 - 10 -
999	Do. Roofing the Verandah with Rafters reepers & Bamboo Mats Flat and Pantiles & Chunam borders at 25 - - ₰ Do.	249	12 - -
896	Do. Paveing with Sft. Stones pointed with Chunam at 7 - 8 - - ₰ Sft.	67	3 - 2 -
	4 Pairs of Teakwood Panneled and Venetion Doors with frames Hinges Screw nails &c. at 28 - - - ₰ Each	112	- - -
	6 Pairs of Teakwood windows with Barred frames Hooks and Hinges &c. at 17 - 8 - - ₰ Each	105	- - -
	Green painting 3 Coats	12	- - -
	Wood oiling 3 Coats	22	8 - -
	Excavating for foundation & Raising the floor	25	- - -
		1861	6 - -

Store Rooms and Hospital Serjeants Quarters.

as detailed above for Guard Room &c. &c. 1861 6 - -

Dead Room.

2560	Cft. Stone in Chunam at - - 1 - - ₰ Cft.	160	- - -
201	Do. Semicircular Arch work Stone in Chunam - at - - 3 - 1 - ₰ Cft.	38	11 - 9 -
2347	Sup. Ft. Plastering 2 Coats of Chunam - at 2 - 1 - - ₰ Sft.	48	6 - 6 -
76	Rft. Cornice work Stone in Chunam at - - 2 - 6 ₰ Rft.	11	14 - -
280	Sup. Ft. Terracing with Beams Joists Selly 2 Courses of flattiles & plastering with 3 coats of Chunam 34 - - - ₰ Sft.	95	3 - 2 -
	Carried Over	354	3 - 5 - 3722 - 12

Brought forward 354-3-5-3722-12-

252 Sup^{ft} Paving with Square Stones painted with Chunam at 7-8 per Sq^{r} 18-14-5

1 Pair of Teakwood Venetian and Glazed Door with frames Hinges &c^{a} &c^{a} 28-0-0

5 Pairs of Double windows Venetian outside and Glazed inside with frames Hinges &c^{a} at 36-0-0 180-0-0

Green painting 3 Coats 15-0-0

Wood Ciling Do 5-0-0

Excavating for foundation & Raising the floor 5-0-0

606-1-10

2 Cookrooms.

2150 C^{ft} Stone in Chunam at 0-1-0 per C^{ft} 134-6-0

40½ Do Semicircular arch work Stone in Chunam at 3-1-0 per Do 7-12-10.

2355½ Sup^{ft} Plastering 2 coats of Chunam at 2-1-0 per C^{ft} 48-9-4.

324 Do Terracing with Joists Brick on edge Jelly 2 Courses of flat tiles and Plastering with 2 Coats of Chunam - at 34-0-0 per C^{ft} 110-2-7-

175 Do Paving with Sq^{r} Stones painted with Chunam at 7-8-0 per Sq^{r} 13-2-0

82 R^{ft} Cornice work Stone in Chunam at 0-2-6 per R^{ft} 12-13-0

2 Pairs of Batten Doors with frames Hooks Hinges &c^{a} &c^{a} at 21-0-0 Each 42-0-0

3 Barred Windows with weather boards &c^{a} at 7-0-0 Do 21-0-0

Green painting 3 Coats 4-0-0

Wood Ciling Do 4-8-0

Excavating for foundation & Raising the floor 3-0-0

Fogongs 10-0-0

Total for one Cookroom 411-5-9-

Do for 2 Do 822-11-6

Planting Trees 250-0-0

Sundry Charges &c^{a} &c^{a} 248-6-8

Total Rupees 5650-0-0

Guard Room Quarters for Medical Subordinates Hospital Serjeants and Store Rooms.

The Buildings are to be raised on a basement of 3 feet in hight above foundations which are to be sunk 3 feet the principal walls and Pillars are to be 14½ and 6 feet respectively.

The Building is to Contain 8 Rooms each of them 16×14 feet with a Verandah inside of 74 R^{ft} by 10 feet clear.

Dead Room

The Building is to be raised on a basement of 2 feet above the foundations which are to be sunk 3 feet the walls are to be raised to 14 feet in height and the Building Containing a Room of 18 by 12 feet.

2 Cookrooms

These Buildings are to be raised on a basement of 1-6 above the foundations which are to be sunk 3 feet the walls are to be raised 14 feet Each of these Buildings Containing a Room of 25 by 10 feet.

Trees to be planted on the N-E. side of the Building to protect it from the winds from that direction.

Central Office of P.W.
Fort Saint George.
9th Nov^{r} 1857

W. Salter Colonel
Chief Engineer D. P.W.

Electrum m x Telle

From

The Chief Engineer

To

The Secretary to the

P.W.D.

Sir

I have the honor to forward

Rec'd Nov 19th 1857

No 5665

Bd - (P.W.) 2315/57

In No 5264 of 1857

Report on the estimate for
constructing cast houses to be
attached to the New European
Hospital recently com-
menced at Bellary amount-
ing to Rs 5650——a

No 13 H

Mo. D.

No 4160

Extract from the Minutes of Consultation

Dated 21st November 1857.

Read the following Extract

from the Chief Engineer P. W. Depart.

Referring for consi-
deration the recommenda-
tion of the Chief Engineer
that an Estimate, amount-
ing to Rs. 5650 for con-
structing cast houses to
the Euro. Hospital at
Bellary, be included in
the Budget for 1858/59.

(Here enter 19th November 57
No 5212)

Approved for entry in the

Budget of 1858/59.

(Signed) R. Hamilton Maya.

A.g. Dy. Secy. to Govt.

To

The Depart. P. Works.

Quarter Mr. General.

2/2

Ld Smith

Letter 24th Nov 57 No 48-57

Public Works 1857 Oct 15th
To Govt 1st Dept.
No 2315.

Extract from the Minutes
of Govt in the Military
Dept

Dated 21st
Received 21st } Nov 1857.

Encls: 2 — No 4160.

Approving for entry in
the Budget of 1858-59 an Es-
timate of Rs 5,650 for con-
structing out Houses to the
European Hospital at
Bellary

No 74+75.

Proc of M. Dept 27 March
1861 Cons 577 ii
pro 15 March No 529.

Re 2207 - 28th Nov
Withdrawn order

No 2207

Ordered to be commu-
nicated to the Chief Engineer
with reference to his letter
dated 9th November 1857
No 5065.

From Dy Secy
28th Nov 57

9 Copies to the Chief Engr Dept 30
with a Plan.