1. Number of pages
2. Date of repair.
3. Initials of Referencer

M.R.O.1—82406—23-11-50

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cons 23-12-57

G.O. No. 2350 Press / Mis. /

4248

Dated 19-12-1857.

Not to be folded or roughly handled

No. 47. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 16th December 1857, No. 5990.

SIR,

I have the honor to forward, for the early consideration and orders of Government, a Plan and Estimate amounting to Rupees (4,380) four thousand, three hundred and eighty, for repairs and improvements to the Cavalry Hospital at Trichinopoly.

2. The proposed works consist of raising and partly re-building the walls, adding a verandah with bath rooms, and a ridge ventilator, and are considered by His Excellency the Commander-in-Chief to be "most necessary."

3. The Estimate which was prepared by the District Engineer of Trichinopoly has been examined in the Central Office, and the rates found to be reasonable and sufficient. I beg therefore to recommend that in consideration of the necessity represented to exist for the improvements the Estimate Rupees (4,380) four thousand, three hundred and eighty, be sanctioned on emergency, and ordered for immediate execution.

No. 3024.

QR. MASTER GENERAL'S OFFICE,
Fort Saint George,
7th Decr. 1857.

Submitted the following letter to the Commander in Chief from the Chief Engineer.
No. 5509, dated 26th November 1857.
Forwards for submission to the Commander in Chief, Plan and Estimate of improvements proposed to be made to the Cavalry Hospital at Trichinopoly.

His Excellency's order thereon.
The Commander-in-Chief observes that the work seems most necessary, and should be executed; His Excellency approves of the Plan.

(Signed) F. A. REID,
Qr. Mr. Genl. of the Army.

No. 48. ORDER THEREON, No. 2350; dated 19th December 1857.

Ordered to be referred to the Military Department.

(Signed) H. FORBES,
Acting Secretary to Government.

Carried Cost 61785

3

Central Office of P.W.
Fort St. George
16th December 1857.

No. 5990.

From The Chief Engineer

To The Secretary to Government P.W.D.

Sir,

Military — Cavalry Hospl. at Trichinopoly

I have the honor to forward for the early consideration and orders of Government, a Plan and Estimate amounting to Rupees 14,380/ Four thousand three hundred and eighty, for Repairs and improvements to the Cavalry Hospital at Trichinopoly.—

Enc: 3

2. The proposed works consist of Raising and partly rebuilding the walls, adding a Verandah with bath Rooms, and a Ridge ventilator and are considered by His Excellency the Commander in Chief to be "most necessary".

3. The estimate which was prepared by the District Engineer of

Carried Cost 41785

of Trichinopoly has been examined in the Central Office, and the Rates found to be Reasonable and sufficient. I beg therefore to Recommend that in Consideration of the necessity represented to exist for the improvements the Estimate Rs. 4380 / four thousand three hundred and eighty, be Sanctioned, on emergency, and ordered for immediate execution.

Fort St. George
16th Decr 87

I have the honor to be
Sir,
Your most obdt Servt

L.L.

A. S. S. Circle

Colo
Chief Engr

To
The Secretary to
Government Pub. D

Copy

Buildings / New Work

Abstract of Estimate No of 1887

District Trichinopoly

Work Improving the Native Lunatic Hospital

Quantities	Description of Work	Rates			Amount	Amount checked
		Rs	As	P	Rupees	Rupees
C Yds						
2571	C/ft of Excavation ——— 100 C/ft	"	7	"	11	
8906	C/ft of Brickwork in Chunam ——— C/ft	"	1	"	777	
6	C/ft of Cornice work in Chunam ——— do	"	2	6	1	
3461	Sqft Roofing with Teak Couples and reepers of flat and pantiles and Chunam borders ——— Sqft	51	12	"	1791	
3113	Sqft Roofing Verandahs with Palmirah rafters Teak reepers flat and pantiles and Chunam borders ——— Sqft	19	7	"	605	
1096	do Ridge Ventilator of roof of Palmirah Couples Teak Reeper scrafts & reepers flat & pantiles and Chunam borders	36	3	"	397	
42½	C/ft Country wood breastsummers ——— C/ft	1	1	9	47	
6	Teak half panneled & half Venetian doors Complete ——— Each	26	14	"	161	
14	Teak windows with double shutters Venetian and Glazed ——— Each	24	9	7	344	
2	Teak half Venetian & half panneled doors to rooms in Verandah ——— Each	21	12	3	44	
					Carried Cost ———	4178

Quantities	Description of Work	Rates			Amount	Amount of each part
C Yds.		Rs	as	ps	Rupees	Rupees
	Brought Over				4178	
	6 Teak Glazed windows to rooms in Verandah ——— Each	16	2	9	97	
1889	Sft. Painting above with 2 Coats of Green paint ——— Sq.	4	8	"	85	
931½	do Plastering with 1 Coats of Chunam ——— Sq.	1	8	"	139	
191	do Plastering with 2 Coats of Di	2	6	9	5	
54	do Granite Stone in Chunam ——— Sq.	23	10	6	13	
1570	do Paving with 1 foot square Granite Stones ——— Sq.	16	2	6	254	
12778	Sft. Whitewashing ——— Sq.	"	1	3	10	
3429¾	Cft. Demolishing old walls of hospital	"	"	1¼	22	
3822	Sft. Taking down old roof of Di	"	3	"	7	
	Sundries ———				235	
						5045
	— Deductions —					
316¼	Sft. Flat and Pantiles of roof under ridge ventilator ——— Sq.	5	4	"	17	
38000	Pantiles available from Hospital	2	"	"	76	
9000	Flattiles available from Hospital	1	"	"	9	
6	Glazed windows available from Hospital	16	2	9	97	
145¼	Palmirah rafters 11 Ft. long Each	1	"	"	145	
109½	Di ——— 12 ——— Di	do	"	13	"	89
12½	Cft. Country wood Beams. Summers ———	do	"	12	"	32
	Carried over ———				465	5045

Quantities	Description of work	Rate			Amount	Amount of each part
		Rs	as	ps	Rupees	Rupees
	Brought Over ———				465	5045
60½	Rft. of Granite Stone Pitching available from old Hospital	3	8	"	2	
1569½	Superficial feet Granite Stones do do	"	2	"	196	
						665
	Total Company's Rupees					4380

Central Office of P.W.
Fort Saint George,
16th December 1857.

A.B.C. Taylor Colonel
Chief Engineer D.P.W.

Enclosure

In Letter

From

The Chief Engineer

D.P.H

M. D.

Ln N° 5810 of 1857

To

The Secretary to Govt

D.P.H.

Dated 16th December 1857

Received

MM 2467/57

N° 5990.

Abstract Estimate for Improvements

the Native Cavalry Hospital at

the District of Trichinopoly.

Amounting to Company's Rs 4381

P.O. Works 1857 No 15 to
P.O. to Com. 23 December
Do Tram No 2467.
The Chief Engineer
To The Secretary to Govt
P.W.D.

Dated 16th Dec. 1857
Recd 17th
No 5990

Enclosure 3.
Retd 2 Enc.

Forwarded for early consideration and orders Plan & Estimate Rs 14380/ for repairs and improvements to the Cavalry Hospital Cath Trichinopoly and recommends that the same be sanctioned as emergency and ordered for immediate execution.
No 2350 With an order 19th Dec.

No 47448.

No 2350

Ordered to be reported to the Military Department.

[illegible]

First Secretary
19th Dec 1857

4 Copies to the Military Dept. with 2 Plans Rec'd 21st
Returned 2 Engd Enc. to the Chief Engr. 25-1-