

MADRAS RECORD OFFICE.

Government of Madras.

P. A. L. W. S. DEPARTMENT.

Cons. 17-2-57

G.O. No. <i>3-3</i>	Press Mis.
<i>13-14</i>	
Dated <i>13-2-</i>	<i>18 1/2</i>

Not to be folded or roughly handled

No. 13. Read the following letter from Colonel C. E. FABER, Chief Engineer; to J. D. BOURDILLON, Esq., Secretary to Government, D. P. W., dated 28th January 1857, No. 9816.

SIR,

1. I have the honor to forward for the consideration of Government copies of letters noted in the margin* from the Superintendent of the East Coast Canal, on the subject of erecting Office and Store buildings.

2. The objections raised by the Superintendent to the Establishment of a Central Office and Store are sufficiently valid, to admit of one exception being made to the general arrangements approved for such buildings in the several Districts, and I am induced therefore, to support his proposition for a continuance of the system which has hitherto obtained in *his* Department, of erecting a Store at each lock with a building (permanent instead of temporary) for the accommodation of the required Establishment of 1 Conicopoly and 6 Lascars.

3. The buildings proposed by the Superintendent to be erected, appear in all respects to be suitable, they provide for a small house at one corner of the yard, containing two rooms, one to be allotted to the Goomastah, and one as an Office for the Executive Officer when necessary; as well as for general purposes also six small rooms on one side of the yard for the Lascars, with a lock up store house, and open shed for the Carpenters, and Smiths, in the corner opposite the Goomastahs quarters.

4. The plan and estimate now submitted, provide for such buildings being erected immediately to the East of the lock at Shadiencoopum, and in forwarding this letter to Government under Clause II of Extract from the Minutes of Consultation No. 696 dated 18th October 1855, I beg to solicit sanction for the early execution of the work, the rates allowed in the Estimate which amounts to Rupees (2,380) two thousand, three hundred and eighty, being moderate and sufficient.

No. 14. ORDER THEREON, No. 303; dated 13th February 1857.

The Right Honorable the Governor in Council sanctions the estimate submitted with this letter, amounting to Rupees (2,380) two thousand, three hundred and eighty, for constructing Office and Store yards and quarters for the establishment employed at the Shadiencoopum Lock, and directs that it be entered in the Budget of 1857-58, in the Government Office. Under this sanction the building will be proceeded with on the 1st of May next, and there appears no necessity for authorizing the commencement of work at an earlier date.

(Signed) H. FORBES,
Acting Secretary to Government.

3

N. 325.

From, Lieutenant R. H. Tanky, Engineer,
Superintendent of the E. C. Canal.

To,
The Chief Engineer Dept. of Public Works
Port Saint George.

Sir,

* N. 109 of 17th Sept/55.
N. 199 of 27th March/56.

My attention having been drawn to your Circulars as per margin, directing that estimates for Overseer's store sheds and Engineer's Office should be sent to the Central Office, I have the honor to inform you, that the delay which has occurred in supplying this information was quite unintentional, as will appear from the following note which I find appended by Lieutenant Chambers to the 1st of these Circulars above mentioned. 'As stores, carpenters sheds, Offices, Smith's sheds &c. already exist at Thedianooppum, and at the Adyar, this Extract of Proceedings must be meant for the information of the Superintendent Eastern Coast Canal, and not for his guidance.'

2 On consideration I do not think the plan of a Central Office and store exactly applicable to the requirements of the Eastern Coast Canal Department; with the divisional charges no doubt such an arrangement would be admirable as a point might easily be selected in a central position and within easy range of many works; but in the case of the Eastern Coast Canal, a point which might appear central one year, would completely be changed in relative bearing by the sanctioning of an additional length of Canal

by government.

9 I could not but observe that, as it would seem possible, the Superintendent of the works, in view of the to the Chief Engineer, might be authorized to submit preliminary estimate for a temporary building near the present site. But in no case, as before said, do I think in the least degree would I suggest.

10 I take the opportunity of begging to your notice that at this moment, I am, virtually, without office furniture and trust that an early and favorable consideration may be given to my estimate forwarded, to the General Officer, 29th November 1856.

Respecting your orders on the subject of this letter
I am, Sir,
Yours faithfully,
Signed, W. M. Lumsden,
Capt of the E. I. Canal.

From, N. 373.
Lieutenant W. M. Lumsden, Engineer,
Capt of the E. I. Canal.

To,
The Chief Engineer
in the Dept of E. Works
at St. George

Sir,
In accordance with the instructions contained

in Extract of Proceedings N. 8783 of the 11th December, '56, I have the honor to submit herewith plan and estimate for a store yard and quarters, for Goomastahs and Lascars employed in working the Chediacoppum Lock. The estimate amounts to Company's Rupees (2313-4-6) two thousand three hundred and thirteen, Annas four, and piee six.

2 The establishment, which it is meant to provide for consists of 1 Goomastah, and 6 Lascars.

On inspection of the plan, it will be seen, that a small house at the corner of the store yard has been allotted to the Goomastah, consisting of two rooms, the outer one of which is intended as an office for the use of the Executive Officer when necessary, as well as general purposes. The six small rooms on one side of the yard, will it is hoped, amply provide for the Lascars, while a lock up store house and open shed situated at the corner opposite the Goomastah's quarters, appears to be necessary adjuncts, where the small though constant repair of the Canal between Madras and Ennore is taken into account.

The site which I think most eligible is immediately to the east of the lock, and as the ground is every where low and exposed to the effects of inundations, I have estimated for raising a plateau of earth 5 to 6 feet above the general level, whereon to erect the buildings. No other location would in my opinion answer equally well and the level excepting in the Village of Chediacoppum 5 to

600 Yards distant is every where the same.

E. C. Canal,

Supt's Office,

Enmore,

6th January 1857.

I have for

I signed / Col. H. S. Santee, M. E.

Supt. of the E. C. Canal

I True Copies,

Wm. S. Santee, Colonel.

Chief Engineer.

Wm. S. Santee

Buildings

(New Work)

Abstract of Estimates No

of 135 /5

District Chingleput

Work Constructing a Store yard & Quarters for Gornasta & Lascars Employed in
working the Lock at Shedioneoffam.

Quantities	Description of Work	Rate	Amount	Amount of each part
		R ^s P ^{as}	Rupies	Rupies
6 1/2 cts	10821 Cft of Bricks work in clay ——— 1/4	" 1 3	845	
2438	do of Bricks work in Channam ——— 2	" 2 "	305	
2703	1/4 cft of Roofing with Palminah, Couples Hips & Jack rafters, rafters nails flat & fantiles & Channam borders ——— 8	" " "	216	
9777	1/4 cft of Plastering ——— 1/4	3 4 "	318	
1348	do of Flooring ——— 2	4 8 "	61	
	9/4 cft of Teakwood wrought & put up ——— 2	12 "	128	
	1 Pair of Gate ——— Each	70 "	70	
	3 Pairs Batten Doors Complete ——— Each	14 "	42	
	6 Single Doors Complete ——— do	8 "	48	
	3 Pairs 4/4 glass window shutters Complete ——— Each	12 "	36	
1895	6/4 Making Embankment & raising foundation ——— "	1 "	118	
	14 feet Diameter Well ——— "	" "	80	
	Summary Charges ——— "	" "	113	
	Total Comings Rupies ———		2380	

Central Office of P.H.
Fort Saint George,
28th January, 1857.

Mr. Baker Colonel
Chief Engineer P.H.

Enclosed in a letter from the
Chief Engineer
to the Secretary to Government
Dated 27th Jan 1857
Review
H. G. M.

P.H. 187/57

Copies of correspondence on
the subject of working of
and stone work, &c. given
to the establishment at
Shedioneoffam.

Enclosure
In a letter

From

The Chief Engineer
D. P. W.

To

The Secretary to Govt.
D. P. W.

Dated 25th { Dec 3/57
Received

P. W. 187/57

N. 7516

Abstract Estimate for Constructing
a Store yard & Quarters for Garmastan
and Fuscar employed in working the Road
at Sheelancroft in the District
Chingaput.

Amounting to Rs. 2350 - -

Ed. M. B. 1857
1857

Ed. M. B. 1857

Ed. M. B. 1857

Ed. M. B. 1857

Ed. M. B. 1857

Ed. M. B. 1857

Ed. M. B. 1857

Ed. M. B. 1857

1857

1857

1857

1857

1857

1857

1857