1. Number of pages. 4
2. Date of repair. 22.6.57
3. Initials of Reference

M.R.O. 1—82,400—28-11-80.

MADRAS RECORD OFFICE.

Government of Madras.

Fee & Lic Works **DEPARTMENT.**

Cons. 21.4.57

G.O. No. 675 — Press Mis.

42-43

Dated 15 — 4 — 1857

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 21st April 1857.

No. 42. Read the following Report from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 1st April 1857, No. 11479.

Report D, on an estimate prepared by the District Engineer of Ganjam, for enclosing a Burial Ground at Purla Kimedy.

Amount of estimate, Rupees (380) three hundred and eighty, comprising the following items.

72 cubic yards stone in chunam at Rs. 1-0-3 per cubic yard, Rupees.....						73
138 do. brick in do. at Rs. 1-12-0	...	...	...	...	...	241
Excavating foundations...	...	...	...	...	...	4
1 Gate complete...	...	...	...	...	...	12
Superintendence and sundries	...	...	...	...	...	50
					Total Rupees...	380

1. The enclosure is to be 120 feet square, and the walls to be raised 6 feet above foundations, which are to be sunk 2 feet.

* No. 33, dated 23rd Jan. 1857, D. 1
§ " 5th Feby. 1857, D. 2
with
1 Abstract estimate.....D. 3
1 Plan.....D. 4

2. The letters noted in the margin from the Acting Collector of Ganjam,* and the Venerable the Archdeacon,§ are forwarded in support of the estimate, and the rates allowed for the work being moderate and sufficient, the Chief Engineer recommends the sum of Rupees 380 for entry in the Budget of 1858-59.

No. 43. ORDER THEREON, No. 675; dated 15th April 1857.

Referred to the Ecclesiastical Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

3
X

Ganjam District
Ecclesiastical
Burial grounds.

No 11479

Report on an Estimate prepared by the District Engineer of Ganjam for enclosing a Burial Ground at Purla Kimedy.

Amount of Estimate Rupees (380) three hundred and eighty comprising the following items.

72 Cub. Yds. Stone in Chunam
@ Rs 1-0-3 ½ Cs. Rs 73---
138 — do — brickwork in do @ Rs 12 — 241---
Excavating foundations — 1---
1 Gate Complete — 12---
Superintendence and Sundries — 50---
Total Rupees 380---

1.— The Enclosure is to be 120 feet square and the walls to be raised 6 feet above foundations, which are to be sunk 2 feet.—

2.— The letter noted in the margin from the Acting Collector of Ganjam, and the Memorable the Archdeacon, are forwarded in support of the Estimate, and the rates allowed for the work being moderate and sufficient, the Chief Engineer recommends the sum of Rupees 380 for entry in the Budget of 1838/39.—

* No 33 dated 25th Jany 1837
* " 5th Feby 1837

with
Abstract Estimate D1
Plan — D2

Central Office of Roads
Fort St George 1st April 1837.

The Secretary to Government
&c &c &c

Lieut Colonel
Chief Engineer

Public Works 1857 Despatch
Despatches 2nd & 4th Sep
No 680

D

To
Hon the Chief Engineer
& the Secretary & Government
P.W. Department.

No 675

Referred to the
Ecclesiastical Depart.
ment for consideration.

Scott Shirreff
15 April 1857

Dated 1st
Read 3d April

4 Enclosures

Copies to the Roads Engr
North & Rigl Excter
Disp. 16

No 11479

Report on an Estimate of
Rupees 380 prepared by the Executive
Engineer of Ranjaud for erecting
a Burial ground at Gunla
Hinedy, with the Chief Engineers
recommendation that the sum
be entered in the Budget of
1858/59.

No 42443.

Submitted
Recommended
Approved