Number of Piece 24
2. Date of repair. 23-6
3. Initials of Repairer
M.R.O. 1—22,400—22-11-50

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cons. 21-4-1857

G.O. No. 713 Press Mis.—

120-24

Dated 18—4— 1857.

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 21st April 1857.

No. 120. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 23rd March 1857, No. 11179.

SIR,

I have the honor, with reference to Clause 2 of Extract from the Minutes of Consultation No. 696, 18th October 1855, to submit two plans, with estimates accompanying, of buildings proposed to be erected for the accommodation of travellers at Nedumbringal on the high road to Tellicherry, from Manautoddy by the Penah Pass.

2. The plans, and estimates, were submitted to the Revenue Board who have stated in their Secretary's letter No. 439, dated 6th February 1857, that both are desirable works, and added their recommendation, that sanction be solicited for their construction.

3. The descriptive details of the works, are specified in the accompanying papers marked A. B.

4. The rates of the estimates are moderate but sufficient.

5. The sanction of Government is solicited for the required expenditure of Rupees (930) nine hundred and thirty, and instructions solicited as regards Budget entry.

No. 121. ORDER THEREON, No. 713; dated 18th April 1857.

The Right Honorable the Governor in Council does not consider the two estimates submitted with the above letter, amounting together to Rupees (930) nine hundred and thirty, for the erection of a Musafarkana and a Cookroom to be attached to the Travellers Bungalow at Nedumbrinjal in the District of Malabar to be of an emergent nature, he therefore directs the Chief Engineer to enter them in the Budget of 1858-59.

(Signed) H. FORBES,
Acting Secretary to Government.

Report A.

Estimate for constructing a Moosaferkanah at Nedabrinjal on the Road from Tellicherry to Manantody in the District of Malabar.-

Amount of Estimate Rupees 490 - - - Four hundred & Ninety

Comprising the following items.-

2618	6 ft.	Laterite in Chunam at	12 - - -	₹ 100 Ft. Rs.	314 -
2347	Sq ft.	Plastering with 1 Coat of Chunam - - - - - -	at 2 - - -	₹ Sq ft. Rs.	47 -
574½	D°	Flooring with Pelly and beaten Clay	at 1 - - -	D° Rs.	6
1054	D°	Roofing with Jungle wood Rafters reapers flat & Pantiles Chunam ridges & edges D°	at 16 - - -	D° Rs.	169 -
		2 Windows - - - - - - - - - - - -	at 5 - - -	Each Rs.	10 -
		2 Doors - - - - - - - - - - - - -	at 10 - - -	D° -	20
		Excavating Foundations and Sundries - - - - - - - - -		-	24 -
					590
		Deduct Value of Old Materials - - - - -			100
		Total Company's Rupees Four Hundred and Ninety - -			490 - -

The Building is to be raised on a basement of 1½ feet in height above foundations which are to be sunk 2 feet The walls 9 feet and the Verandah Pillars to be 6 feet - The Building is to Contain 2 Rooms and a Verandah -

2 Rooms each 14¼ by 12 feet
1 Verandah 31 by 7½ feet

Central Office of P. W. -
Fort Saint George
23 March 1857 -

W. Caldwell Colonel
Chief Engineer D. P. W. -

Report .B.

Estimate for constructing a Cook House to be attached to the Travellers Bungalow at Nedabrinchal on the Road from Tellicherry to Manuntoddy in the District of Malabar. —

Amount of Estimate Rupees 440 — Four hundred and forty. —

Comprising the following items —

2063	Cft. Laterite in Chunam including Plastering — at 12 — per 100 Cft. Rs.	248	-
	Sft. Flooring with Jelly & beaten Clay at 1 — per Sft. Rs.	5	
14×8½	Sft. Roofing with Junglewood Rafters		
870	Reapers flat and Pantiles Chunam ridges and edges Rows — at 16 — per Do. Rs.	139	-
	Cft. Junglewood — at 6 — per Cft.	3	
9½	3. Windows — at 5 — Each	15	
	2 Doors — at 10 — Do.	20.	
	Excavating Foundation and Sundries	10	
	Total Company's Rupees Four hundred and forty —	440.	

The Building is to be raised on the foundation which are to be sunk 2½ feet the walls 9 feet and the Verandah Pillars to be 6 feet. —

The Building is to Contain 2 Rooms and a Verandah

2 Rooms each 12 by 12 feet
1 Verandah 26½ by 7½ feet

Central Office of P. W.
Fort Saint George
23 March 1857

W. L. Salter Colonel
Chief Engineer D. P. W.

Examined and Recorded
Secretary's Office
Fort St. George
[illegible] 1857

Examined and Recorded
Secretary's Office
Fort St. George
[illegible] 1857

Examined and Recorded
Secretary's Office
Fort St. George
[illegible] 1857

Examined and Recorded
Secretary's Office
Fort St. George
[illegible] 1857

Buildings (Public) (New Work)

Abstract of Estimate No. of 1855

District Malabar.

Work. Constructing a Cook House to be attached to the Travellers Bungalow at Nedabuirchal on the road from Tellicherry to Manantody.

Quantities.	Description of work.	Rate. Rs	As.	P.	Amount. Rupees.	Amount of each part. Rupees.
C. Yds.						
2063	Cubic Ft. Laterite in chunam including plastering — 100 ft —	12	"	"	247	
478/12	Square Ft. Flooring with jelly and beaten clay — 100 ft —	1	"	"	5	
870	Square Ft. Roofing with Junglewood rafters rupers flat and pantiles chunam ridges and edges &c. — 100 ft —	16	"	"	139	
9/12	C. Ft. Junglewood — 1 ft —	"	6	"	4	
	3 Windows — Ea —	5	"	"	15	
	2 Doors — Ea —	10	"	"	20	
	Excavating foundation & Sundries —				10	
						440
	Total Company's Rupees Four Hundred and forty					440

Central Office of P. W.
Fort St. George
23 March 1857

Lt. Colonel
Chief Engineer

Tellicherry 23rd March 1857

Estimate B.

Estimate for Constructing a Cook House attached to the Travellers Bungalow at Nedabuirchal on the road from Tellicherry to Manantody in the District of Malabar amounting to Rupees 440.-

Quantities	Description of work	Rate.			Amount.	Amount of each part.
C. Yds.		Rs.	A.	P.	Rupees.	Rupees.

Enclosure

In a Letter

From

The Chief Engineer
D. P. W.

To

The Secretary to Govt
D. P. W.

Dated. 23d March/57
Received " "
P.W. 591/57
No. 1117/57

Abstract Estimate of the expense of constructing a Cook House to be attached to the Travellers Bungelow at Nedabrunchal Annamulay to Cos Rs. 490.

Buildings (Judicial.) (New Work)

Abstract of Estimate No. of 1857

District Malabar.

Work. Constructing a Moosafer Kanah at Nedabrinjal on the Road from Tellicherry to Mananteddy.

Quantities.	Description of work.	Rate. Rs	As.	P.	Amount. Rupees.	Amount of each part. Rupees.
C. Yds.						
2618	Cubic Fet. Laterite in chinnam ₹/100 cft	12	"	"	314	
2347	Square Ft Plastering with one coat chinnam ———— ₹/Sqre	2	"	"	47	
574½	Square Ft. Flooring with Jelly and beaten clay ———— ₹/Sqre	1	"	"	6	
1054	Square Ft. Roofing with jungle wood, rafters mapers flat and pantiles chunam ridges & edges ₹/Sqre	10	"	"	169	
	2 Windows ———— do	5	"	"	10	
	2 Doors ———— do	10	"	"	20	
	Excavating foundation ₹/Sundries				24	
						590
	Deduct value of old Materials ————					100
	Total Company's Rupees Four hundred and ninety ———					490

Central Office of P.W.
Fort St. George
23 March 1857.

A.B. Baker Colonel
Chief Engineer

Quantities	Description of work	Rate.			Amount.	Amount of each part.
C. Yds		Rs	A.	P.	Rupees.	Rupees.

Enclosure

No 4 to

From

The Chief Engineer
B. & P.

To

The Secretary to Govt
D.P.W.

Dated 23 Oct
Received 1st March/57

P.W. 591/57
No 111/1/1

Abstract Estimate of the expense of constructing a Mussafer Khana at Nedungal on the road from Sellicherry to Manantody in the District of Malabar Amounting to Co's Rs 190 ——

For Orders - See the Collector's letter on the state of the main building - 19 c

Public Works Despatch No 591 -

From the Chief Engineer 23 March/57 -

I see nothing to this Estimate - it appears to me that the repairs which have been executed - of which the expenditure is stated - have been necessary - and that the Estimate for the present year is too low for the work -

W Cully

Public Works Dept
Dis Cons Fort St George 18th April 1857
Nom. No. 391

To The Chief Engineer
For Secretary to Govt
Info

Dated 23rd March 1857
Received 24th Do
Rs 1117/4
Encd 9

Submits under Clause 2 of Ext. Min: of Cons: the 6th of 18th Oct. 55 Correspondence relating to the erection of a Cart Shed for the Travellers Bungalow at Nedumbrinjal in Chingleput together with Plan & Estimate, and under the circumstances represented recommends the sanction of the amount Rs. 1930/ One hundred & thirty on emergency.—

Withdrawn Order
No. 713. 18th April

No. 713

The Right Honorable The Governor in Council does not consider the two Estimates submitted with the above letter, amounting together to Rupees 1930/ One hundred and thirty, for the erection of a Mundapar Kana and a cart shed to be attached to the Travellers Bungalow at Nedumbrinjal in the District of Chingleput to be of an emergent nature. He therefore directs the Chief Engineer to enter them in the Budget of 1858/59.

Fort St George
18th April 1857

9 Copies to the Chief Engr. Dist 20:
with 7 Dup Encls

Nos 120 & 121.

25 March 231 Chapl
R15