1. Number of pages. 10
2. Date of request. 7-7-37
3. Initials of Reference.

M.R.O. 1—32 400—23-11-60

MADRAS RECORD OFFICE.

Government of Madras.

Publishing **DEPARTMENT.**

Cons. 12-5-57

G.O. No. 588	Press Mis.
35-36	
Dated 7—5—	18 57

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 12th May 1857.

No. 35. Read the following Extract from the Minutes of Consultation in the Judicial Department, dated 27th April 1857, No. 478.

Read the following Extract Minutes Consultation in the Public Works Department.

Referring for consideration report of the Chief Engineer on an Estimate for improving the Moonsiff's Court House at Oodamalcottah in the Coimbatore District, amounting to Rupees 420. } (Here enter 8th April 1857, No. 664.)

The Right Honorable the Governor in Council approves the additions proposed to be made to the Moonsiff's Court House at Oodamalcottah in the Coimbatore District; and considers that the Estimate should be sanctioned.

(True Extract.)

(Signed) T. PYCROFT,
Chief Secretary.

No. 36. ORDER THEREON, No. 888; dated 7th May 1857.

Ordered that the Estimate sanctioned in the foregoing Minutes Consultation amounting to Rupees (420) four hundred and twenty, for improving the Moonsiff's Court House at Oodamulcotta in the District of Coimbatore be entered in the Budget of 1858-59.

(Signed) H. FORBES,
Acting Secretary to Government.

No. 478.

Extract from the Minutes of Consultation ~~under~~ date the 27th April 1857.

Read the following Extract Minutes Consultation in the Public Works Department.

Referring for consideration report of the Chief Engineer on an Estimate for improving the Moonsiff's Court House at Oodamalcottah in the Coimbatore District, amounting to Rupees 420. } (Here enter 8th April 1857, No. 664.)

The Right Honorable the Governor in Council approves the additions proposed to be made to the Moonsiff's Court House at Oodamalcottah in the Coimbatore District; and considers that the Estimate should be sanctioned.

(True Extract.)

Chief Secretary.

To the Public Works Department, with 3 original enclosures.

Fxd F. Cartledge.

Buildings (Judicial) ..... (New Work)

Abstract of Estimate No ..... of 185/5

District Coimbatore

Work Improving the Mooneiffs Court House at Dovamulcottah.

Quantities.	Description of work.	Rate. Rs.	A.	P.	Amounts. Rupees.	Amount of each part. Rupees.
C. Yds.						
62	C.yds. Brick in Chunam with					
	ding Plastering ₹ C.yd.	3	"	"	185	
975	Sq.ft. Flooring with Jelly					
	in Chunam ₹ Sqre.	2	"	"	20	
1425	Sq.ft. Roofing with Palmirah					
	rafters ree pers flat ₹ pan tiles ₹ Sq.ft.	12	"	"	171	
	2 Windows ₹ each	4	"	"	8	
	2 Doors ₹ "	7	"	"	14	
						398
	Sundries & Excavating foundation ₹ Cu.yd.					22
	Total Rupees					420

Central Office of P.W.
Fort St. George
1st April 1857

A.E. Cotton Colonel
Chief Engineer & P.W.

Quantities	Description of work	Rate.			Amount.	Amount of each part.
C. Yds		R.	A	P.	Rupees	Rupees.

C3

Enclosure

In a Report

From

The Chief Engineer
S. P. W.

To

The Secretary to Govt
S. P. W.

Dated. 1st
Recd 3 April 57

P.W. 886 57
No 11479

Abstract Estimate of the
expense of improving the
Moonsiffs Court at Codamud-
cottah in the District of
Coimbatore Amounting to
Co's Rupees 420—"—"

1837. D.
In No. 645

Public Works 1857 Depte
Dy. to Cons: 12th May

No. 886

Extract from the Minds: of Consultation in the Judicial Department.

Dated 27th April
Received 7th May } 1857

3 Enclos: No. 478

Approving the additions proposed to be made to the Moonsiffs Court House at Oodamalaikah in the Coimbatore District & sanctioning the Estimate for Rs. 820 according by

No 35. to 36.

with an Order No. 888. 7th idem

No. 888

Ordered that the Estimate sanctioned in the foregoing Minit Cons: amounting to Rupees 1120/ four hundred and twenty, for improving the Moonsiffs Court House at Oodamulcotta in the District of Coimbatore be entered in the Budget of 1858/59.—

Fort St. George
7th May 1857

9 Copies to the Chief Engr. Dist.s with 2 Endrs.

1857 D. Pubs. No. 949