1. Number of pages. 6
2. Date of repair. 5.7.57
3. Initials of Reference. J

M.R.O. 1—82 400—22-11-50

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Con 12-5-57

G.O. No.	933	Press / Mis.
56-27.		
Dated	15-5-	18 .

Not to be folded or roughly handled

R

Fort Saint George, Public Works Consultation of 19th May 1857.

No. 26. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 8th May 1857, No. 187.

SIR,

1. I have the honor to forward under Clause 2 of Extract Minutes of Consultation, No. 696, dated 18th October 1855, an estimate of Rupees (1,000) one thousand, prepared by Lieutenant Palmer, Executive Engineer for building a wall round the burial ground at Chicacole in the Ganjam District, and to recommend the work for immediate execution.

2. The burial ground is at present, only enclosed by a mud wall, which is constantly damaged by rain, and does not suffice to keep out the cattle.

3. The estimate provides for building a wall, in all 763 feet long, by 7 feet in height above foundations, to be sunk 3 feet, the foundations are to be of rough stone in chunam, and the wall above of brick in chunam. The estimate also provides for a gate complete.

4. At the suggestion of the Assistant Collector, a piece of ground 117 feet long, by 32 feet broad, is proposed to be enclosed as a burial place for Dissenters; the cost of which is also included in the estimate.

5. The estimate now submitted was received with the letters* noted in the margin, and was forwarded for the opinion of the Venerable the Archdeacon, with Extract from Proceedings No. 11,975, dated 22nd April 1857.

* Acting District Engineer's letter No. 336, dated 4th April 1857.
Acting Collector's letter No. 162, dated 9th April 1857.

6. The Archdeacon in his reply,† suggests, that if any objection should be raised on the ground of expence, the wall might probably be built of brick in mud, instead of chunam, and considering that a brick in mud wall, with a coping of brick in chunam, and the whole plastered will suffice. I beg to enclose an estimate for the same, prepared in the Central Office, on the District data for such work; the estimate amounting to Rupees (750) seven hundred, and fifty.

† No. 287, dated 28th April 1857.

No. 27. ORDER THEREON, No. 933; dated 15th May 1857.

Ordered to be referred to the Ecclesiastical Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

Georgetown District

Central Office of R.W.
Port St. George 8th May 1837.

No. 187

From The Chief Engineer

To The Secretary to Government
R.D. Department

Ecclesiastical Burial grounds.

5 Enclosures
3 Letters
2 Estimates

Sir,

1. I have the honor to forward under Clause 2 of Extract Minutes of Consultation No. 696 dated 18th October 1833 an Estimate of Rupees (1000) One thousand, prepared by Lieutenant Palmer, Executive Engineer for building a wall round the burial ground at Chieaole in the Georgetown District and to recommend the work for immediate execution.

2. The burial ground is at present only enclosed by a mud wall, which is constantly damaged by rain, and does not suffice to keep out the cattle.

3. The Estimate provides for building a wall, in all 763 ft. long, by 7 ft. in height above foundations, to be sunk 3 ft. the foundations are to be of rough stone in Chunam, and the wall above of brick in Chunam. The Estimate

also

also provides for a Gate complete.-

4.- At the suggestion of the Assistant Collector, a piece of ground 117 feet long, by 32 feet broad, is proposed to be enclosed as a burial place for Dissenters, the cost of which is also included in the Estimate.

5.- The Estimate now submitted was received with the letters noted in the margin, and was forwarded for the opinion of the Venerable the Archdeacon, with Extract from Proceedings No 11975 dated 22d April 1837.

6.- The Archdeacon in his reply suggests that if any objection should be raised on the ground of expense, the wall might probably be built of brick in mud, instead of Chunam, and considering that a brick in mud wall, with a coping of brick in Chunam, and the whole plastered will suffice, I beg to enclose an Estimate for the same, prepared in the Central Office, on the District data for such work, the Estimate amounting to Rupees (750) Seven hundred and fifty.-

I have the honor to be
Sir
Your most Obed't Servant
Lieut Colonel
Chief Engineer

Ag. District Engineers Letter No 3368 d/ 4 April/37.
Ag. Collectors letter No 162 d/ 9 April/37.

No 207 d/ 28 April/37

Central Office Fort St George 8th May 1837

A. Sup. Engr N.C.

Pub: Works 1837 Dept.
Jr. to Govt 19th May.
No 942

From
The Chief Engineer
To. The Secretary to Government
P.W. Department

Dated 8th
Rec'd 9th May 1837.
5 Enclos:

Ex from Exec. Engr. Chicacole Dy 8th May 1837 Ct. No 95 Inf. 16 June
Inwards under Clause 2 of
Gt: Mun. Cons: No 696 dated 18th Oct. 36
for the consideration and orders of Govt. two Estimates for building a wall round the burial ground at Chicacole and recommends the work for immediate execution.

Estimate of Chunam is rd Rs 1000
Do. of Mud —— d —— 750

No 933 With an order 15th inst. May

No 26 & 27.

No 933

Ordered to be referred to the Ecclesiastical Department for consideration

J Dr

Fort St. George
15th May 1837

Reports to the Chief Engr with 5 Encls Ct. No 16