1. Number of pages 14
2. Date of [illegible] 8.7.37
3. [illegible]

M.R.O. 1—32,400—28-11-50.

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cons. 26.5.57

G.O. No. 943 Press Mis.

15—16

Dated 22—5— 1857

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 26th May 1857.

No. 15. Read the following Extract from the Minutes of Consultation in the Ecclesiastical Department, dated 11th May 1857, No. 207.

Read the following Extract Minutes Consultation Public Works Department.

(Here enter 20th April 1857.)

The Government authorize the Item " compound wall with two teak wood gates complete and levelling the ground" for the Waltair Church Rupees (875-2-3,) eight hundred, and seventy-five, annas two, and pice three, being included in the next Budget; any repairs that may be needed to the edifice may be executed under orders of the Chief Engineer.

2. The Governor in Council is not prepared to sanction more for so small a Church within a short distance of another in which there is ample accommodation.

(True Extract.)

(Signed) E. MALTBY,
Acting Chief Secretary.

No. 16. ORDER THEREON, No. 973; dated 22nd May 1857.

Ordered to be communicated to the Chief Engineer with reference to his report dated 17th December 1856, No. 8932, Z.

(Signed) H. FORBES,
Acting Secretary to Government.

Brick oven Rupees

Ecclesiastical Department

No. 207

Extract from the Minutes of Consultation
Dated 11th May 1857.

Read the following Extract
Minutes Consultation Public Works
Department.

Here enter 20th April 1857.

The Government authorize
the item "Compound wall with two teak
wood gates complete and levelling the
ground" for the Waltair Church Rs. 875-2-3
Eight hundred and Seventy five, Annas
Two, and Rice three, being included in
the next Budget. Any repairs that may
be needed to the edifice may be executed
under orders of the Chief Engineer.

2 The Governor in Council
is not prepared to sanction more
for

Fried over Rupees

for so small an Church putting a short distance of another pin which there is ample accommodation

[True Extract]

[illegible]

Sgt Chief Secretary

To

The Public Works Department

With 3 original Enclosures

[illegible]

Sgt Secretary

J. J. Robinson

Buildings (Ecclesiastical) (New Work)

Abstract of Estimate No. of 1855

District Vizagapatam.

Work. Constructing & making additions to the Waltair Church.

Quantities	Description of work	Rate. Rs	A.	P.	Amounts. Rupees.	Amount of each part. Rupees.
C. Yds						
	Alterations & Additions to the Church.					
842	Cft Rough stone in clay ——— Sft	"	"	4	10	
710	" Rough stone in chunam — " —	"	"	8	30	
2478	" Brick work in chunam — " —	"	1	2	181	
72	" Arch work in chunam — " —	"	2	1	9	
77½	" Cornice work in — " — "	"	2	1	10	
3600	Sup Sft Plastering with 2 coats of chunam ——— pSqre	1	14	7	69	
125	" Plastering cornice with 2 coats of chunam ——— "	2	14	9	4	
400	" Paving with brick on edge in chunam & a bevelling course underneath & plastering 2 coats of chunam — "	5	9	8	22	
2	Masonry columns ——— ea	18	"	"	36	
450	Sup Sft. Terracing with brick on edge Selly 3 courses of flat tiles & 3 coats of chunam in and out ——— pSqre	14	0	5	65	
	Excavating the foundation and the basement					
125	ood wrought & put up Sft	2	8			
	d removing part alls, steps & terrace					
	ried over Rupees					

Quantities	Description of work	Rate.			Amount.	Amount of each part.
C.Yds		Rs.	A.	P.	Rupees.	Rupees.
	Brought over Rupees				782	
	Cutting the walls and making archways and repairing the 1 door including the archwork &c. in brick masonry				14	
	Ornamental work to the capital of the Pillasters				1	
	1 Pair of circular strong panneled and venetian door with frames &c. complete				90	
	2 Pairs of panelled and venetian doors with frames &c.	40	8	"	81	
	1 Fixed venetian window with frames &c. complete				6	
	Removing the pulpit and reading desk out of the way of the Punkahs and reducing the dimension				15	
	Green paint 3 coats to the doors & Windows wood oil 3 coats to the Beams & Joists				35	
	2 Vestry rooms.					1091
830	6ft Rough stone in clay. Pcft	"	"	4	17	
661	" Rough Stone in chunam to Basement	"	"	8	20	
	Brick work in chunam	"		1		
	" k work in chunam	"				
	rick work in	"				
	Plastering with 2 ats of chunam Pfce			1		
	rried over Rupees					

Quantities	Description of Work	Rate			Amount	Amount of each part
	Brought over Rupees				292	1091
	Sqft Plastering cornice with 2 coats of chunam Pfce	2	14	9	6	
0	" Terracing with brick on edge, jelly 2 course of flat tiles & plastering 3 coats of chunam in and out	14	8	5	51	
5	" Flooring with Brick on edge in chunam & levelling course underneath & plastering 2 coats of chunam	5	9	8	15	
	Excavating foundation and filling the basement				7	
	Ornamental work to the capital of the 10 pillasters				1	
16	Cft. Teakwood 16 joists each @	2	8	"	40	
	2 Pairs of panelled and venetian door with frames &c. complete @	40	8	"	81	
	4 Pairs of Teakwood double windows venetian & glazed shutters with frames &c. complete	49	"	"	196	
	Green paint 3 coats to the doors and windows wood oil 3 coats to the joists				20	
						717
	Front Terrace					
	work in chunam Cft	"	1	2		
	ried over Rupees					

Quantities	Description of Work	Rate	Amount each part	Amount of
	Brought over Rupees		34	1808
1000	Sup/ft Plastering with 2 coats of chunam ₹/gre	1 14/	19	
100	" Plastering cornice with 2 coats of chunam "	2 14 9	3	
30	Cft Cornice work in chunam ft	" 2 1	4	
522	Sup/ft. Terracing with brick on edge jelly 3 course of flat tiles. & plastering 3 coats of chunam ₹/gre	14 8 5	76	
111½	Cft Teakwood wrought & put up ₹/cft	2 8 "	279	
	2 Masonry columns &c	17 8 "	35	
	Raising 6 Masonry columns @	3 12 "	22	
	Wood oil 3 coats to the Joists &c "		10	
				482
	Portcochere			
196	Cft Rough Stone in clay for foundation	" " 4	4	
408	Cft. Brick work in chunam cft	" 1 2	30	
	Cornice work in " " "	2 1	5	
	1/ft Terracing with brick ige jelly 3 course of flat & plast 1/2 " 3 coat chunam ₹/gre			
	Carried over Rupees			

	Brought ₹		88	2290
600	Sq/ft Plastering with 2 Coats Chunam Sq/ft	1 14 7	11	
125	Sq/ft Plastering Cornice with 2 Coats of Chunam	2 14 9	4	
22×2 dia	4 Masonry Columns with Pedestals of 4/ft Complete	22 " "	88	
	Excavating foundations.		1	
160-1-9	Teakwood wrought and put up	2 8 "	400	
	Wood oil 3 Coats to the joists &c		15	
				607
	Belfry			
256	Cft Arched roof with brick in Chunam.	" 2 4	37	
42	Cft Cornice work in Chunam	" 2 1	5	
600	Sq/ft Plastering with 2 Coats of Chunam.	1 14 7	12	
125	Sq/ft Plastering Cornice with 2 Coats of Chunam.	2 14 9	4	
13×½ dia	4 Masonry Columns.	9 12 "	39	
101-6-9	Cft Teakwood Summers	2 8 "	254	
	1 Teakwood Common Ladder of 30 ft long.		60	
	Wood oil 3 Coats to the Summers		5	
39	Cft Brickwork in Chunam for Spandrils.	" 1 4	3	
	Compound Walls.			
	Rubble in Clay for foundation using old Stones.	" " 2		

	Brought				91	3316
1274 3/4	Rough Stone in Chunam for Compound walls using 6 Cd Stone.	"	"	6½	431	
112	Cft Brick work in Chunam for 4 gate pillars.	"	1	2	8	
200	Sft Plastering with 1 Coat Chunam	1	4	6	3	
	Excavating foundation				26	
12x6	2 Teakwood Gates with iron bars and fixtures & painted Complt:	66	"	"	112	
	Levelling the ground 50 ft around the Church				204	
						875
	Superintendence					200
	Contingencies &c					9
	Total Co Rupees					4400

Central Office of P.W.
Fort St George
17 Decr 1856 -

Chas Foster Colonel
Chief Engineer D.P.W.

Z2

13

Enclosure

In

From

The Chief Engineer

DPW

To

The Secretary to Govt

DPW

Dated 17 December 1856

Recd. P.W. ~~3000~~/56

No 8932.

P.W. 958/57

Abstract Estimate for making addition to the Church at Waltair in the District of Vizagapatam Amd [illegible]

Rupees 4

Comm 21st April 1857 No 44-142

Public Works 1857 Dept
Dito Comm 26th May.

No 958

Extract from the Minutes of Consultation in the Ecclesiastical Departt

Dated 11th } May 1857
Received 12th }

3 Enclos: No 207

Authorizing the intended wall with two teak wood gates complete & levelling the ground for the Waltair Church Rs 875-2-8 Being included in the next Budget Estimate observing that any repairs to the Office may be executed under orders of the Ch Engr.

With an order of No 973. 22nd May

No 15+16.

No 973

Ordered to be communicated to the Chief Engineer with reference to his Report dated 17 December 1856 & No 8932, 2-

Fort St George
22nd May 1857

9 Copies to the Chief Engr. with 2 Encls. Dispt 23.