

MADRAS RECORD OFFICE

Government of Madras.

DEPARTMENT.

G.O. No.

Press
MIS.

Dated

18

Not to be folded or roughly handled

No. 17. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 14th January 1858, No. 6624.

SIR,

I have the honor to forward, for submission to Government, an estimate of Rupees (9,050) nine thousand and fifty, which is already entered in the Budget for constructing Offices for the Division and Brigade Staff and Guard Room for a Cavalry Picquet at Bangalore.

Vide accompanying letter No. 3204 dated 24th December 1857.

2. This Estimate was not received till lately and having been referred for the opinion of the Commander in Chief, has now been returned with His Excellency's approval.

3. The plans appear suitable and convenient, the rates of the estimate are moderate and sufficient and the amount is accordingly recommended for sanction.

Letter from Major A. DEBUTTS, Acting Superintending Engineer in Mysore; to Colonel C. E. FABER, Chief Engineer, dated Bangalore, 20th November 1857, No. 141.

SIR,

I have the honor of informing you, that in consequence of the Lieutenant General Commanding the Division, having added a Cavalry Picquet Guard Room, Pension Pay Office, &c. to the Public Offices at this station, I have prepared a revised Plan and Estimate for them, which amounts to Rupees (9,050) nine thousand and fifty.

This estimate will of course in due time come before you, for your approval, but I now apprise you of the same, as I entered a sum of Rupees 3,500 in No. 1 of my Budget Lists as you may feel disposed with this information, to enter the corrected sum in your General Budget.

No. 3204.

Quarter Master General's Office, Fort St.
George 24th December 1857.

Submitted the following letter to the
Commander in Chief, from Chief Engineer.
No. 6142, dated 22nd December 1857.

His Excellency's order thereon.
His Excellency the Commander in Chief
entirely approves of the Plan.

Forwards, for opinion, Plan and Estimate for Offices for the Divisional Staff and Cavalry Picquet Guard Rooms, adjoining the Cantonment Main Gaurd at Bangalore.

There appears however an error in the describing of the Rooms, two sets having been allotted to the Deputy Assistant Quarter Master General of the Division.

(Signed) F. A. REID,
Quarter Master General of the Army.

No. 18. ORDER THEREON, No. 110; dated 21st January 1858.
Ordered to be referred to the Military Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

flattiles & plastering of coats of Chinnam 24 14 644 2554

... ..
... ..
... ..

... ..
... ..
... ..

... ..
... ..
... ..
... ..
... ..
... ..
... ..

... ..
... ..
... ..
... ..
... ..
... ..
... ..

flat tiles & plastering of coats of Chumam, Feb 24 14	644
Carried over	5559

Buildings ()

(New Work)

9x

Abstract of Estimate No. of 185 / 5

District. Mysore:

Work Constructing Offices for Deputy Asst. Quarter Master General's Pay Office with European Cavalry Regiment Guard room. Division Pay Office, Regiment Guard Room, adjoining the Cantonment Main Guard at Bangalore.

Item	Description of Work	Rate		Amount	Amount of each part
		R ^{rs}	P ^{cs}	Rupies.	Rupies.
125	Pay Office with Upper story and European Cavalry Regiment Guard Room				
127	Sup ^{ft} Unroofing		6		4
188	Sup ^{ft} Removing the old walls		1/4		5
	Taking down the old Ceilings, Roofs and Summers				3
127	Sup ^{ft} Excavation		1		16
127	Sup ^{ft} Foundation Stone in sand		9		123
938	Sup ^{ft} Basement Stone in Chumam		16		88
1249	Sup ^{ft} Brick in Chumam		110		1404
202	Sup ^{ft} Arch work in Chumam		34		12
123	Sup ^{ft} Cornice work in Chumam		511		84
185	Sup ^{ft} Plastering with coat of Chumam	2	4		353
15	Sup ^{ft} Whitewashing Inside 2 Coats		2		9
36	Sup ^{ft} Bluewashing Outside 2 Coats		22		12
27	Sup ^{ft} Filling the Basement with sand	1	8		21
12	Sup ^{ft} Paving with granite stone in sand	7			80
12	Sup ^{ft} Edging the Verandah		2		4
12	Sup ^{ft} Teakwood wrought & put up	1	18		659
182	Rafter Sails				8
9	Sup ^{ft} Terrace with Brick and edge &ally Course of flat tiles & plastering & coats of Chumam	24	1/4		641
	Carried Over				6559

Quantities 6 Yds.	Description of Work.	Rates			Amounts	
		R ^s	A ^s	P	Rupies	Rupies of each part.
	Brought forward				3559	
516	1/2 Slope Roofing the Verandah with 1 Inch thick teak Reapers					
	Nails 3 Course of flat tiles and plastering 3 Coats of Chunar	19	4		99	
	6 Pairs of pannelled Doors with frames & Iron works ^{1/2} Complete	28			168	
	21 Pairs of Windows inside glazed outside Pannelled & Shutters with frames and Iron works ^{1/2} Complete	22			462	
14	25 Swing Windows Complete Ea	6			150	
	Lead painting the above with Linseed Oil 3 coats	5	10		79	
	Offices for Deputy Adjutant Quarter Master Generals					4517
2852	1/2 Excavation					
2419	1/2 Foundation Stone in sand		1		15	
529	1/2 Basement Stone in Chunar		9		113	
5680	1/2 Brick in Chunar		16		50	
157 1/2	1/2 Arch work in Chunar		10		651	
108	1/2 Cornice work in		34		33	
1270	1/2 Filling the Basement with sand		5	11	40	
1090 1/2	1/2 Paving with granite stone in sand		1	8	19	
367	1/2 Edging the Verandah		7		76	
9243	1/2 Plastering 1 coat of Chunar		2		4	
	Carried Over				208	
					1209	4517

Quantities	Description of work	Rates			Amount	
		R ^s	A ^s	P	Rupies	Rupies of each part
	Brought forward				1209	4517
4257	1/2 Whitewashing inside 2 Coats		2		5	
4986	1/2 Bluewashing Outside 2 Coats		2	2	7	
202-5 1/2	1/2 Teakwood wrought and put up		10		329	
140	Rafter Nails			3	6	
964 1/2	1/2 Terracing with Brick on edge & 3 Course of flat tiles and 3 Coats of plastering to the Ceiling and to top of the terrace	24	14		240	
846	1/2 Slope Roofing the Verandah & Rooms with 1 Inch thick teak Reapers nail	19	4		163	
	3 Course of flat tiles and Plastering 3 Coats of Chunar					
7	Pairs of Pannelled Door with frames and Iron works ^{1/2} Complete	28			196	
11	Pairs of windows inside glazed outside Pannelled Shutters with frames ^{1/2} Complete	22			242	
8	Swing windows Complete	6			48	
1150	1/2 Lead Painting the above with Linseed Oil 3 coats	5	10		64	
	Pension Pay Office and Native Cavalry Picquet Guard Room					2509
632	1/2 Excavation			1	3	
533	1/2 Foundation Stone in sand		9		25	
146	1/2 Basement Stone in Chunar		16		14	
930	1/2 Brick in Chunar		10		107	
31	1/2 Archwork in		34		7	
28	1/2 Cornice in		5	11	11	
	Carried Over				167	7026

Quantities	Description of work	Rate	Amount	Amount of each part
	Brought forward		167	7026
1676	Brick Round Pillars with plastering & chunam Each	11 8 "	46	
1676	Supplft. Plastering with one coat of chunam	2 4 "	38	
1188	Whitewashing inside 2 boats	" 2 "	1	
1047	Blue Washing Outside 2 boats	" 2 2 "	1	
567	8ft. Filling the Basement with sand	1 8 "	8	
586	Supplft. Flooring with granite stone in board	7 " "	41	
41	Trimming feet of Edging the Verandah 15 couples with 1 collar beam to each	" 2 "	5	
	\$ Each	8 " "	120	
4226	8ft. Teakwood wrought and put up	1 10 "	69	
47	Rafter Nails for Verandah Joists Each	" " 7	2	
508	Supplft. Roofing with Teak reapers Nails Flat and Pantiles	11 4 6	57	
381	Slope Roofing the Verandah with 1 Inch thick Teak reapers Nails 3 course of flat tiles plastering 3 boats of chunam	19 4 "	73	
102	Trimming of Chunam borders around the Eaves and Ridges	" " 7	4	
317	Pair of Ridge Ventilators Complete	1 7 1	46	
	Pair of Pinned Door Shutters with frames and brass works & complete	28 " "	28	
	Carried Over		706	7026

Quantities	Description of work	Rate	Amount	Amount of each part
	Brought forward		706	7026
3	Pairs of windows glazed inside and framed out shutters with brass works & complete	22 " "	66	
175	Supplft. Lead painting the above with Linseed Oil 3 coats	5 10 "	10	
	Total Native Cavalry Picket Guard Room			782
	Add contingencies and superintendence			460
	Total Company's Rupees & Pice thousand and fifty			9050

Central Office of P.W.
Fort Saint George
14 Jan 1858

M. Fisher, Colonel
Chief Engineer P.W.

Enclosure

In a letter

From

The Chief Engineer

D. P. W.

To

The Secretary to Govt.

D. P. W.

Dated 14/3

Received

14/3/58

DD 85/58

N^o - 1624

Abstract Revised Estimate
for Building Offices for Deputy
Asst. Adjt. & Quarters, General's of
the Division Pay Office with Eu-
ropean Cavalry Regt. Guard Room
Pension Pay Office & Native Cavalry
Regt. Guard Room, Adjoining the
Cant. Barracks at Bangalore in the
District of Allypore.
Amounting to Rs. 9050.

Central Office of P. W.
Fort Saint George
14 January 1858.

N^o 1624
From The Chief Engineer
To The Secretary to Government
Public Works Department

Sir,

Military

I have the honor to forward, for
your consideration, an Estimate of Expenses
for the construction of Offices
for the Division and Regt. staff and
Guard Room for a Cavalry Regiment at Bangalore.

The Estimate was not received
till late and having been referred for the
opinion of the Commander in Chief, has now been
received with His Excellency's approval.

The above is a suitable and
economical estimate and the amount is accordingly
recommended.

Yours accompanying
letter of 3205/57
Dec 5/57

Recommended for election.

John C. Brown

W. H. C. Brown

14 March 1888

W. H. C. Brown

W. H. C. Brown

W. H. C. Brown

W. H. C. Brown

W. H. C. Brown

W. H. C. Brown

W. H. C. Brown

W. H. W.

understand to be referred
to the Military Department
for consideration.

24

Amounting to £4 10

Chas. W. Gregory
214th January 1858

4 Papers to the Society of the 20th Dec 1822.

Handwritten: *Handwritten*

1876/7

Feb. 14. 1877 25.1 day
- 23.1 day 183 - 169 26.1

[illegible]

1863