1. Number of sheets: 14
2. Date of [illegible]: 20-7-37

M.R.O. 1—32 400—23-11-30

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Letter 21-7-57

G.O. No. 1368 — Press / Mis.

15-16

Dated 16-7- 18 57

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 21st July 1857.

No. 15. Read the following Extract from the Minutes of Consultation in the Military Department, dated 30th June 1857, No. 2149.

Read the following Extract from the Minutes of Consultation in the Public Works Department.

Referring a Report from the Chief Engineer recommending the estimate of Rupees 1840, for constructing a shed and store and Guard room for the Rifle Musketry Depot at Secunderabad for entry in the Budget of 1858-59. } (Here enter 22nd June 1857, No. 1209.)

The Governor in Council observes that the building referred to will not now be required, it being the intention of the Commander of the Forces shortly to discontinue the Musketry Depôt.

(True Extract.)

(Signed) C. A. BROWNE, Colonel,
Secretary to Government.

No. 16. ORDER THEREON, No. 1368; dated 16th July 1857.

Ordered to be communicated to the Chief Engineer with reference to his Report dated 2nd June 1857, No. 863, G.

(Signed) H. FORBES,
Acting Secretary to Government.

MILITARY DEPARTMENT.

No. 2149.

Extract from the Minutes of Consultation, 30th June 1857.

Read the following, Extract from the Minutes of Consultation in the Public Works Department, under date the 22nd June 1857, *No.* 1209.

Read the following Report from Colonel C. E. Faber, Chief Engineer ; to H. Forbes, Esq., Acting Secretary to Government, dated 2nd June 1857, No. 863.

Report G, on an Estimate prepared by the Superintending Engineer, Hyderabad Subsidiary Force, for constructing a Shed, and Store, and Guard room, for the Rifle Musketry Depôt at Secunderabad.

Amount of estimate Rupees (1,840) one thousand, eight hundred and forty, comprising the following items, of which the details are given in the accompanying abstracts.

Constructing shed	- -	Rs. 960
do. Store and Guard room	,,	880
Total		1,840

1. The shed is to consist of an open double verandah, raised on a basement 2 feet in height. The foundations of the pillars are to be 3 feet in depth, the centre pillars to be raised 18 feet, and the side pillars 8 feet above the basement, the roof to be tiled.

2. The building for the Store and Guard room, is to be raised on a basement 3 feet in height above foundations, which are to be sunk 3 feet. The centre wall is to be raised 18 feet, the end walls including Gables 15 feet on an average, and the side walls 12 feet, supporting a tiled roof.

3. The building is to contain 2 rooms, each 20 feet long, 9' 3" broad.

4. The approval of His Excellency the Commander-in-Chief to the proposed buildings is given in the accompanying copy of letter, No. 1329, dated 9th instant, and the Chief Engineer recommends the estimate, in which the rates allowed are moderate and sufficient, for entry in the Budget of 1858-59.

Referred to the Military Department for consideration.

(A True Extract.)

(Signed) H. FORBES,
Acting Secretary to Government.

The Governor in Council observes that the building referred to will not now be required—it being the intention of the Commander of the Forces shortly to discontinue the Musketry Depôt.

(True Extract and Copy.)

Secretary to Government.

To the Department Public Works, with 4 enclosures. 4 spare copies.
,, Quarter Master General.

Exd. A. A. DeMonte.

Buildings ( ) (New Work)

Abstract of Estimate No. of 185 /5

District Secunderabad

Work Constructing Store and Guard Rooms for the Rifle Musketry at Secunderabad

Quantities	Description of Work	Rates			Amount	Amount of each part.
C. Yds.		Rs	As	P.	Rupees.	Rupees.
3149	Cft. of Brickwork in Chunam — Cft.	"	1	11	413	
37	do of Arch work in Chunam — do	"	2	8	6	
59	do of Cornice work in Chunam — do	"	3	4	12	
400	Sft. of Flooring with jelly and Chunam — Sft.	3	10	5	15	
3384	Sft. of Plastering with 1 Coat of Chunam — Sft.	2	3	"	74	
690	Sft. of Roofing with teakwood, reapers nails, flat & pantiles, & Chunam borders — Square	10	12	5	74	
13	Sutingmundums for rafters Each	8	"	"	104	
1	Cuddies for wall plates — Each	1	"	"	4	
5	Doors Complete — do	25	"	"	125	
	Excavating foundation, raising the floor & ramming the same	"	"	"	10	
	Sundries				43	
					Total Company's Rupees —	880

Central Office of P.W.
Fort Saint George,
2nd June 1857.

Lt.
Asst. Engr. R.E.

W. Eaton Colonel
Chief Engineer P.W.

Quantities	Description of Work	Rates			Amount	Amounts of each part
C. Yds.		Rs.	As.	P.	Rupees	Rupees

C.3

Enclosure

Ina Report

From,

The Chief Engineer
D.P.H.

To,

The Secretary to Govt
P.W.D.

Dated 2nd June 1857
Recvd

No 863.
P.W. 1419/446/57

Abstract Estimate for Constructing Store & Guard Rooms for the Rifle Musketry at Secundrabad
Amounting to Co. Rupees 880—

Sd/
Sec. No 2640 of 1857

Buildings ( ) (New Work)

Abstract of Estimate No of 185 /5

District Secundrabad

Work Constructing a Shed for the Rifle Musketry Depot at Secundrabad

Quantities	Description of Work	Rate			Amount	Amount of each part
C. Yds.		Rs	As	P	Rupees	Rupees
1530	Sft. of Brickwork in Chunam Sft.	"	1	11	183	
1566	Sqft. of Plastering with 1 Coat of Chunam Sqrs	2	3	"	34	
136½	do of Flooring with jeerg & Chunam	3	10	5	50	
2030	do of Roofing with teakwood, rafters, nails, flat and pantiles, and Chunam borders Sqrs	10	12	5	219	
21	Surjpinnandums for Summers &	8	"	"	168	
30	Do for rafters 2 feet apart &	8	"	"	240	
	Ceiling the beams & rafters	"	"	"	15	
	Sundries				46	
	Excavating foundation & raising the floor & Ramming the same	"	"	"	5	
	Total Company's Rupees					960

Central Office of P.W.
Fort Saint George
2nd June 1857.

Wm Caldwell Colonel
Chief Engineer D.P.W.

D.P.W. Engr. C.C.

Quantities.	Description of Work.	Rates			Amount.	Amount of each part.
C Yds.		Rs.	as.	P	Rupees	Rupees

G:

Enclosure

In a Report

From,

The Chief Engineer

& Sp. P. W.

To,

The Secretary to Govt.

Dpt W.

Dated 2nd June 1857

Recd

1419

P.W. 446/57

No. 863.

Abstract Estimate for Constructing a Shed for the Rifle Musketry Depot at Secunderabad.

Amounting to Comps. Rupees 960—

Ref

Lieut. 2640 of 1857

Cons: 23d June 57 No 5 to 2.

Public Works Rd 1857 Dept
Dft to Cons 21st June

C. F. 1419

Signal from the Mins
& Con in the Military
Department
Dated 20th June
Received 22nd July 1857

Case lodged with Maj
given to Lieut Dept 24/7/57 No 2149

Observing that the
Rifle Musketry Depôt
at Chatham will
not now be required;
it being the intention
of the Commander of the
Forces shortly to dis-
continue the Musketry
Depôts.

No 15 & 16.

Wilkes on order
No 1368. 16th July

No 1368

Ordered to be com-
municated to the Chief
Engineer with reference
to his Report dated 2d June
1857 No 863 C.

Fort St George
16th July 1857

Copies to the Chief Engr Dirs No 19
with a Plan.

Letter No 2640 of 1857.