1. Number of
2. Date of
3. Initials of Re

M.R.O. 1—82,400—28-11-30.

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Con. 4. 8:57

G.O. No. 1489 Press Mis.

52.23

Dated 1 — 8 — 18 57

Not to be folded or roughly handled

IX

Fort Saint George, Public Works Consultation of 4th August 1857.

No. 52. Read the following Extract from the Proceedings of the Chief Engineer, dated 13th July 1857, No. 1985.

Read the following Extract from the Minutes of Consultation Public Works Department.

(Here enter 16th June 1857, No. 1156.)

Resolved, with reference to Extract Minutes Consultation No. 1156 of the 16th Ultimo, to submit the following estimates for enclosing Burial Grounds at—

	Rs.
Rajahmundry	1,210
Cocanada	355
Juggernaikpoorum	930
Total...	2,495

two thousand, four hundred and ninety-five.

2. The dimensions of the Burial Grounds have been reduced as suggestde by the Venerable the Archdeacon in his letter dated 3rd December 1856, a copy of which was forwarded to Government with my communication No. 8814 of the 12th Idem, and in the accompanying letter, dated 27th November 1856; and in view to still further reducing the estimates the walls are to be built, as the case may be, with brick or stone in clay, with a coping only of brick or stone in chunam; the whole to be plastered or pointed with chunam.

3. The estimates have been revised in the Central office on the rates usual in the Rajahmundry District, and it remains for Government to pass orders whether they are to be sanctioned for immediate execution, or to be entered in the Budget of 1858-59.

(Signed) C. E. FABER, Colonel,
Chief Engineer.

No. 53. ORDER THEREON, No. 1489; dated 1st August 1857.

Ordered to be referred to the Ecclesiastical Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

Buildings / (New Work)

Abstract of Estimate No of 185 /5

District Rajahmundry

Work Constructing a Wall for enclosing the Ground of the new Burial Ground at Rajahmundry.—

Quantities	Description of Work	Rates			Amount	Amount of each part
C. Yds		Rs	As	P	Rupees	Rupees
772	C. ft. Brick in Clay ——— C. ft.	"	1	3	60	
178	Do. Brick work in Chunam for Coping the wall & flooring Do.	"	1	7	18	
875	Sup. ft. Plastering with Chunam ——— Do.	1	10	"	14	
378	Do. Roofing with Rafters Reepers wall plates beams Nails Tiles and Chunam boarders ——— Do.	12	8	"	47	
	Excavating the foundation and levelling the Earth ———				2	
	1 Door Complete ———				8	
	1 Window. Do. ———				4	
						153
	Compound walls.					
8296 7/8	C. ft. Brick in Clay ——— C. ft.	"	1	3	648	
959 3/8	Do. Brick work in Chunam for Compound walls & gate Pillars.	"	1	7	95	
	Carried Over ———					153

Quantities	Description of Work	Rates			Amounts	Amount of each part
C Yds		Rs	As	P	Rupees	Rupees
	Brought forward					153
8875	Sub Ft Plastering with Chunam	1	10	0	144	
	2 Masonry Urns				3	
	Excavating the foundation and levelling the earth				8	
	1 Gate Door Complete				50	
						948
	Sundry Charges at 10 Cent	10	"			109
	Total Company's Rupees One thousand Two hundred and Ten					1210

Central Office of D. W.
Fort Saint George
18th July 1857

A. Taylor Colonel
Chief Engineer D. P. W.

W
A. Asst. Engr. M.C.

Enclosure
In a letter

From
The Chief Engineer
D.P.W.

To
The Secretary to Govt.
D.P.W.

Dated 1st July 1857
Received

No. 1985
R 143/57

Abstract Estimate for
Constructing a Wall for
enclosing the ground of the
new Burial Ground at
Rajahmundry.

Amounting to C.R. 1210—
E/57 D.
3 Aug

Buildings / / (New Work)

Abstract of Estimate No. of 185 /5

District Rajahmundry

Work Constructing a Compound Wall to the Burial Ground at Doggarnaickpooram.

Quantities	Description of Work	Rates			Amount	Amount of each part
Cub Yds		Rs	As	P	Rupees	Rupees
6814½	Cft Brick in Clay — Cft	"	1	6	639	
1255	Do Brick work in Chunam for compound walls and 2 Gate Pillars — Do	"	1	10	144	
4800	Sqft Pointing in Chunam — Sqft	"	12	"	36	
	2 Masonry Arms complete				3	
	Excavating the foundation and levelling the earth —				6	
	1 Gate Door complete —				20	
	Sundries and Superintendence at about — — — Cent	10	"	"	82	
	Total Company's Rupees Nine hundred and Thirty					930

Central Office of D.P.W.
Fort Saint George
16th July 1857

A.W. Cotton Colonel
Chief Engineer D.P.W.

W
A. Asst Engr

Quantities	Description of Work	Rates			Amounts	Amounts of each part
C Yds.		Rs	As	P	Rupees	Rupees

Enclosure

In a letter

From

The Chief Engineer
D.P.W.

To

The Secretary to Govt.
D.P.W.

Dated 13th July/57
Received 14/31/57

No. 1985

Abstract Estimate for constructing a Compound Wall to the Burial Ground at Jaggarnaickpooram in the Distruct of Rajahmundry.

Amounting to Co's Rs. 930-0-0

E/57 D.
Le No. 313.

Buildings / / (New Work)

Abstract of Estimate No of 185 /5

District Rajahmundry

Work Constructing a Compound wall to the Burial Ground at Cocanada.

Quantities	Description of Work	Rates			Amount	Amount of each part
Cft. Yds		Rs	As	P	Rupees	Rupees
2410½	Cft. Brick work in Clay-Mortar	0	1	6	226	
456	Do. Brick work in Chunam for Compound walls and 2 Gate Pillars	4	1	10	52	
2500	Sup. Ft. Painting in Chunam Do.	0	1	12	19	
	2 Masonry Arms				3	
	Excavating the foundation and leveling the earth				3	
	1 Gate Door				20	
	Sundries and Superintendence at 10 per Cent	10	"	"	32	
	Total Company's Rupees Three hundred and fifty five					355

Central Office of P.W.
Fort Saint George
13th July 1857.

Wd Slater Colonel
Chief Engineer D.P.W.

W
A. Supt. P.W.

Quantities	Description of Works	Rates			Amounts	Amounts of such part
C Yds.		Rs	As	P	Rupees	Rupees

Enclosure

In a letter

From

The Chief Engineer

D. P. W.

To

The Secretary to Govt.

D. P. W.

Dated 13th July 1857.

Received 17th July 1857.

P. W. R. 1631/57.

No. 1985

Abstract Estimate for Constructing a Compound wall to the Burial Ground at Cocanada in the District of Rajahmundry.

Amounting to C. Rs. 355.

6/57. D.

Ac. No. 313.

No. 1985

Extract from the Proceedings of the Chief Engineer in the Department of Public Works.

Under date the 13th July 1857.

Read the following Extract from the Minutes of Consultation Public Works Department.

[Here Enter 16th June 1857 No. 1156.

Resolved, with reference to Extract Minutes Consultation No. 1156 of the 16th Ultimo, to submit the following Estimates for enclosing Burial Grounds at

Rajahmundry	Rupees 1210.
Cocanada	355.
Juggernaikepoorum	930.
Total Rupees	2495.

Two thousand four hundred and Ninety five.

2. The dimensions of the Burial grounds have been reduced as suggested by the Honorable the Archdeacon in his letter dated 3d December 1856, a Copy of which was forwarded to Government with my Communication No. 8814. of the 12th Idem, and in the accompanying letter, dated 27th November 1856; and in view to still further reducing the Estimates the walls are to be built, as the case may be, with bricks or stone in Clay, with a Copeing only of brick or stone in Chunam; the whole to be plastered or pointed with Chunam.

The

3. The Estimates have been revised in the Central Office on the rates usual in the Rajah: mundry District, and it remains for Government to pass orders whether they are to be sanctioned for immediate execution, or to be entered in the Budget of 1858/59.—

Alex Taylor Colonel
Chief Engineer

Ag
Ch. Engr. W.C.

To

The Secretary to Government
Public Works Department

Cons: 16th June /57 Nos 104 & 105.
—"— 16th " " " 92 & 93.

29-7-63

No 1489.
Ordered to be returned to the
Ecclesiastical Department with
enclosures.
Chief Engr.

Fort St. George
1st August 1857

Recd at the Fort St. George
1st August 1857

Pub. Nos 1857. Departt.
Dto Dec 4th August
No. 1431

Extract from the Proceedings of
the Chief Engineer F.S.F.
To
The Secretary to Govt.
P.W.D.

Dated 13th
Recd 15th } July 1857

No. 1985 Returned 4 Encs
5-2-60

Enclosures
Ex Minutes of Cons Ecclesiastical Dept 16th
& 17th August 57 Cons Nos 1163 & 1164
Forwards as requested an Estimate
Minute Cons No 1156. of the 16th
Ultimo. Estimates Amounting in
the Aggregate to Rupees 2495.
for Enclosing Burial grounds
at Rajahmundry, Cocanada &
Juggernaickpooram in the
Rajahmundry District.

Ro. of the Ecclesiastical & Depart
Dg Dept 1st/59 Cons 25th Augs
No. 1489. 1st Aug.

With an order

No 1052 & 53.