3. Height of letters

K.R.O.—[illegible]

MADRAS RECORD OFFICE.

Government of Madras.

[illegible] DEPARTMENT.

G.O. No. [illegible] Press Mis.

Dated [illegible] 18[illegible]

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 8th September 1857.

No. 5. Read the following letter from Colonel C. E. FABER, Chief Engineer; to H. FORBES, Esq., Acting Secretary to Government, dated 27th August 1857, No. 3196.

SIR,

I have the honor to forward for submission to Government a plan and estimate of certain additions and improvements proposed to be made to the buildings occupied by the Commissioner of Police on the Pantheon road, amounting to Rupees (1,600) one thousand, and six hundred. The additions consist of a verandah to be added on the eastern side of the office, fixing wooden rails to the Cashkeeper's room, and erecting a shed for bullocks, drivers, lascars and tent of the Coroner.

2. The additions are recommended by the Commissioner, supported by the Barrack Master and the rates appear moderate and sufficient.

3. I beg to recommend the estimate for entry in the Budget of 1858-59 if not thought fitting for immediate execution.

No. 6. ORDER THEREON, No. 1671; dated 2nd September 1857.

Ordered to be referred to the Judicial Department for consideration.

(Signed) H. FORBES,
Acting Secretary to Government.

Report

Estimate for Erecting a Verandah on the east side of the Building & placing the Teakwood common Rails to the Cook Keeper's Room of the same & also erecting a common shed for the use of the Bullock Carts Tents Lascars & drivers & for grain boiling within the Compound of the Office of the Commissioner of Police on the Pantheon Road.

Amount of Estimate Rupees 1600 – One thousand Six hundred Comprising the following items –

No. 1

Erecting a Verandah on the east side of the Building

2835	Sq.ft	Brick work in Chunam	"	1¼	Sq.ft 317
108¾	Do.	Flat Arch work in Chunam over the one Door and Six windows	"	2½	Do. 19
582		Cornice work in Chunam to the extremity of the Verandah	"	3	Do. 9
6307⅛		Terracing with Brick on edge 3 Course flat tiles & plastering 3 coats Chunam over the Same	192		Sq.ft 121
2350		Plastering with 2 Coats Chunam to the walls &c.a	1 13 9		Sq.ft 44
200	Do.	with 2 Coats to Do. to the Cornice	2 13 9	Do.	6
570		Flooring with 8 in.s Sq.r Bricks in Chunam and a Levelling course of old bricks underneath	5 7 10	Do.	28
		Coolly hire for cutting & uniting the old and new Terrace			6
	Do.	for removing & Windows & Sills for Making opening and repairing the sides in masonry and plastering the Same & also repairing the floors &c.a			4
		Carried Over			554

Brought forward ——— 534

Coolly hire for taking down and removing the old platform ——— 1

Excavating the foundation raising and levelling the earth ——— 7

Filling river sand 2 feet in depth under the foundation ——— 11

Removing and shifting 2 old Venetian blinds into another position between the columns on the west side Verandah & refacing them with mahogany & plastering the same ——— 11

62-6-6 40 Teakwood posts each wrought & put up ——— 1 13 ft. 13

1 Pair Panelled Venetian door for inner cross wall with frame hooks hinges & bolts &c complete ——— 20

2 Pairs Venetian window shutters for small inner room with frames hooks hinges & iron bars &c complete ——— 36 x 6 Each 7

1 Double canvass screen for the other or west side Verandah with teakwood posts framed and a door in centre with cast iron hinges and nails and wooden knobs with wedges & also with white paint 3 coats with a priming coat of wheat flour &c complete ——— 5

Coolly hire for reducing & repairing 2 old venetian blinds with new teakwood and nails &c ——— 3

2 Teakwood half circular water spouts each 2½ feet long ——— " 12 " Each 2

Removing & Refacing 2 old water trunks & paying tar pitch and

Carried Over ——— 849

Brought forward ——— 849

Cutting & also facing with teakwood blocks & having a space of 3 inches between the wall and trunks ——— 5

1 Brass lock of 8 in. Complete ——— 4

2 Granite Stones of 12 in. square under the water trunks & facing them in masonry ——— " 4 " Each 1

6 Granite Stones of 2 feet long by 8 in. by 1 foot broad & fixing them in masonry for bonding the old and new walls ——— 7

Cutting the wall and fixing the Joists with masonry & plastering the same ——— 10

Paying Tar with 2 coats to the ends of the Joists and sides of the doors and window frames ——— 2

675 Lead colour 3 coats to the Joists doors and windows ——— 2 12 " Sq. 18

375 Do. 2 coats to the old windows ——— 2 " 9 Do. 8

Difference of price in 12.4 Cubic ft. of Teakwood about required to this work between 4 and 2½ Cubic ft. @ 3½ Rs. Charged in the data and the rates of the Market ——— 65

Sundry Charges and Scaffolding &c ——— 31

1000

No. 2

Cash Keepers Room

1 Teakwood common rail with posts top and bottom frames & a Door in Centre with cast iron hinges & bolts &c complete ——— 24

Carried Over ——— 24 1000

	Brought forward			24	1000
1	Teakwood common rail with top & bottom frames to the doorway			4	
1	Pair Teakwood common railed doors & frames with cast iron hinges and bolts & screw nails complete to the doorway			5	
	Lining with teakwood planks of 3/4 ins thick with top & bottom & centre frames & nails to the sides for protecting the cash chest			3	
1	Flat iron cross bar of 5 feet long by 2½ ins by ½ in thick with staples & nails to prevent the door opening			5	
	Cutting the walls & floors & fixing the top & bottom frames & posts with masonry & plastering the same & also repairing the floors &c			3	
250	Wood Oil 3 coats to the rails and posts &c	1	97 Sft	3	
	Difference of price in 13½ Cft of teakwood about required to this work between 4 and 2½ Cft per 3½ Rs Charged in the data and rates of the Market			7	
	Sundry Charges &c			1	
				55	
	No 3				
	Common Shed for the use of the Bullocks Carts and tents &c				
3855	Brick work in Clay with 22/7 sort wall bricks	1	1 Cft	261	
22½	Arch work in Clay	2	"	3	
	Carried Over			264	1055

	Brought forward			264	1055
1013	Roofing with Palmirah rafters reapers nails & covering with pran-tiles only	13	"	1 Sft	142
650	Laying with brick & Jelly in Clay of 3 ins thick and well beaten down with water & streamed over with sand for floor	1	97	Rs "	10
3000	Painting in Chunam		119	Ds "	22
4	Pairs Batten doors with frames hooks hinges & bolts &c complete	10	15 6	Each	44
43	Rft scarfed palmirah breast summers with nails				6
3	Single bolt padlocks of 3 ins	"	8	" Ds "	2
	Excavating the foundation filling river sand 1 foot in depth & levelling the same				7
105	Red paint 3 Coats to the doors	2	6	Sft	3
1850	Paying tar with 2 coats to the rafters & reapers of the roof		14	" Ds "	14
	Difference of price in 23 Cft of teakwood about required to this work between 4 & 2½ Cft per 3½ Rs Charged in the data & rates of the Market				12
	Sundry Charges & Scaffolding &c				9
					545
	Total Company's Rupees One thousand and Six hundred				1600

The Verandah 2 Rooms on the east side of the building is to be raised on a basement of 2¾ feet in height above the foundations which are sunk 6½ feet of which 4½ feet in Masonry and 2 feet in River Sand — The principal walls to be

15½ feet high.

1 Room 36½ × 10½ feet

1 Do 12 × 10½ feet

The Building for Coroners Vault & Lascar Shed is to be raised on a basement of 3½ feet in height above foundation which are to be sunk 3 feet. The Centre walls 14 feet the side walls 8 3/4 feet and the Verandah wall is to be 6 feet.

The Building is to contain 6 Rooms and 1 Verandah.

6 Rooms - each 10 × 8 feet

1 Verandah - 32 3/4 × 4 3/4 feet

Central Office of D.P.W.
Fort Saint George
27th August 1857

M. Walker Colonel
Chief Engineer D.P.W.

No. 3198

From The Chief Engineer

To The Secretary to Government F.W.D.

Sir

I have the honor to forward for submission to Government a Plan and Estimate of certain additions and improvements proposed to be made to the buildings occupied by the Commissioner of Police on the Pantheon Road, amounting to Rupees (1,600) one thousand and six hundred.

The additions consist of a Verandah to be added on the Eastern side of the Office facing wooden Rails to the Road, Bathing room, and Privy adjoining as shewn for buildings, drawn red and sent of the Margin.

2 The additions recommended by the Commissioner are supported by the Barrack Master and the latter appears moderate and sufficient.

3 I beg to recommend the Estimate for entry in the Budget of 1858/59 if not sought sooner for immediate execution.

I have the honor to be,
Sir
Your most Obedient
Most Humble Servant
A. Fuller Colonel
Chief Engineer.

2nd Augst 1857.

Enclosed.

Enclosure in a letter from
The Chief Engineer
To The Secretary to Government
F.W.D.
Dated 24th August 1857.
Received

No. 3198
F.W.D. 57

Report on an Estimate for certain additions & to the Office of the Commissioner of Police on the Pantheon Road for Rupees 1,600.

1/57.8.
In No 1441.

Public Works 1857 Department
Dte Gen 8th Augt 1857

From The Chief Engineer

To The Secretary to Government
D. F. D.

Dated — 27th } August 1857
Received 29th }

No 3196

Enclosed 4 Reds
No 1671. 2 Sept 1857
With an Order
Forwarding for submission to
Government a Plan and Estimate
for certain additions and improvements
to the Buildings occupied by the
Commissioner of Police on the
Pantheon Road for Rs (1600) one
thousand & Six hundred & recommending
its entry in the Budget of 1858/59 if
not thought fitting for immediate execution

No 1671

Ordered
to the Judicial Department
for consideration

Fort St. George
2d Sept 1857

Forwd to the Judl Dept
with the Indx Dispr 3d

No 586