1. Number of Pages.
2. Date of reprint.
3. Initials of Reprinter.

M.R.O. 1—32,400—22-11-38.

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Cur. 19.10.58

G.O. No. 2190 Press —Mis.—

93-94

Dated 19—10— 1858

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 19th October 1858.

No. 93. Read the following Extract from the Minutes of Consultation in the Military Department, dated 5th October 1858, No. 3579.

Communicating to this Department a letter from the Quarter Master General, intimating the approval of the Commander in Chief of the Plan of the proposed Married Quarters to be constructed for the Infantry Barracks at Secundrabad. } (Vide Military Consultation, 5th October 1858, Nos. 175-176.)

No. 94. ORDER THEREON, No. 2190; dated 19th October 1858.

Orders will be issued from this Department on the Project referred to in the letter from the Quarter Master General of the Army communicated with the above Extract, when the Plan forwarded with Extract Minutes Consultation, dated 9th September 1858, No. 1856 shall have received the approval of Government in the Military Department, and an intimation made as to whether the work estimated at Rupees 1,80,300 should be entered in the Budget of 1859-60 or be carried out immediately.

(Signed) T. PYCROFT,
Chief Secretary.

Military Department.

No. 3579

Extract from the Minutes of Consultation
Under date the 5th October 1858

Read the following Letter
Dy. Mr. General's Office
(No. 248
From The Quarter Master General
of the Army -
To The Secretary to Government
Military Department

Sir,

With reference to the Resolution of Government, dated 15th Instt, forwarding for the approval of the Commander-in-Chief a Plan of the proposed married Quarters to be constructed for the Infantry Barracks at Secunderabad, I am desired by His Excellency to say that the Plan is quite unobjectionable, providing the Buildings can be conveniently adapted to the site

site shall may be chosen for them.

Head Quarters
Ootacamund
25th September 1858

Signed F. R. Reid
2d Inv. Genl

Communicated to
Department Public Works
Signed H. Marshall Lt Colo
Dy Secy to Govt

To
The Department Public Works
" " Quarter Mr. General

Comps. RB

Buildings ( ) (New Work)

Abstract of Estimate No of 185 5

District Secunderabad

Work Constructing Ten Ranges of married mens Quarters for a Regement of British Infantry at Secunderabad.

Quantities	Description of Work	Rates			Amount	Amount of each part
Sq Yds		Rs	as	P	Rupees	Rupees
39881	Sq. Bricken Chunam ——— Sq.	...	1	11	1777	
633	Do Arch work to Doors, Windows Ventilators and Closets ——— Do.	.	2	8	166	
181	Do Cornice work in Chunam ——— Do.	.	3	4	38	
39500	Sq. Plastering with one Coat of Chunam Sq.	2	3	.	864	
7799	Do Paving with Granite & Chunam Do.	21	.	.	1638	
11646	Do Roofing with Teakwood Rafters, nails, Flat and pantiles and Chunam bridges ——— Do.	10	12	5	1255	
138	Teakwood Couples with 2 Collar beams and 2 Rafter nails &c Complete ——— E	7	.	.	966	
138	Rafters for Rear Verandah Do.	2	.	.	276	
145	Teakwood Rafters to Front Verandah ——— Do.	3	.	.	435	
219	Rft. of Brass Summers wrought & put up ——— Rft.	.	8	.	109	1291
60	Cuddies for wall to Cattle ——— E	1	.	.	60	
	Constructing 3 Flights of Stone Steps ——— Do.	20	.	.	60	
16	Half Venetianed and half Pannelled Doors with Frames, Hinges bolts, &c. Complete ——— Do.	30	.	.	480	
					Carried over	11064

Quantities	Description of Work	Rate			Amounts	Amount of each part
C Yds.		Rs	As	P	Rupees	Rupees
	Brought over				11064	
	13 Glazed Venetianed and panelled Doors with Frames hinges, bolts, &c. Complete D°	25	"	"	325	
	11 D° D° D° D°	22	"	"	308	
	29 Half Panelled and Glazed windows Complete D°	20	"	"	580	
	29 Glazed Ventilators with Frames, pivots, Rings, &c. Complete D°	10	"	"	290	
	13 Closets with Shelves & Shutters, hinges, bolts &c. Complete D°	20	"	"	260	
	29 Wooden Pegs for Ventilators D°	"	1	"	2	
	13 Accoutrements Pegs with Shelves &c. Complete D°	1	"	"	13	
	Painting and varnishing the Doors, windows, Ventilators, Closets and Shelves & oiling the Rafters &c.	"	"	"	250	
	Constructing 11 Flights of Steps with brick in Chunam D°	8	"	"	42	
8175	Cft. Excavating foundation Cft.	"	"	1	43	
12307	D° Raising floor and Ramming the Same D°	10	"	"	65	13,242
	Cook Rooms, Wash houses Privies for 2 Quarters Under one roof					
2011	Cft. Brickwork in Chunam Cft.	"	1	11	241	
	Carried over				241	13242

10

Quantities	Description of Works	Rate			Amount	Amount of Sackhart
	Brought over				241	13242
16	Cft. Cornice work in Chunam Cft.	"	3	4	3	
22	D° Arch work in D° D°	"	2	8	4	
2775	Sft. Plastering with one Coat of Chunam and whitewashing Sq.	2	3	"	61	
96	D° Terracing with brick on edge, gelly 3 Courses of flat tiles & plastering D°	20	"	"	19	
360	D° Roofing with Teakwood Rafters, mats flat and pantiles & Chunam borders D°	10	12	5	39	
271	D° Paving with Lamunated Stone and Chunam D°	10	"	"	27	
	26 Teakwood Rafters D°	1	"	"	26	
	10 D° Laths D°	"	12	"	8	
	7 Cuddies for wall plates D°	"	12	"	5	
	75 Rafter nails Hundred	2	"	"	1	
	6 Teakwood batten Doors Complete &	12	"	"	72	
12	Sft. of Necessary Seats Sft.	"	8	"	6	
	Constructing fire places with 10 feet Chimney and roofed Ventilators	"	"	"	15	
321	Cft. Excavating foundation Cft.	"	"	1	3	
	Total for 2 Cook rooms, 2 Washhouses, and 2 Privies under one roof				530	
	Total for 5 Sets or 10 Quarters					2650
	Cook Room Washhouse Privy for one Quarter under one roof					
1210	Cft. Brick in Chunam Cft.	"	1	11	119	
12	D° Arch work in Chunam D°	"	2	10	2	
	Carried over				151	15892

Quantities	Description of Works	Rate			Amount	Amount Brought Forward
	Brought over				151	15892
18 Sq.	Cornice work in Chunam	Sq.	"	3	4	
1670	Sq. Plastering with one Coat of Chunam	Sq.	2	3	36	
40	Do. Terracing with Brick on Edge in Jelly three Courses of flat tiles and plastering	Do.	20	"	8	
180	Do. Roofing with Teakwood Rafters nails Fleet and pantiles and Chunam borders	Do.	10	15	19	
126	Do. Paving with Lamunated Stone in Chunam	Do.	10	"	13	
	13 Teakwood Rafters	C	1	"	13	
	5 Joists	Do.	"	12	4	
	1 Cuddeh for wall plates	Do.	"	12	3	
	50 Rafter nails	1100	2		1	
	3 Batten Doors Complete	C	12		36	
6	Sq. Necessary Seats	Sq.	"	8	3	
	Constructing Fire place with Sq. Chimney and Roof Ventilators	"	"	"	15	
	Excavating Foundation	"	"	"	1	
	Total for one Cook Room one wash House and one Privy and one Porch				304	
	Total for 3 Sets of 3 Quarters					921
	Carried over					16813

Quantities	Description of Works	Rate			Amount	Amount Brought Forward
	Brought over					16813
	Compound Walls					
2448	Cft. Brick in Chunam	Cft.	"	1	11 293	
2754	Sft. Plastering with one Coat of Chunam and whitewashing the walls	Sft.	2	3	" 60	
590	Rft. of Open drain with Brick in Chunam around the Quarters	Rft.	"	1	" 1113	6
	Excavating foundation					507
	Sundries					17320 677
	Total for 1 Range Rupees					17997
	Do. for 10 Do. Do.					179970
9	Rft. of Open main Drain with Stone in Chunam between the Quarters	Rft.	"	1	" 330	330
	Grand Total Company's Rs					180300

Central Office of Ch.
Fort Saint George
31st Augt. 1855

Major
Offg. Chief Engineer Ch.

No 4.

Enclosure

In a letter

From

The Offg. Chief Engr.

Dated

To

The Secretary to Govt.

Dated

Lr No 1429 of 1858

Dated 31st August 1858

Received

No 3296

Abstract Estimate for Constructing Ten Ranges of Enamied Brick Quarters for a Regiment of Bengal Infantry at Secunderabad

Amounting to Company's Rupees 180,800 — a — i

2357

P.W. in No 2111 of 1858

Cons: 14th Sept. 1858 Wo 41-42

Public Works 1858 Depart.
Cons 19th Octr Letter
No 2357

Ext. Mins. Coyd in the
Military Depart.

Dated 5th Octr 3 1858
Rec'd 8th do
Ref. to D. 22 Nov. 58 No 2853 inclosing
No 3579 7 Dec

Encs 2 papers

Communicating to the Department a letter from the Quarter Master General intimating the approval of the Commander in Chief of the Plan of the proposed Married Quarters to be constructed for the Infantry Barracks at Secunderabad.

With an Order
No 2190 - 19th October 1858.

No 9894.

No 2190

Orders will be issued on
from this Department on the Project
referred to in the letter from the Quarter
Master General of the army Comm-
-unicated with the above Extract
when the Plan forwarded with the
Extract Minutes Cons: dated 9th Sept.
1858 No 1856 shall have received
the approval of Government in the
Military Department, and an inti-
-mation made as to whether the
work estimated at Rupees 180300.
should be entered in the Budget of
1859/60 or be carried out immediately

Front Wm Gerrard
19th Octr/58
4 Copies by the Mail
With Orgl Plan & Estimate

Dept 20th