

1. Number of pages.
2. Date of receipt.
3. Initials of Reference.

7

M.R.O. 1-82,400-28-11-80.

MADRAS RECORD OFFICE.

Government of Madras.

Public *Work* **DEPARTMENT.**

Cons. dated 7-6-1858

G.O. No.	<i>604</i>	Press Mis.
<i>39-40</i>		
Dated	<i>8-6-</i>	<i>1858</i>

Not to be folded or roughly handled

CM

No. 39. Read the following letter from Colonel C. E. FABER, Chief Engineer ; to H. FORBES, Esq., Acting Secretary to Government, dated 26th February 1858, No. 7681.

SIR,

1 Statement.
1 Letter No. 235, dated 15th February 1858.
1 Comparative Statement.
1 Supplemental estimate.

• Ex. Mins. Cons. No. 577.

I have the honor to forward for submission to Government, a supplemental estimate of Rupees (984) nine hundred and eighty-four, for completing the bridge over the Muldavy stream near Boochireddypolliem in Nellore. The original estimate for this work, framed by Major Boileau, consisting of two arches of 36 feet span, sanctioned on the 24th* September 1855, was deficient in provision for centring, baling and excavating foundation &c., to which circumstance the excess is chiefly owing ; and the sum of Rupees 129 13-5 arises from an increase of rates.

2. The work has been carried on nearly to completion, and only the parapets and plastering remain to be done.

3. The expenditure up to the 31st August 1857, amounted to Rupees (3082-4-7) three thousand, and eighty-two, annas four, and pice seven.

4. I beg to recommend the early sanction of the supplemental estimate, and that permission should be given for completing the work.

Letter from Lieutenant J. MULLINS, District Engineer, Nellore ; to Colonel C. E. FABER, Chief Engineer, dated Kanootala, 15th February 1858, No. 335.

SIR,

With reference to Extract from your Proceedings, No. 2913 of the 14th August 1857, I have the honor to forward a supplemental estimate, amounting to Rupees 984 for the bridge across the Muldavy stream near Boochereddypollem.

2. Of the additional amount thus required it will be seen, by the comparative statement, that Rupees 927-8-6 are due to the omission from the original estimate of any items for centring, bailing and excavating foundations, Superintendence and turn channels, and that Rupees 129-13-5 only are due to extra expense in executing the work above the rates entered in the estimate.

3. The total decrease in the item brick and chunam is due to the omission of the flooring under the arches which Captain Collyer, on his visit to the work in March 1857, considered unnecessary owing to the compactness of the soil. In lieu of the flooring the brick and chunam foundations of the centring have been left, and the intermediate spaces filled with gravel and broken brick well rammed.

4. In my letter No. 1157 of the 26th June 1857, I have fully explained the causes which led to the increase cost of the materials &c.

No. 40. ORDER THEREON, No. 604; dated 8th April 1858.

Under the Provisions of No. 1. of the Rules communicated with Colonel Baker's letter of the 1st August 1856, the Right Honorable the Governor in Council sanctions, for immediate execution, the supplemental estimate, amounting to Rupees (984) nine hundred and eighty-four, submitted with the above letter, for completing the bridge across the Muldavy stream in the Nellore District.

(Signed) H. FORBES,
Acting Secretary to Government.

Public

Chief Engineer.

Chief Engineer.

To the Secretary to Government P. W. D.

Sir,

I have the honor to forward, for submission to Government, a supplemental Estimate of Rupees (984) - nine hundred and eighty four, for completing the Bridge over the Muldary Stream near Boochieddypollum in Tellore. The original estimate for this work, framed by Major Boileau, consisting of two arches of 36 feet span, sanctioned on the 24th September 1855, was deficient in provision for centlings, baling and excavating foundation &c, to which circumstance the excess is chiefly owing, and the sum of Rupees 129-13-5 arises from an increase of rates.

2 The work has been carried on nearly to completion, and only the parapets and plastering remain to be done.

3 The expenditure up to the 31st August 1857 amounts to Rupees (3082-1-7) three thousand and eighty two, & 1/2 annas.

4 I beg to recommend the early sanction of the supplemental Estimate, and that permission should be given for completing the work.

I have the honor to be,

Yours most Obedt. Servt.

W. C. L. Colonel.

Chief Engineer.

Central Office of P. W. D.

Fort Saint George,

26 February 1858.

Yours

