1. Number of pages. 107
2. Date of [illegible] 21.6.57
3. Initials of [illegible]

M.R.O. 1—82 400—23-11-50

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

Fin 8, 20.4.1858.

G.O. No.	25	Press Mis.
112-113 Dated	19-4-	1858.

Not to be folded or roughly handled

Fort Saint George, Public Works Consultation of 20th April 1858.

No. 112. Read the following letter from Major E. LAWFORD, Superintending Engineer Southern Circle in charge of Central office of Public Works; to H. FORBES, Esq., Acting Secretary to Government, dated 1st April 1858, No. 8724.

SIR,

I do myself the honor to submit for sanction, the accompanying estimate amounting to Rupees (376) three hundred and seventy-six, for constructing an outer verandah, and executing sundry repairs to the Dhurmavaram Talook Cutcherry in the District of Bellary. The Collector to whom the estimate was forwarded recommends the work, and as the rates entered therein for labor and materials are reasonable, I beg that the sanction of the Right Honorable the Governor in Council may be accorded for the Execution of the work on Emergency.

1 Estimate
1 Abstract do
1 Copy of letter from Collector of Bellary No. 52, dated 12th March 1858

Letter From C. PELLY, Esq., Collector of Bellary; to Lieutenant J. F. FISHER, District Engineer of Bellary, dated 12th March 1858, No. 52.

SIR,

I have the honor to return with my countersignature the estimate received with your letter of the 6th Instant No. 1774 for executing sundry repairs and constructing an outer verandah to the Dhurmaveram Talook Cutcherry, and to request you will be so good as to take the necessary measures for obtaining sanction and executing the repair.

No. 113. ORDER THEREON, No. 725; dated 19th April 1858.

The Right Honorable the Governor in Council sanctions out of the one lac fund, the Estimate submitted with the above letter, amounting to Rupees (376) three hundred and seventy-six for constructing an outer verandah, and executing sundry repairs to the Dharmaveram Talook Cutcherry in the District of Bellary.

(Signed) H. FORBES,
Acting Secretary to Government.

Bellary, Collectors Office 12th March 58.

No 52.

311

From C. Pelly, Esq
Collector of Bellary
To Lieut. J. F. Fisher
District Engineer of Bellary

Sir,

I have the honor to return with my Countersignature the Estimate received with your letter of the 6th Instant No 1771 for repairing Gurrey Ghauts and constructing an Outer Verandah to the Dharmashalas at Tekkalkotta and to request you will be so good as to state what necessary measures for obtaining Sanction and executing the repairs.

I have the honor to be
Sir
Your most obedient
humble Servant
C. Pelly
Collector

A true Copy
Jno T. Fisher
Dist Engr of Bellary

A true Copy

Superintending Southern Circle
In charge of Central Office of Wks

Ordinary Estimate

Estimate for providing sundry repairs to the Dummanenum Salcak Cutcherry in the District of Ballary Comprising the construction of an outhouse and the Plastering of the record room & Repair to the roof

Locality	Name of Work	Measurements: Length	Breadth	Height	Cubic Contents	Cubical Contents	Particulars	Qnty	Rate	Amount	Total	Remarks
Dummanenum	Outhouse	100	12	"	1200		Roofing with Country Bamboo mats	17 8 "	sq.ft	210 " "		Referred to the Collector C.E.
		1½	1½	2½		202½	12 Pillars Brickwork in Chunam	" 1 6	Cft	18 15 9		
		50	1	6		300	Stone in Chunam for a Wall of the roof	" 1 "	"	18 12 "		
	Roof	19	12	"	228		Common Terracing	5 " "	sq.ft	11 6 4		
		188	1½	3		846	Brickwork for Parapet Walls	" " 9	Cft	39 10 6		
		59	25	"	~~300~~ 1475		Selly in Chunam for Plastering the record room about	3 " "	sq.ft	44 ~~" "~~ 4 "	343 ~~340~~ " 7	†
							Carriage & Superintendence ~~10 per Cent~~				32 " 5 ~~34~~	
							~~Sundries~~				~~1 15 5~~	‡
							Total Estimate Rupees				376 " "	

Lt Amb Munroe
5th March 1858
Supt. P.W.D.

Collector

Asst. Executive Engr.
Dt. Supt. Circle

Lieut. & Executive Engr.

5 21

Buildings ( ) (New Work)

Abstract of Estimate № . of 185 5

District Bellary

Work Constructing an outer Verandah to the Thurmaveram Talook
Cutcherry and Executing sundry repairs to the same.

Quantities	Description of Work.	Rate.			Amount.	Amount of each part.
C. Yds		Rs	as	P.	Rupees.	Rupees.
1200	Sup. Sft. Roofing with franklites Bam. 200 mats Rafters and Chunam Borders &c. ——— Square	17	8	"	210	
202½	12 Pillars Brick in Chunam Cft.	:	1	6	19	
300	Stone in Chunam ——— do	"	1	"	19	
228	Sup. Sft. Common Terracing ——— Sq.	5	"	"	11	
846	Cft. Brick in mud ——— Cft.	"	"	9	40	
1175	Sup. Sft. Plastering with jelly in Chunam ——— Sq.	3	"	"	44	
	Sundries and Superintendence ———	"	"	"	32	
					Total Company's Rupees	376

Central Office of P.W.
Fort Saint George
1st April, 1858.

Superintendent in charge of Central Office
P.W.O.

Quantities.	Description of Work.	Rates			Amount.	Amount of each part.
C. Yds		Rs.	As.	P.	Rupees	Rupees

Enclosure

In a letter

From

The Chief Engineer
D.P.W.

To

The Secretary to Government
D.P.W.

Dated 1 April 1858.
Received

P.W.D. No. 1925/58 No. 8724.

Abstract Estimate for Constructing an outer Verandah to the Dharmavaram Talook Cutcherry and Executing sundry repairs to the Same in the District of Bellary.

Amounting to Company's Rs. 376-0-0

8724 Central Office 9th April 1858.

From The Superintending Engineer
Southern Circle
In charge of Central Office 9th

To The Secretary to Government
Fort St George.

Sir

I do myself the honor to submit for sanction, the accompanying Estimate amounting to Rupees (376) Three hundred and seventy six, for constructing an Outer Verandah, and executing sundry repairs to the Dharmavaram Talook Cutcherry in the District of Bellary. The Collector, to whom the Estimate was forwarded recommends the work, and as the rates entered therein for labor and materials are reasonable, I beg that the sanction of the Right Honorable the Governor in

Estimate & Letter from Collector Bellary dt 22 Mch 58

in Council may be accorded for the
Execution of the Work on Emergency.

I have the honor to be
Sir
Your most Obedient Servant

Signing Southern Circle
in charge of Central Office of P.W.

WB.

To
The Secretary to Government
Fort St. George

Noted

From the Ch. Engr's
8th Dept/58 Ltr. 2433.

Nos. 1128 & 1183

28th April 58. 13th

Rec'd Wks 1858 Despatch
Dy to Com: Genl Depts

No 725

Engr in Chief
The Officer in charge
Cashel Office of Ptr W.
H Majesty's Govt.
Dublin 19th April 58.
Read 1st May

No 3724 Encl 3

Submitting & recommending
for sanction an Estimate
amtg to £376 for constructg
with an arched Culvert
and guarding Fence &c
across the Thurlesbeg
Tabor & Culvert
on the Cashel Extension
of Waterford

No. 725. 19th April 1858
Public Works order

No. 725

The Right Honorable
the Commissioners of Public Works
in Ireland

Gentlemen

I have the honor to submit herewith
a Letter, addressed to me by
Messrs Bolton Brown & Co
Civil Engineers, for transmission
to you, requesting, for reasons
stated therein, that a
sanction may be obtained for the
construction of a Culvert
& fencing in the District of
Ballagh

I am
Gentlemen
Your most obedient
Servant

Thos. Jervis St. George
19th April 58

Thos Jervis St. George Esq
Chief Engr Office