

(1) Number of pages 14

(2) Date of repair 13-10-36

(3) Initials of the Referencer CF

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.
on 30/11/37

G.O. No. <u>229</u>	Press Mis. <u> </u>
<u>187.85</u>	
Dated <u>30-11-37</u>	<u>18.57</u>

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
for the month of November 1859.*

No. 187. Read the following Proceedings of the Madras Government in the Judicial Department, dated 23th November 1859, No. 1605.

Defer passing orders on the plan and estimate for a Sadr court house pending the consideration of the question relative to the amalgamation of the Supreme and Sadr courts. } (Vide Judicial Proceedings from 21st to 30th November 1859, Nos. 45-46.)

No. 188. ORDER THEREON, 30th November 1859, No. 2797.

Ordered to be communicated to the Chief Engineer for information and guidance.

(Signed) L. FORBES,

Dy. Secretary to Government.

Buildings /
Abstract of Estimate No.
[New York]
of 185 . / 5

Abstract of Estimate: No.

(New York)
of 1855.

District. Madras

District. Madras

Work. Erecting a new Court House for the accommodation of the
Sudder & Foujdaree Adalat on the site of the Buildings at Royapettah.

			Amount
			Rs.

Work. Erecting a new					
Mudder & Foujdaree Udalat on the site of the Buildings as per					
Quantities	Description of Work	Rate			Amount for each part
		R ^s	as P.	Rupees	Rupees
6 Yds	<u>No. 1</u>				
	<u>Portecochere</u>				
7990	7990 C ^t Brick work in Chumam ^g g ^t Constructing entablature over the Columns and pillars all round the Portecochere in masonry inclusive of dentel Cornice and Corners cornice and architrave of the Ionic order and also plastering & complete as per Plan		2 3		1124
					250
1493 1/2	1493 1/2 Sup ^t Terracing with brick on edge jelly 3 in. thick 3 Course flat tiles and plastering 3 Coats Chumam ^g g ^t	28	6 7		424
2000	2000 Plastering 2 Coats Chumam ^g g ^t Constructing a pediment over the terrace of the Portecochere in masonry inclusive	1	13 9		37
Carried over					1835

Quantities	Description of Work	Rate	Amount	Amount for each part
C. Nds.		R ^s P ^{as} D ^s	Ruppes	Ruppes
	Brought over		1835	
	of Common Cornice for Counter Balance and building dentel Cornice in front of the same of the Ionic order and plastering &c Complete as per Plan		140	
8	Pedestals with top and base in masonry and plastering &c Complete as per Plan under the pillars and Columns	17 8	140	
2	Pillars with Capitals and base in masonry and plastering inclusive of Volute ornamental works &c Complete as per Plan over the pedestals	50	100	
6	Fluted Ionic order Columns with Capitals and base with Volute and ornamental works and plastering &c Complete as per Plan	131 4	787	
	Carried over		3062	

Quantities	Description of work	Rate	Amount	Amount of each part
		R ^s P ^{as} D ^s	Ruppes	Ruppes
	Brought over		3002	
1	Masonry steps in masonry and 12 in. Sq. blue stones flooring and plastering &c Complete as per Plan for leading to the ground floor		350	
	Filling with river sand 2 feet in depth under the foundation		56	
	Excavating the foundation raising and filling with earth to the basement		16	
512 1/2	Rft. Teakwood wrought and put up	13	929	
	Lining with teakwood planks and nails over the beams between the Joists		14	
2	Teakwood half circular water spouts each 2 1/2 ft. long	10	1	
2	Teakwood water trunks with iron cramps and nails & painting with lead Colour over the same	22 15 6	16	
	Costly here for fixing the above trunks with teakwood blocks against the walls by having			
	Carried over		4412	

Quantity	Description of work	Rate	Amount	Amount of each part
	Brought Over		Rupies 4412	Rupies
	Space of 3 ins. between the walls and trunks	"	"	"
	2 Granite stones of 12 ins. sq. under the water trunks and fixing them in masonry	"	1	"
	16 Perforated tin plates with copper nails to the air holes at the sides of the beams	"	1	"
1800	Suppl ^d Wood Oil 3 Coats to the beams and Joists 16 2/3 sq. ft.	"	19	"
	Difference of price in 7/17 Cts of teakwood between 4 1/2 2/8 Cts per 3 1/2 Rs. charged in the data and the rates of the market	"	329	"
	Sundry Charges & scaffolding	"	231	"
	<u>No. 2</u>			5000
	2 Porticos			
8871	Brick work in Chunar 7 Cts	2 3	1217	
	Constructing entablatures over the Columns all round the Porticos in masonry inclusive of dentel & Cornice & architraves of the Ionic order & also plastering 1/8" complete as per Plan	"	275	
	Brought Over		1522	5000

Quantity	Description of work	Rate	Amount	Amount of each part
	Brought Over		Rupies 1522	Rupies 5000
	8 Fluted Ionic order Columns with Capitals and base inclusive of Volute and ornamental work & plastering as per Plan — 6	131 1/4	1050	
	Constructing 4 pilasters against the walls in masonry with Capitals and base inclusive of Volute & Ornamental work and plastering 1/8" complete as per Plan — 5	11	56	
650	Suppl ^d Terracing with bricks on edge joining 3 ins. thick 3 Course flat tiles and plastering 3 Coats Chunar — 7 1/2	28 6 7/8	182	
700	D Plastering 2 Coats Chunar — 1	13 9	13	
1150	D D with 2 Coats Chunar to the parapet walls — 2	13 9	27	
	Paving 10 ins. sq. glazed tiles for 2 Verandahs —	"	15	
	Erecting 2 Masonry steps & 12 ins. sq. blue stone floor — 1/8" plastering 1/8" complete as per Plan for leading to the Verandah — 6	10	80	
	Brought Over		2975	5000

Quantities	Description of work.	Rate	Amount	Amount of each part
	Brought Over	2975	5000	
	Filling with river sand 2 feet in depth under the foundation	"	17	
232.11	Excavating the foundation 1/2	"	12	
	Ct ^e Teakwood wrought and put up	1 15	122	
700	Suppl ^t Wood Oil 3 Coats 7/34	1 7	7	
	Difference of Price in 3200 of teakwood between 1/2 1/2 Ct ^e of 3 1/2 W ^d charged in the Date and the rates of the Market	"	147	
	Sundry charges & scaffolding	"	182	
			3792	
	No 3			
	3 Small Porticos			
770	Ct ^e Brick work in Chunnam	2 3	108	
	Constructing entablature over the Columns in Masonry and also plastering 1/2 complete as per Plan	"	75	
4	Columns 1/2 Complete as per Plan	27	108	
116	Suppl ^t Terracing with brick on edge jelly 3 ins thick 3 Course flat tiles & plastering 2 Coats Chunnam	28 6 7	33	
	Carried over		324	8792

Quantities	Description of work	Rate	Amount	Amount of each part
	Brought Over		324	8792
231	Suppl ^t Plastering with 2 Coats Chunnam	1 13 9	4	
	Erecting 2 Masonry steps 1/2 Complete as per Plan for leading to the Verandah	45	90	
	Filling with river sand	"	11	
	Excavating the foundation	"	3	
53 1/2	Ct ^e Teakwood wrought & put up	1 13	97	
	Wood Oil 3 Coats to 7	"	2	
	Difference of price in 73 1/2 Ct ^e of teakwood between 1 1/2 1/2 Ct ^e of 3 1/2 W ^d charged in the date & the rates of the Market	"	33	
	Sundry charges & scaffolding	"	27	
			591	
	No 4			
	Ground floor			
211702	Ct ^e Brick work in Chunnam	2 3	27770	
2454	D Circular arch work D	3 6	537	
2835	D Flat arch work D	3	532	
90	D Cordon work in D	2 5 1/2	14	
15	Pillasters 1/2 Complete as per Plan	17 8	262	
6	D D D	12	72	
	Carried over		31187	9353

Quantity	Description of work	Rate	Amount	Amount of each part
		Rs. & P.	Rupies	Rupies
	Brought over		31187	9383
115	1/2 ft Flat arch work in Churnam underneath the entablature over the pillars — 1/2 ft	3	21	
	Constructing entablature over the pillars & flat arch in Masonry & also plastering & Complete as per Plan —		325	
2260 1/2	Sup 1/2 ft Terracing with brick on edge jelly 3 ins thick & plastering 3 coats chunam — 17	8	3956	
10400	D Plastering with 2 Coats chunam inclusive of rustic work — 1/2 sq	2 7/8	257	
37000	D D with 2 Coats chunam — 1	13 9	688	
19400	D Flooring with 10 in sq glazed tiles in Churnam and a levelling course of 3rd sort wall bricks underneath — 13	3 6	2564	
2520	D D with 10 in sq glazed tiles in Churnam — 11	12	296	
	Erecting 2 small masonry steps & Complete as per Plan —		120	
	Erecting a Circular masonry steps & Complete as per Plan —		220	
			30531	9383

Quantity	Description of work	Rate	Amount	Amount of each part
		Rs. & P.	Rupies	Rupies
	Brought over		39534	9383
1	Teakwood double flight stair case 15' and 10' wood top & bottom frames & landing with joists & planks & placing iron rods over the gallery & wood oil & complete as per Plan —		175	
2	Long Teakwood stair case & complete as per Plan —		225	
	Filling with river sand —		1275	
	Excavating the foundation —		650	
3051	1/2 ft Teakwood wrought & put up 1 1/2	13	5531	
	Lining with teakwood planks & nails —		60	
26	Pairs Pannelled Venetian doors with frames hooks hinges & bolts & complete — 1 1/4	4	1073	
22	Pairs Venetian window shutters with frames hooks hinges & bolts & complete — 33	2	729	
2	Pairs Railed doors with posts and thick frames hooks hinges & bolts & complete for securing the passages — 35		70	
4	Pairs — — — — — 55		110	
	Carried over		49762	9383

Quantities	Description of works	Rate		Amount		Amount of each part
		No	At	Rupies	Rupies	
	Brought over			49762	9383	
10	Iron locks of 10 ins complete	"	"	30		
6	Iron double bolt padlocks	"	"	4		
156	Perforated tin plates with copper nails to the air holes at the sides of the beams	"	"	39		
14500	supply Wood Oil 3 Coats	1	"	9	152	
7000	Green Paint 3 Coats	11	12		333	
	Difference of price in 1800 of teakwood between 2 1/2 cft & 3 1/2 R ^{ch} charmed in the dist at the rates of the market				2200	
	Sundry charges & scaffolding				2666	
						55186
	<u>No. 5</u>					
	<u>Upper floor</u>					
62023	C ^{ft} Brick work in Chaman	2	6		9691	
3722	D Flat arch work in D		3		698	
360	D Circular arch work in D		5	6	79	
197	D Cornice work in D		3	6	63	
503	R ^{ft} Dental Cornice & mouldings	1	"		500	
	Constructing entablature over the Columns in the stair case room 1/2" complete as per Plan				30	
	Brought over			11041	64569	

Quantities	Description of work	Rate		Amount		Amount of each part
		No	At	Rupies	Rupies	
	Brought over			11041	64569	
	2 Columns 1/2" complete as per Plan	15	12		32	
2031 1/4	supply Terracing with brick on edge jelly 3 ins thick					
	2 Course flat tiles & plastering					
	3 Coats chunam to the ceiling & over the terrace	27	8		5587	
69000	Plastering with 2 Coats chunam	1	13	9	1283	
20500	Flooring with 10 ins sq ^{ft} glazed tiles in Chaman	11	12		2409	
4070	Covering with flat & painted chunam borders over the truss roof	8			326	
	Cornice work in chunam of the pediment shape over the 49 flat & 2 false arches & 2 windows & 2 false windows				137	
5100	R ^{ft} Moulding works 1/2" & 1" R ^{ft}	2			638	
3235 3/4	C ^{ft} Teakwood wrought and put up	1	13		5865	
12	Flat iron triangular truss with screw & nuts of 2 feet long each for junction of principal rafters and king posts	2			24	
	Brought over			27342	64569	

Quantities	Description of work	Rate	Amount	Amount of each part
		No 27 8	Refers	Refers
	Brought Over		27342	64569
21	Flat Iron hoop strips with screw & nuts for junction of principal rafters & tie beams—E	3	"	72
6	" " " for tie beams & king posts—G	3	8	21
	lining with teakwood planks and nails over the beams between the joists—	"	"	100
4	Double Canvas screen with top & bottom frames & uprights & also lead colour 3 coats over the same—G	75	"	300
	Iron rails screws between the flat arch to the exterior of the buildings as per Plan complete—	"	"	775
54	Pairs Pannelled Venetian doors with frames hooks hinges & bolts & complete—E	41	4	2228
46	Pairs Venetian window shutters with frames hooks hinges & bolts & complete—E	33	2	1524
	Brought Over		32362	64569

Quantities	Description of work	Rate	Amount	Amount of each part
	Brought Over		32362	64569
18	Swinging attic pannelled shutters with frames & iron axletrees & latch with cotton ropes & complete—E	13	7	262
54	Pairs Glazed doors with iron folding hinges and bolts & complete—G	26	7	1428
46	Pairs Glazed window shutters with iron folding hinges & bolts & complete—G	19	2	380
30	Brass locks of 10 in complete	3	8	105
	lining clungry cloth with gilded iron nails including teakwood frames & screw nails & also milk white paint 3 coats over the same under the ceiling of the trap roof—	"	"	300
116	Perforated tin plates with Copper nails to the air holes at the sides of the beams—	"	"	29
50	Teakwood half circular water spouts each 2 1/2 feet long—G	"	10	31
	Brought Over		35377	64569

Quantities	Description of work	Rate	Amount	Amount of each part
		Rs. & P.	Rupies	Rupies
	Brought Over		35377	64569
6	Teakwood water trunks with iron Cramps & nails and painting over with lead Colour $\frac{1}{2}$ completed	3 13 3	23	
14	D D D	22 15 6	1010	
	Coaly lime for fixing the above trunks with teakwood blocks against the walls by leaving a space of 3 ins between the wall & trunks	" "	100	
50	Granite stones of 12 ins sqr under the water trunks & fixing them in masonry	" "	15	
31000	Suppl ^t Wood Oil 3 Coats Sqrs	1 " 9	324	
11000	D Green paint 3 Coats—D	4 12 "	522	
	Applying Varnish to the doors windows of the interior & glazed shutter—	" "	175	
	Difference of price in 6800 cft of teakwood between $18\frac{1}{2}\%$ cft & $3\frac{1}{2}\%$ R ^t charged in the data & the rates of the market—	" "	3117	
	Sundry charges & scaffolding &c	" "	2032	
				42695
	Carried Over			107264

Quantities	Description of work	Rate	Amount	Amount of each part
		Rs. & P.	Rupies	Rupies
	Brought Over			107264
	No 6			
	2 Sky lights—			
5 1/2	cft Brick work in Churnam sqr	2 9 "	9	
86 1/2	Suppl ^t Semiteraced roof with teakwood reapers & nails 2 Course flat tiles 1/2 ins thick jelly and plastering 2 Coats Churnam over the same— $\frac{1}{2}$ sqr	14 "	121	
150	D Plastering with 2 Coats Churnam—D	1 13 9	3	
8	Teakwood posts with Caps and iron hoops $\frac{1}{2}$ completed	1 6 "	11	
62	cft Teakwood wrought and put up— $\frac{1}{2}$ cft	1 13 "	113	
	Lining with teakwood planks and nails to the eaves of the roof—	" "	3	
	Lining with planks and nails to the sides of the well of the Sky lights—	" "	8	
	Lining with planks and nails over the breastwork for closing the gables—	" "	4	
	Carried Over		272	107264

Quantities	Description of work	Rate		Amount of each part	
		R	A	Rupies	Rupies
	Brought Over			272	107264
	Fixed glazed screen with top and bottom frames uprights and screw nails 1/2" Complete as per Plan over the wall of the sky light			217	
	Strengthening the glazed Screens with 12 iron straps and fixing them in the uprights and beams with screw nails			15	
1500	Sup ^d Wood Oil 3 Cwt to the brassminiers and couples 1/2" 2 1/2	1	9	16	
	Applying Varnish to the glazed shutters 1/2"			10	
	Difference of price in 85 Cwt of teakwood between 1882/8 Cwt per 3 1/2 Rupies charg- ed in the data and the rates of the market			39	
	Sundry charges and scaffolding 1/2"			27	
					596
	Brought Over				107860

Quantities	Description of work	Rate		Amount of each part	
		R	A	Rupies	Rupies
	Brought Over				107860
	Cooly hire for taking down and removing the terrace beams, joists, doors, and windows wall floors and foundations 1/2" of the present building and also collecting the old materials of the same				2460
	Total Rupies				110300

Central Office of P. W.
Fort St. George.
22 November 1889

J. M. L. Smith Colonel
Chief Engineer. P. W.

Enclosure

In a letter

From

The Chief Engineer
D. P. W.

To

The Secretary to
Government,
D. P. W.

0003106/54.

Dated 22nd Nov 1859.
Received.

No 7524

Incl. 19th
In 1929.

Abstract Revised Estimate
of Erecting a new Court-house
for the accommodation of the
Sudder and Foujdaree Adalat
on the site of the Buildings at
Nawapetlah lately vacated by
that Court at Madras
Amounting to Rs 110,300.

JUDICIAL DEPARTMENT.

PROCEEDINGS of the MADRAS GOVERNMENT.

Read the following letter from Lieutenant Colonel J. H. BELL, Chief Engineer; to the Secretary to Government, Public Works Department, Fort Saint George, dated 22nd November 1859, No. 7524.

No. 90, dated 11th January 1859.

With reference to the Orders marginally quoted, I have the honor to forward the plan for a new Court House for the Sudder Adalat, with a revised Estimate thereof, amounting to Rupees 1,10,300.

2. The plan having already received the approval of the Judges, I need not refer it to them again and would only state my opinion that the arrangements appear perfectly suitable and convenient, that the architectural character of the building is appropriate, and that the dimensions of the foundations and superstructure as well as of the various rooms are correct.

3. The rates on which the present Estimate is framed are those which prevail at present and therefore there is every reason to believe that the work will be completed within the specified amount, the period allowed by the Civil Architect for its construction being two years.

4. The site of the proposed sanction is the same as that now occupied by the dilapidated Court House, for the removal of which adequate provision has been made.

5. If approved by Government, I would request permission to enter the Estimate in the Budget List No. 1.

Transferred to the Judicial Department.

(Signed) J. D. BOURDILLON,
Secretary to Government.

22nd November 1859.

ORDER THEREON, 25th November 1859, No. 1605.

The Government will defer passing Orders upon the Plan and Estimate for a Sudder Court House, submitted with the above letter, pending the consideration of the question relative to the amalgamation of the Supreme and Sudder Courts.

(True Extract.)

Chief Secretary.

To the Department Public Works, with a Plan and Estimate.

Ed. F. Cardledge.

P.H.C. 11th Jan'y 1858.

Dec 12213

Public Notice 1858

to visit the 3rd of January

No 3106.

Proceedings of the
Lancaster District in the
National Asylum

At Test 25th Jan'y 1858

Wm. J. Rogers

E-2. Return Dec 19:12:57

1858/4/188

order on the 11th of
October for a check
out of the funds
the committee relative
to the management
of the Asylum and
the costs.

Nov 27-30:2 November

William Crook &

1858/9/7

Address to the com

reference to the Asylum
Engineers for information

and guidance.

For George
30 January

Wm

to copy the the 11th of Jan'y
with Jan'y 27 & 28. 1858

Wm