M.R.O. 1—77,006—8-6-37.

(1) Number of pages 6

(2) Date of repair 15-5-58

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Judicial DEPARTMENT.

G.O. No. 1505 Press ~~Misc.~~

1554-156

Dated 8 — 8 — 1861.

**Not to be folded or roughly handled**

## *Proceedings of the Madras Government, Public Works Department, 8th August* 1861.

No. 155. Read the following Proceedings of the Madras Government in the Military Department, dated 31st July 1861, No. 2,716 :—

Approving the estimate for dismantling, re-building and enlarging the Gram Godown at the Remount Depôt near Oossoor, in the District of Salem. } (Vide Military Proceedings, 31st July 1861, Nos. 626-627.)

---

No. 156. ORDER THEREON, 8th August 1861, No. 1,505.

Ordered to be communicated to the Chief Engineer for information and guidance, with reference to his letter, dated 26th July 1861, No. 3,170.

(Signed) J. D. SIM,
*Secretary to Government.*

Southern Circle P.W.

Salem District.

Abstract Estimate of rebuilding and enlarging Syrau Godown at the Renaunt Depôt near Cattoor

| [illegible] | Description of work | Rate | Amount | Total |
|---|---|---|---|---|
| [illegible] | Cubic Yards of roughstone in said at | 1 2 | 92 8 | 81 10 8 |
| [illegible] | Cubic Yards of brick in Chunam | 3 12 | 1045 8 12 | |
| [illegible] | Do of brick in Chunam | 12 | 72 9 4 | 954 4 |
| [illegible] | Square of flooring with Jungle wood Couples and Rafters, flat and Pantiles, and Chunam borders at | 21 | 625 12 9 | |
| [illegible] | Do of flooring with brick jelly in Chunam at | 5 5 | 27 5 | 36 4 6 |
| [illegible] | Do of blue washing in and Outside | 6 | 27 8 | |
| [illegible] | Do of blue washing in and Outside complete | 26 4 | 52 8 | |
| [illegible] | Battened Doors with hinges &c Complete | 5 4 | 3 12 | |
| [illegible] | Windows glazed 2 + 2 | | | |
| [illegible] | Pulling down the old building | | 150 | |
| [illegible] | Sundries and Extra Establishment at 5 per cent | | 103 4 11 | 102 6 9 |
| | Total Rupees | | | 2350 2210 |
| | Deduct Value of old Materials | | | 350 |
| | Balance Company's Rupees | | | 2000 1860 |

[illegible] Engineers office
the 21st May 1861.

J. Elphinstone Capt.
District Engineer

Passed
Collector

Distributed to the
Acts and Agents

MILITARY DEPARTMENT.

*PROCEEDINGS OF THE MADRAS GOVERNMENT.*

Read the following letter:—

*From the Chief Engineer Department Public Works, Chepauk, 26th July* 1861, *No.* 3170; *to the Secretary to Government, Public Works Department, Fort Saint George.*

With reference to the Proceedings of Government, No. 528, dated 13th March last, I have the honor to forward, for submission to Government, a Plan, Specification and Estimate, amounting, after correction in this Office, to Rupees 2,000, which provides for dismantling, re-building, and enlarging the Gram Godown at the Remount Depôt near Oossoor, in the District of Salem.

*Enclosures* 5.

1 *Plan* 1/3224/61.
1 *Abstract Estimate* 3/1404/61.
1 *Report* 2/3224/61.
2 *Demi-Official letters from the Acting Remount Agent, dated 17th and 24th June* 1861.

2. The foundations of the old building, which are of Brick and Chunam, will be made available, as far as possible, in the re-construction of the new Godown.

3. The proposed building will consist of two rooms, each measuring 59¼ × 12 feet, capable of containing 225 tons of Gram, with a porch at each end for the convenience of persons employed in the daily issue of this article.

4. The Estimate,* which has been examined and corrected in this Office, Captain Gahagan states, provides for all the necessary work and that a Supplemental Estimate will not be required. The Agent for Remounts has also countersigned it and the Plan in token of approval. I request, therefore, that Government will be pleased to accord early sanction to the Estimate, the amount, Rupees 2,000 to be defrayed from the Reserve Fund in the Budget for 1861/62.

*Rupees* 2,000.

---

ORDER, No. 2716, 31*st July* 1861.

Approved for execution as proposed.

(True Extract.)

*Deputy Secretary to Government.*

To the Department Public Works, with 5 enclosures.
" Quarter Master General.

Exd. T. Stubbs.

1720 Space Copies

Pro. 15th March/61 N° 245-246

P. W. 1861 Q. Mast. Genl.
Pro: of Lov. for August
N°. 1793.

Proceedings of the Board
of Officers in the Military
Survey Q. Mast. Genl.

Dated 31st July
Received 5th Aug. 1861.
N°. 2716.

E-5.
15.5.
1497

Approving the estimate for
dismantling, Rebuilding and
enlarging the Grain Godown
at the Remount Depot
near Aligarh in the
District of Selem.

With an Order
N°. 1505. 8th Aug.

N°. 1505.

Ordered to be communicated to the
Chief Engineer for information & guidance in
reference to his letter dated 26th July 1861 & 31st.

Q. Mast. Genl.

Chief Engineer
Agra

8th Aug. 1861

Chief Engineer Agra
N°. 2716 Q. M. Genl. 5/11/61
Chief Engineers

N°. 1554-1556.