1266

M.R.O. 1—77,006—8-8-37.

(1) Number of pages 10

(2) Date of repair 27-8-42

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	1266	Press Mis.
100-101.		
Dated	5-6-	1862.

Not to be folded or roughly handled

12
27-8-42

Proceedings of the Madras Government, Public Works Department, 5th June 1862.

No. 100. Read the following Proceedings of the Madras Government in the Military Department, dated 26th May 1862, No. 1,899 :—

Approving of the estimate for carrying out certain alterations to the building recently occupied by the Treasury Officers in the Fort, and stating that there is no objection to the removal of the "strong room" if His Excellency the Commander-in-Chief consents to the arrangement. } (Vide Military Proceedings, 26th May 1862, Nos. 520-521.)

No. 101. ORDER THEREON, 5th June 1862, No. 1,266.

1. Communicated to the Acting Deputy Chief Engineer, Central Circle, whose particular attention is called to paragraph 2 of the Order in the Military Department.

2. The work will be executed from the General Funds of the Presidency District for the current year.

(Signed) W. H. HORSLEY, Lieut.-Colonel,
Secretary to Government.

Abstract Estimate No 4 22

District Presidency

Work Alterations required to be executed at the late General Treasury for the purpose of Converting it into a Sergeant Mess House Regimental work Shops Quarter Masters Stores Reading Recreation and Coffee rooms and School Masters Quarters

Quantity	Description of works	Rate	Amount	Amount of each part
	Pantry and Kitchen Range			
2	Cooly hire for removing 2 windows and Masonry sills for converting the openings into Door ways and fixing 1 New and 1 old doors and with Masonry and plastering the sides with 2 Coats Chunam also flooring with 2 Line dressed granite Stones to the sprees of the door ways	6	12	
	Cooly hire for removing 2 Door frame with iron bars and Conveying to the yard for filling up the same		1	
111⅛	Qtt. Bricke work in Chunam	0	2 5 16	12 7
13	Do. Arch work in Chunam to the bed of the Cistern	0	3 10½	3 2 4
200	Plastering with 2 Coats Chunam to the walls inside	2	0 2	4 0 4
50	Do. with 2 Coats yellow Chunam to Do. outside	2	3 1	1 16
9	Laying bricks Jelley in Chunam of 3 brick and plastering over the same	3	6 7	0 6 2
	Constructing 1 Duffs Cooking range with five bricks in clay and iron articles &c. Complete as per plan			4 2 0
	Constructing a Masonry fire place with arch surrounded with an iron Chimney as per Plan for the use of the Coffee rooms			15
	1 Iron Chimney of 36 feet height by 6 Diameter with Shifting Cowle secured to the wall with Circular headed Staples	3		108
	Cooly hire for removing the terrace and fixing 4 earthen S Venti: lators with Jelley in Chunam and plastering	1		4
15	Rft. Cooly hire for removing the old granite floor and levelling Course excavating earth 3 feet deep to fixing the earthen pipes with asphalte filling the earth and recovering the granite Stones in Chunam with levelling Course from the Cistern of the Kitchen range to the out side Main Cesspool for discharging the water			7 8
132	Cooly hire for removing the old granite floor and levelling Course and forming a slope in the Cooking range	1 4	1	10 5
91	Flooring with the old granite Stone in Chunam with old levelling Course and forming a Spule in Do.	6		5 7 4
	Carried Over			599 15 8

Brought forward					599 15 8
4 Earthern S. Ventilators	2	8	10		
Rft. Earthern pipes of 4½ Diameter		4	3	12	
1 Granite of 2 line dressed for Covering over the Cesspool with holes			9		
1 Pair of Batten door Shutter with frames hooks hinges and bolts &c.			40		
Keg green paint 3 Coats to the Doors			2	7	
					665 3 7

Quarter Masters Office and Store

Cooly hire for Cutting the Crosswall for turning the arch being hand work		1	16	4	
Circular arch work in Chunam		3	10½	16	5 7
Plastering with 2 Coats Chunam to the arch and sides &c.	2	8	11	3	13 4
Flooring with 2 line dressed granite Stones in Chunam to the Space formed by the arch way	29	9	4	7	6 4
					43 13 3

Regimental work shop

Cooly hire for Cutting the wall and opening 2 doorways and fixing the doors and lintels with masonry and plastering the Side ales flooring with 2 line deep granite Stone in chunam to the Space	6			12	
Cooly hire for Cutting the wall and opening 5 Cwindow ways and fixing new windows and lintels with masonry and plastering Complete	3	8		21	
Cooly hire for removing a portion of the terrace and Ceiling planks fixing 7 Earthern S. Ventilators with brick Selley in chunam and plastering	1			7	
7 Erthern S. Ventilators	2	8		17	8
8 Teakwood lintels wrought and put up	2	10		79	12
2 Pair Batten door Shutters with frames iron hooks hinges and bolts &c. 8 × 4 feet	31	10		63	4
6 Pairs Batten window Shutters with frames iron hooks hinges and bolts &c.	24			192	
Keg green paint 3 Coats to the doors and windows &c.	2	7	6	16	9
					360 8 7
Carried Over					1069 9 7

Brought forward					1069 9 7

Quarter Master Sergeant or School Masters Quarter and Bath room

Cooly hire for Cutting the wall and forming 2 doorways and fixing 2 new doors and Lintels with Masonry and plastering the reveals and also flooring with 12 inch dg°. bricks in Chunam to the Spaces formed by the doorways					4 8 9
Constructing a Masonry Step including bed fearing 2 line dressed granite Stones treads in Chunam and plastering Complete as per plain in front of the Verandah				14	
2 Teakwood Lintels each in wrought and put up	3	10		22	6 10
2 Pairs Batten door Shutters with frames iron hooks hinges and bolts &c.	31	10		63	4
Keg green paint 3 Coats to the doors and lintels	2	7	6	3	11 3
Rft. Cooly hire for Constructing a dwarf wall with Masonry and plastering		2		1	10
Laying brick Selley in Chunam of 3 inches thick forming a Slope well rubbed over	3	5	7	5	13 9
					119 13 10

Drain

Cft. Brick work in Chunam				2 5	7 4 5
Plastering with 2 Coats Chunam				2	2 9 8
2 Rabbited granite Stone each 4 × 12 × 5				2	4
2 Do. Do. 2 × 12 × 5				1	2
1 Iron Stench Trap					6 9 6
Cooly hire for removing the granite floor and levelling Course excavating earth 3 feet deep and fixing the earthern pipes refilling the earth resetting the above granite Stones in Chunam with old levelling Course in the gate way					10
1380 @ 51. 3. lay. Excavating earth for laying the earthern pipes and filling the same well tamped with water					2 6 6 3
37 Rft. Earthern pipes of 4½ Diameter				4	9 4
193 Do. Do. of 8" Do.				4	6 17 6
Cooly hire for fixing and Pointing the pipes					14 6
					187 13 10

Passage

Carried Over					1377 5 3

	Brought forward					1377 5 3
	Passages					185½
396	Cft. Brick work in Chunam		0	25 59	13 0	
550	Plastering 2 Coats Chunam to the Screen walls		2	2 11	0 11	
	Coolly hire for Cutting the walls and forming the door ways and fixing 2 Doors with Masonry and plastering the reveals &c. with 2 Coats Chunam also paving 2 Line dressed granite Stones in Chunam to the Space of the door ways		6	12	0	
	Coolly hire for Constructing 2 Masonery Steps including beds and paving 2 Line dressed granite Stones in Chunam and plastering as per Plan in front of the door ways		17	8 35	0 5	
	2 Pair Batten door Shutters with frames iron hooks hinges bolts &c.		33	9½ 67	3 35	
175	Keg green paint 3 Coats to the Doors		2	7 6 4	51	
						189 6 3
	Treasury Room and Court yard					
	Coolly hire for Cutting the wall forming the 7 door ways fixing the doors and lintels with Masonry and plastering the Sides also paving with 1st. bricks in Chunam to the Spaces of the door ways		6	42	0	
	Coolly hire for Removing a portion of the terrace and fixing 8 Earthern Ventelators with bricks Jelly in Chunam and 8 Cast Iron Ventelators plastering		1	8	0	
			2	8	20	
	7 Sealwood lintels each wrought and put up		3	10	69 126	
	7 Pairs Batten door Shutters with frames iron hooks hinges and bolts &c.		31	10	221 6	319 2 0
4677½	Coolly hire for removing the old Laterite Stone floor with levelling Course and Collecting the Materials for reuse		1	46	126	350
2377½	Flooring with old Laterite Stone in Chunam with old levelling Course underneath and forming a Slope on both sides for discharging the rain water as per Plan		6	14	210 5	
2300	Flooring with new Laterite Stone in Chunam and levelling course of 3d sort wall bricks underneath and forming a Slope		17	9	403 15	
					Carried over	934 8 4 1566 11 6

	Brought forward					934 8 4
600	Keg green paint 3 Coats to the doors and lintels		2	7 6	14 13 0	
	Compound wall					
955½	Brick work in Chunam		0	25	144 5 1	
975	Plastering with 2 Coats Chunam to the walls		2	2	19 9 7	
195	Setting broken bottles in Chunam over the Coping		0	1 2½	14 7 7	
	Coolly hire for cutting the wall and fixing railing gate with Masonry and plastering Complete				2 0	
	1 Sealwood railing gate with posts new hooks hinges and Cross bar round bolts and Complete				22 8	
100	Read paint 3 Coats to Do				2 6	
	1 Granite Stone including fixing for the gateway				2 8	
	Removing the rubbish Sundry Charges and Scaffolding &c.					20
	Total Rupees Two thousand Eight hundred and Seventy five					2875

Fort Saint George
30th April 1862

Lieut
Asst. Dist. Engineer

Lieut Col
District Engineer Presidency

Approved and note to Superintendent
Barrack Master

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter :—

From the Acting Deputy Chief Engineer Central Circle, Chepauk, 14th May 1862, *No.* 577; *to the Secretary to Government, Public Works Department.*

I have the honor to submit herewith, for the consideration of Government, an Estimate amounting to *Rupees* 2,670, for carrying out certain alterations to the Building recently occupied by the Treasury Officers in the Fort, to adapt it for various very useful purposes for the recreation and comfort of the Regiment quartered in the European Barracks.

Enclosures 6.

1 *Letter from the District Engineer Presidency, No.* 38, *dated 3rd May* 1862, *with* 3 *enclosures.*
1 *Plan.*
1 *Estimate.*
1 *Specification.*

2. The accompanying Plan and Memorandum by the Barrack Master, fully explain all the arrangements which it is proposed to carry out, and which have received the approval of His Excellency the Commander-in-Chief, on whose personal requisition the project has been undertaken.

3. I beg leave, with reference to Colonel Hitchins' letter enclosed, (paragraphs 4 and 5) strongly to recommend the additional work which that Officer judiciously proposes to execute, *viz*, the removal of the solid Building which occupies the centre of the best room in the block, and which was formerly used as a "strong room" for Treasure arriving from the Provinces. I do not think the remote contingency suggested by the Barrack Master of its being hereafter required for storing public property is of sufficient value to be weighed against the great detriment which must arise from it, if left as it now stands, and I therefore recommend that Government should sanction its demolition and removal, for the expense of which no addition will be required to the Estimate, for the saving which will be effected in the item of ventilators, &c., will more than cover it.

Referred to the Military Department, for consideration.

(Signed) W. H. HORSLEY, Lieut.-Colonel,
Secretary to Government, P. W. D.

16th May 1862.

ORDER, No. 1899, *26th May* 1862.

1. Approved.

2. The Governor in Council sees no objection to the removal of the "*strong room*" as recommended in paragraph 3 of Colonel Ouchterlony's letter, provided His Excellency the Commander-in-Chief consents to the proposed arrangement.

(True Extract.)

Deputy Secretary to Government.

To the Public Works Department, with six enclosures. two spare Copies
„ Quarter Master General.
„ Barrack Master.
„ Brigade Major Fort Saint George.

Exd. T. Stubbs.

No. 1862 Despatch
from Govt. for sund
No. 1621

Pro: of the M. Govt
and the Military
Department
Dated 26th } May 1862
Rec'd 28th }

No. 1899.

6 Encls.
4 — returned to the Ag. Chief Engr. CC.

Approving of the estimate
for carrying into effect
alterations to the Building
recently occupied by the
Treasury officers in the
Fort, and stating that there
is no objection to the Accom-
modation of the Attorney General
in His Excellency the Com-
mander-in-Chief's Govt
Secretariat in the arrangements
with an Order.

No. 99 - 100
No. 100 - 101

No. 1266

Communicated to the Acting Deputy
Chief Engineer Central Circle whose
particular attention is called to
para 2 of the Order in the Military
Department.

The work will be executed
from the General Funds of the
Presidency District for the Current
year.

13 Copies

for the Actg. Dy. Chief Engr.
C.C. with 4 Encls.
& Copies of the letter & Order
Accountant General
Chief Secretary
5 June 1862