M.R.O. 1—77,606—8-6-37.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Library DEPARTMENT.

G.O. No.	1322-	Press / Mis.
S. 12-2-13		
Dated	11-6-	18 62-

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 11th June 1862.

No. 212. Read the following letter from Lieutenant-Colonel W. H. HORSLEY, Chief Engineer, to the Secretary to Government, Public Works Department, dated Chepauk, 3rd June 1862, No. 1,293:—

SIR,

1. I have the honor to submit for the orders of Government the accompanying estimate of Rupees 469, for fitting up a portion of the Store room at Chepauk as a Workshop for the use of Mr. Doderet, Mathematical Instrument maker.

2. Mr. Doderet's services will shortly be replaced at my disposal by the Government Astronomer, and as it is very desirable that he should be employed as soon as possible after rejoining the Central Office in repairing the damaged Instruments now lying in the Stores, I recommend that the above estimate may be at once sanctioned for execution from the General Funds of the Presidency District for the current year.

No. 213. ORDER THEREON, 11th June 1862, No. 1,322.

The estimate for Rupees 460 submitted with this letter is sanctioned for execution from the General Funds of the Presidency District for the current year.

(Signed) W. H. HORSLEY, Lieut.-Colonel,
Secretary to Government.

Carried Over 339

BUILDINGS

New Works.

ABSTRACT of Estimate No. of 186 -6

DISTRICT Presidency

WORK Making Certain additions to a portion of the Store Room at Chepauk ordered to be Set a part for use of the Mathematical Instruments Maker as a Work Shop.

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
675	Qrs. Brick wall in Clay 1½ Bk.	"	1	11⅛	81	
30	Do. Arch wall in Chunam 1½ Bk.	"	3	10½	7	
1000	Sup. ft. Plastering with 2 Coats Chunam to the Old & New walls 1½ Sq.	2	"	2	20	
720	Do. Flooring with 6 inches Sq. Bricks in Chunam & a Levelling Course of wall bricks under-neath ——— Do.	7	2	8	55	
133	Qft. Removing the Old wall 1½ Bk.	"	1	"	8	
2-11-	Qft. Seakwood Sunk 1½ Bk.	3	10	"	11	
2	Pairs Glazed Window Shutters with Iron hinges &c. Complete	6	7	"	14	
1	Glass Window with Circular Top including frame & Batten Shutters &c. Complete	"	"	"	62	
1	Pair Batten door with frame hinges & hooks &c. Complete	"	"	"	22	
1	Do. ——— Do. ———	"	"	"	18	
1	Smiths bench	"	"	"	24	
1	Do. ——— Do. ———	"	"	"	15	
	Carried Over				337	

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount of each part. Rupees.
	Brought Over				337	
	1 Smiths bench	"	"	"	17	
	1 Common Teakwood al= = mirah with Shelves & two Drawers Complete	"	"	"	45	
	Enlarging two pairs of window Shutters & framing Each pair into One	"	"	"	3	
	2 Padlocks & keys Complete	1	"	"	2	
	Setting up Smiths Forge	"	"	"	11	
	Panding	"	"	"	13	
	Excavating foundation &, Sundries &c	"	"	"		
	Total Rupees				460	

Central Office of P.W.
Chennai
3rd June 1862.

Lt. J. Pownall Asst. Colonel
Chief Engineer D.P.W.

Public Works Department

No 1293

From,
Lieutenant Colonel W. H. Horsley
Chief Engineer D. P. W.

To,
The Secretary to Government
Public Works Department

Sir,

I have the honor to submit for the orders of Government the accompanying Estimate of Rupees 460 for fitting up a portion of the Store room at Colaba as a Work Shop for the use of Mr. Podere, Mathematical Instrument Maker.

2 Mr. Podere's services will shortly be replaced at my disposal by the Government Astronomer, and as it is very desirable that he should be employed as soon as possible after rejoining the Central Office in repairing the damaged Instruments now lying in the Stores, I recommend that the above estimate may be at once sanctioned for execution from the General funds of the Presidency District for the current year.

I have the honor to be
Sir
Your Most Obedient Servt

Central Office of D. P. W.
Colaba 3d June 1862

Edw. Bonella Lieut. Col.
Chief Engineer D. P. W.

X. J. R. F.

No 1293
Dated 3d June 1862
Received 5th June 1862

Abstract Estimate
For Fitting Establishment
-ations to a portion of the
Stone Room at Colaba
ordered to be set apart for
use of the Mathematical Ins
-truments Maker now
Work in the District of
Presidency Division

Circular
Dated 1862
From
The Chief Engineer
D. P. W.
To
The Secretary to Govt.
D. P. W.

No. 962 Dep.t of Gov.t Fort. June/62
Prov: Dn
From No. 1709
Lieut.t Col.o W.m H. Horsley
Chief Engr. D & M.

To, The Secretary to Government
Public Works Dep.t

Dated 3d
Rec.d 4th June 1862.

Encl. No. 1293

Submitting for sanction Estimate of Rupees 460 for fitting up a portion of the Store room at Chepauk as a Workshop for Mr. Doderet the Mathematical Instrument Maker.

No. 212. 213

W.H. an order No. 1322-11 June.

Correct

No. 1322

The Estimate for Rs. 460 - submitted with this letter is sanctioned for execution from the General funds of the Presidency District for the current year.

Fort St. George
The 11th June 1862.

To The Agent Chief Engineer Dist.t 12th
3. Accountant General
7. Chief Engr.

1282