M.R.O. 1—77,006—8-6-37.

(1) Number of pages 8

(2) Date of repair 3-2-43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Revenue DEPARTMENT.

G.O. No. 2514	Press / Mis.
Dated 24-11-	18 42.

Not to be folded or roughly handled

(1)

Proceedings of the Madras Government, Public Works Department, 26th September 1862.

No. 480. Read the following Proceedings of the Madras Government in the Military Department, dated 18th September 1862, No. 3,209 :—

Approving of the estimate for two additional Privies to be constructed in the European Cantonment at Wellington. (Vide Military Proceedings, 18th September 1862, Nos. 359 @ 361.)

No. 481. ORDER THEREON, 26th September 1862, No. 2,314.

Communicated to the Deputy Chief Engineer, Southern Circle, for information and guidance.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

Military — New Works.

Detailed Estimate No 6 of 1862 and 1863

Wellington

Coimbatore District

Work — Constructing and Building Two Privies in Rear of No 2 and 5 Blocks of Barracks at Wellington

Particulars				Measurements Contents	
Excavation					
Foundations of the whole of the Walls	228⅔	1½	2	686	11/27
				25	11/27
Brick in Mud					
Foundations of the whole of the walls	228⅔	1½	2	686	
Back Screen wall	81	1½	5½	519	¾
Front do do	2	1½	5½	32.	½
Walls of Building	142⅔	1½	7	1164	½
Two Gables	18⅔	1½	2	43	½
				2446	½
Deductions				95	¼
Total Cft. Brick in Mud				2351.	
Pointing					
Two Sides of Back Screen wall	162		5½	891	
do do Front Screen wall	240		5½	55	
do do Walls of Buildings	285⅓		7	1997	⅓
Do do Gables.	32⅔		2	65	⅓
Total Sup.re feet Pointing				3008	⅔
Roofing					
	66⅔	15		995	
Extra Roofing for Ventilation	15	6		90.	
Total Sup.e feet Roofing				1085	

Flooring with paving Piles — 72 . 3 . / 6 . 7 . / 5 . 3 . — 47

Windows to swing with frame —— 2

Door Batten and hung with 3 in bolts —— 1

Galvanized Iron Buckets including Carriage —— 35

Slats

32 Pieces
32 do
64 do } For frames — 96 . 4 . 4 / 64 . 4 . 4 / 288 . 4 . 4 — 6 / 2⅔ / 12

Planking for Seats — 62 . 4½ . 4½ — 13½

do for Risers — 62 . 1½ . ½ — 1

Total Cft Hardwood — 45 11/12

Quantities	Description of Charges	Price	Data	Amount	Total
25 11/27	Cubic Yards of Excavation	4 . .	per yd	6	57
2351	Cubic feet Brestwork Mud	20 . .	per 100 Sft	470	32
3018⅓	Sup[e] feet of Pointing	1 . .	per 100 Sft	30	2 10
1085	do Roofing	30 . .	do	325	8 . .
667	do Flooring with Piles	8 . .	do	53	5 9
2.	Windows	15 . .	each	30	. . .
1	Door (Batten)	20 . .	do	20	. . .
35	Galvanized Iron Buckets	3 . .	do	105	. . .
45 11/12	Cft wood work	2 8 .	Cft	114	12 8
				1155	6 . .
	Sundries at 5 per Cent			57	10 . .
	Total for one pump			1213	. . .
	one more			1213	. . .
	Total Estimate Rupees			2426	

Executive Engineers Office
Kellingtan
18th July 1862

Executive Engineer

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following papers:—

Memorandum from the Quarter Master General of the Army, Head Quarters, Bangalore, 13th August 1862, *No.* $\frac{301}{312}$.

Forwarded for the sanction of Government, the work being essentially necessary,—Plan and Estimate were not called for, a rough Estimate only was asked for; but as the detailed record has been furnished, it is forwarded likewise.

From the Officer Commanding Southern Division, Head Quarters, Trichinopoly, 7th August 1862, *No.* 787; *to the Quarter Master General of the Army, Bangalore.*

Referring to my letter of the 3rd and your reply thereto, No. 168, of the 5th ultimo, on the subject of additional Privies at Wellington, I have the honor to report, for the information of the Commander-in-Chief, that the Engineer's Estimate for two additional Privies is greatly in excess of what I contemplated it would be.

I forward the Plan and Estimate for His Excellency's satisfaction.

I suggested to the Executive Engineer the introduction of the galvanized Iron Buckets instead of the Wooden Tubs now in use, as the latter become so offensive as to require constant changing, and when they are not changed, the Privies become most offensive.

Referred to the Public Works Department.

18*th August* 1862.

From the Deputy Chief Engineer Southern Circle, Madras, 28th August 1862, *No.* 144; *to the Secretary to Government, Department Public Works.*

With reference to Order of Government, No. 2023, dated 25th August 1862, I have the honor to re-submit the Plan and Estimate, received therewith, for two additional Privies to be constructed in the European Cantonment at Wellington, the amount of the Estimate having been corrected to Rupees 2,486, and I beg leave to recommend it for sanction out of the General Funds of the Coimbatore District.

Enclosures 2.
1 *Plan.*
1 *Estimate.*

Referred to the Military Department, for consideration.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government, P. W. D.

2nd September 1862.

ORDER, No. 3209, 18*th September* 1862.

Approved.

(True Extract.)

Deputy Secretary to Government.

To the Quarter Master General.
„ Public Works Department, with two enclosures. 1+20 spare Copies

Exd. T. Stubbs.

P.W. 1862 Departt
Engr & Constr Depôts

No 2843.

Copy of the Report in the
Military Departt

Dated 18th } Sept 12
Received 20th }

No 3209

Enclos: 2

No 2314 -

Communicated to
the Deputy Chief Engineer S.C.
for information and
guidance

Colchester
26th Septr 1862

Approving of the estimate for two additional Drains to be constructed in the Barrack Department at Walmington

13 Copies.

To The Deputy Chief Engr S.C. with 8 Copies of the Military Letter Sept 29
" Accountant General C. in Chief for Do

No 480. 481.

Walmington Order
No 2314 - 26 Septr

X 84.