M.R.O. 1—77,006—8-6-31.

(1) Number of pages 8.

(2) Date of repair 6.2.43.

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Library DEPARTMENT.

G.O. No. 2334 Press / Mis.

Dated 29-9- 1862.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 29th September 1862.

No. 520. Read the following Proceedings of the Madras Government in the Military Department, dated 23rd September 1862, No. 3,266:—

Approving of the estimate for the construction of a new Gram shed and store room for the Battery of Artillery at Trichinopoly, and requesting that the Chief Engineer may be directed to call for and submit an estimate for a shed on the principle of Duff's Cooking range for Gram Boiling sheds.

(Vide Military Proceedings, 23rd September 1862, Nos. 474-475.)

No. 521. ORDER THEREON, 29th September 1862, No. 2,334.

1. Communicated to the Deputy Chief Engineer, Southern Circle, for information and guidance.

2. Lieutenant-Colonel Ouchterlony is requested to attend to the requisition contained in paragraphs 2 and 3.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

New Works.

DISTRICT Trichinopoly

WORK Constructing a New Grain Shed & Store Rooms with Drying place for the Battery of Artillery

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees	Amount. of each part. Rupees.
	Grain Shed					
2136	Cft. Brick in Clay — 3 Cft.	"	1	"	134	
155	Sq. Ft. Do. in Chunam — 1 Sq. Ft.	"	1	9	17	
2152	Sq. Ft. Pointing with Chunam — 1 Sq. Ft.	"		12	18	
800	Do. Roofing with Cocoanut Rafters Bamboo Rafters and Tuntiles — 1 Sq. Ft.	"	15	"	120	
374	Do. Flooring with Gravel 1 Cft.	"	8	"	2	
24	Rft. Junglewood Breast = Summers — 1 Rft.	"	6	"	9	
1	Junglewood Batten door	"	"	"	10	
1	Do. Window with bars	"	"	"	6	
	Blue washing	"	"	"	5	
	Excavation	"	"	"	3	
	Contingencies & Sundries	"	"	"	33	
						357
	Drying place					
216	Cft. Brick work in Chunam — 1 Cft.	"	1	9	24	
169	Sq. Ft. Stone flooring — 1 Sq. Ft.	"	7	"	12	
	Carried Over				36	357

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees	Amount. of each part. Rupees.
	S. Brickwork				36	357
	Plastering	"	-	-	3	
	Excavating foundation					
	Sundries & Contingencies	"	-	-	1	
						43
	Total Rupees					400

E Deering Capt R.E.

(2) Circle Office
10th Sept. 1862

for Sd/ Chief Engr & Circle

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter:—

From Captain E. Hemery, *Royal Engineers, for Deputy Chief Engineer Southern Circle, Madras,*
10*th September* 1862, *No.* 81; *to the Secretary to Government, Public Works Dept., Chepauk.*

Submitted for the information of Government, with a recommendation that the accompanying Estimate of Rupees 400, for constructing a new Gram Shed with Store-room and drying place for the Battery of Artillery at Trichinopoly, may be sanctioned from the general funds placed at the disposal of the District Engineer, for expenditure during the current official year.

The Estimate has been approved* of by His Excellency the Commander-in-Chief.

Enclosures 5.

1 *Original Letter from District Engineer, No.* 576.
1 *Do. do. No.* 512, *dated* 11*th July* 1862.
1 *Specification.*
1 *Letter from Quarter Master General No.* 391, *dated* 3*rd September* 1862.
1 *Abstract Estimate.*

* *Letter from Quarter Master General No.* $\frac{391}{6857}$, *dated* 3*rd September* 1862.

Referred to the Military Department.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secy. to Govt. P. W. Dept.

11*th September* 1862.

ORDER, No. 3266, 23*rd September* 1862.

Approved as regards the Gram Shed and Store-room.

2. The Governor in Council is of opinion that the present offers a favorable opportunity for introducing the principle of Duff's Cooking range for Gram boiling Sheds, recommended by the Remount Agent at Oossoor, as being more economical and convenient than the plan in ordinary use†—the requirements consisting simply of a range of Caldrons fed by a single stove, whereby also both the men and horses will be secured from the annoyance now caused by the smoke from the boiling room.

† *Vide Proceedings of Government, No.* 660, *dated* 18*th February* 1861.

3. The Chief Engineer will accordingly call for and submit an Estimate for a Shed on the above plan.

(True Extract.)

Deputy Secretary to Government.

To the Public Works Department, with 5 enclosures.
" Quarter Master General.
" Remount Agent Oossoor, for information.

Exd. T. Stubbs.

Pol. 1862 Department

Proc. of Oct. 2893 Sept.

Pros. of Madras Government

in the Military Department

Dated 23rd Sept. 1862.

Read 25th " "

Encls. 5 No. 2334 dated 29th Sept. 1862.

from Chief Engr. S. Circle

Approving of the estimate for the construction of a new grain shed and store room for the Battery of artillery at Trichinopoly and requesting that the Chief Engineer may be directed to call for and submit an estimate for a shed on the principle of Duff's boiling Range for Grain Boiling—

Shed—No. 2334. 29th Sept. 62

With an Order [illegible]

No. 2334—

Communicated to the

Deputy Chief Engineer Southern

Circle for information and guidance.

Lieut. Colonel Pechtelany

is requested to attend to the

requisition contained in paras

2 & 3.

Chepauk

29th Sept. 1862

13 Copies.

To

The Dy. Chief Engr. S. Circle with 12 Encls. & 8 Copies

" " Accountant General " Military Dept. with 8 Copies

Lieut. 30th

No. 820-521

No. 87