M.R.O. 1—77,006—8-6-37.

(1) Number of pages 6

(2) Date of repair 6.2.43

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 2336 Press / Mis.

524-525

Dated 29-9- 18 62.

Not to be folded or roughly handled

1

Proceedings of the Madras Government, Public Works Department, 29th September 1862.

No. 524. Read the following Proceedings of the Madras Government in the Revenue Department, dated 20th September 1862, No. 2,048:—

Approving of the estimate for repairing the Sea Custom House at Keelackarry in the District of Madura. } (Vide Revenue Proceedings, 20th September 1862, Nos. 399-400.)

No. 525. ORDER THEREON, 29th September 1862, No. 2,336.

Communicated to the Deputy Chief Engineer, Southern Circle, for information and guidance.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

Madura Distuct

Abstract Estimate No

Raising the Sea custom house at Keelackarry

Description of Work.	Rate			Per.	Amount			Total		
Sqre ft. roofing with old & new materials	5	.	.	0 Sqre	29	2	.			
Do. flooring with brick Selly in Chunam	3	.	.	Do.	16	11	.			
Do. Plastering 2 Coats of Chunam	2	8	.	Do.	31	8	.			
Do. flooring with stone Selly in Chunam	4	.	.	Do.	60	10	.			
Cub ft. wrought Palay wood	1	8	.	Cft.	82	6	.			
Sqre ft. Terrace with brick Selly in Chunam	3	.	.	Sqre	28	8	.			
Cyo. brick in Chunam	5	.	.	Cyo.	44	10	.			
Door Complete	.	.	.		30	.	.			
Do. Do.	.	.	.		20	.	.			
Windows with Iron bars	10	.	.	Each	60	.	.			
Stone Supporters	1	.	.	Do.	5	.	.			
Padlocks with Keys					2	8	.			
								410	15	.
Superintendence and Sundry repairs &c.								39	1	.
Total of Estimate Rupees								450	.	.

Madura Distuct
Office Madura
11th August 1862

W. Harington.
1st Assto. Distuct Engineer
in Charge Madura Distuct

5B

REVENUE DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter from Captain E. HEMERY, R. E., for Deputy Chief Engineer, Southern Circle, to Colonel W. I. BIRDWOOD, R. E., Secretary to Government, Public Works Department, dated 9th September 1862, No. 93:—

SIR,

1 Letter from the District Engineer, No. 417, dated 14th August 1862.
1 Abstract Estimate.

1. Under paragraph 1, Section III, Chapter XXIV of the new Public Works Code, I have the honor to submit for the sanction of Government, the accompanying estimate amounting to Rupees 450 for repairing the Sea Custom House at Keelackarry in the District of Madura, as the proposed outlay exceeds more than one-fourth of the value (Rupees 1,187-8-0) of the building.

2. The estimate, which has been countersigned by the Collector in token of approval, is recommended for sanction from the General Repair Funds allotted to the District of Madura for the current year.

Referred to the Revenue Department.

Chepauk,
10th *September* 1862.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government, P. W. D.

ORDER THEREON, 20th September 1862, No. 2,048.

The work is approved.

(True Extract.)

Chief Secretary.

To the Public Works Department. *with 2 Enclosures.*
" Board of Revenue.

Exd. S. T. Augustin.

Rev=2589/62.

Madura District
Abstract Estimate &c
Repairing the Sea
Custom House at Kee.lac
Karry

Public Works 1862 Dept.
Pro: of Govt. for Sept.
No. 2865
Pro: of the M. Govt. in
the Revenue Dept.
Dated 20 } Sept. 62
Received 24 }
No. 2048
Enclod. 2.
1 Sent to the Dy. Chief
Engr. C.

Approving of the estimate
for repairing the Sea em
=bankment at Kedgeree
in the District of Hooghly.

No. 524. 525.

With an order
No. 2336-29 September.

2336

No. 2336.

Communicated to the Deputy
Chief Engineer S. Circle for information
and guidance.

Chepmell
29th Sept. 1862

13 Copies.

To the Deputy Chief Engr. S. with 1 Encl. & 8 Copies
" the Revenue Pro: Sept. 2865
" Accountant General with Rev. Pro.
No. 87