M.R.O. 1—77,003—8-6-37.

(1) Number of pages 4

(2) Date of repair 2/. 5. 42

(3) Initials of the Referencer

# MADRAS RECORD OFFICE.

## Government of Madras.

Relief Works DEPARTMENT.

| | |
|---|---|
| G.O. No. 577 | Press / Mis. |
| Dated 20-2-1 | 1860 |

***Not to be folded or roughly handled***

## *Proceedings of the Madras Government, Public Works Department, 20th February* 1862.

No. 349. Read the following Proceedings of the Madras Government in the Military Department, dated 17th February 1862, No. 616:—

Approving of certain alterations in the plan of the Quarters for two Apothecaries in connection with the new European Hospital at Bellary. } (Vide Military Proeeedings, 17th February 1862, Nos. 364-365.)

---

No. 350. ORDER THEREON, 20th February 1862, No. 277.

Communicated to the Deputy Chief Engineer, Central Circle, for information and guidance.

(Signed) W. H. HORSLEY, Lieut.-Colonel,
*Secretary to Government.*

## MILITARY DEPARTMENT.

### *PROCEEDINGS OF THE MADRAS GOVERNMENT.*

Read the following letter :—

*From the Acting Deputy Chief Engineer Central Circle, Chepauk, 7th February* 1862, *No.* 10,307 ;
*to the Chief Engineer and Secretary to Government, P. W. D., Fort Saint George.*

The Order of Government as per margin, which sanctioned the construction of Quarters in one block for two Apothecaries in connection with the new European Hospital at Bellary, at an estimated cost of Rupees 3,650, having been communicated to the District Engineer ; that Officer has sent up a slightly revised Plan, the Estimate for which amounts to Rupees 3,900 ; the alterations which the District Engineer suggests are, that the tiled roof, which was continuous from the ridge to the eaves, should stop at the main walls, and that the covering of the Verandahs should be semi terraced roofs of three courses of flat tiles and plaster. The other changes are the addition of ridge ventilators, ground ventilators, ventilating tubes in the enclosed Verandahs, two glass windows to be substituted for doors in front, and a modification of the arrangement in the out-houses.

*No.* 4526, *dated* 11*th December* 1861.

*Enclosures* 3.

1 *Estimate, Rupees* 3,910.
1 *Plan.*
1 *Letter from District Engineer, Bellary No.* 424, *dated* 24*th January* 1862.

2. The alterations are all very desirable, and as they will only add Rupees 260 to the amount already sanctioned, I beg to forward the Plan, Estimate and correspondence, and to recommend that the sanction of Government may be accorded for the improvements proposed. The Estimate has been examined and corrected.

---

ORDER, No. 616, 17*th February* 1862.

The Governor in Council approves of the alterations proposed.

(True Extract.)

Secretary to Government.

To the Public Works Department, with five enclosures.
,, Quarter Master General.

Exd. T. Stubbs.

Public Works Office 1862. Dept.
Rec'd Contr. for February
No. 475.

Plan of the Barrack Square
in the Military Depot.

Dated 17th February 1862
Rec'd 19th Do.

Enclosed No. 616.

Explaining & containing
alterations in the plan
of the Quarters for
two Apothecaries in
connection with the new
European Hospital at
Bellary —

Withdrawn Order

No. 277
Communicated to the Deputy
Chief Engineer Central Circle for Infor-
mation and Guidance —

Fort St George
20th February 1862

13 Encls.

To the Deputy Chief Engineer C.C. with 3 Encls.
Disp. 25th