

(1) Number of pages 6(2) Date of repair 11.12.63

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2917	Press ~~Mis.~~
120-21	
Dated 6. 12	1862.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
6th December 1862.*

No. 120. Read the following Proceedings of the Madras Government in the Public Department, dated 2nd December 1862, No. 1,406:—

Sanctioning for entry in the Budget of 1863-64 estimate of
Rupees 12,400 for a range of sheds and out-offices within the
compound of the General Hospital as Store room for the
Commissariat Department and Quarters for Hospital
Serjeants. } (Vide Public Proceedings, 2nd December
1862, Nos. 8-9.)

No. 121. ORDER THEREON, 6th December 1862, No. 2,917.

Communicated to the Chief Engineer and Acting Deputy Chief Engineer, Central Circle,
for information and guidance.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

Revised
Abstract Estimate No 42 of 1862

District Presidency

erecting a Range of tiled Buildings for the use of the Hospital
and Commissariat Stores and Offices & attached to the General
Regimental Hospital prepared to accompany a Report from the
Chief Engineer of the Presidency

Description of work.	Rate	Amount
Brick work in chunam	2 3	475 13 5
Flat arch work in chunam over the doors and windows	3 4	136 7 9
Circular arch work in chunam over the arches	3 10 1/2	378 2 9
Roofing with flat and pantiles and chunam borders	9 5	1009 12 1
Roofing with palm-leaf rafters and nails &c	7	740 5 1
Lining with teakwood repest and nails over the rafters of the above roof	10	913 4 10
Plastering with 2 coats chunam to the walls &c	2	256 1 1/2
Flooring with 8 inch square bricks in chunam and a bedding course of 3rd sort wall bricks underneath	9 3 7	749 7 2
Flooring with 8 inch square bricks in chunam	7 4	50 5
Erecting 5 large steps in masonry and flooring with 8 inch square bricks in chunam and plastering the sides as per plan leading to the Verandah	" "	50 "
Erecting 5 small steps in masonry and flooring with 8 inch square bricks in chunam and plastering the sides on the back side of the Building	" "	31 4
Erecting 13 small steps in masonry and flooring with 8 inch square bricks in chunam and plastering the sides leading to the Out Offices & store Room	" "	45 8
Erecting the fire places & foyals in masonry & plastering the same	" "	7
Erecting the stove fire in masonry and Do.	" "	4
Excavating the foundation filling & levelling the earth to the base with & laying sand 1 1/2 feet deep under the foundation	" "	215 1
Carried Over		4472

Description of work

Rate Amount

Brought Over 94 72

1 wrought and put up	5	10	489	7	9	
2 wrought and fixed screw nails	3	12	237	8	7	
3 battens door with frames hooks hinges and bolts &c complete	25	11	12	359	11	9
4 battens door with frames hooks &c complete	14	13	2	133	6	8
5 Do Do Do Do Do	17	12	7 1/2	266	13	4
6 Do Do Do Do Do	22	7	9	44		5
7 battens window shutters with frames hooks hinges and iron band &c complete	17	12	1	266	5	3
8 Do Do Do Do Do	10	2	4	152	3	
9 Do Do Do Do Do	4	11	3	32	14	9
10 bars to the bulls eyes	"	"	4	"	"	"
11 paint 3 coats to the doors and windows &c	"	"	60	"	"	"
12 tar with 2 coats to the rafters of the roof	"	"	92	"	"	"
13 iron locks of 8 inch complete	"	"	25	"	"	"
14 charges and scaffolding &c	"	"	383	7	7	"

Total Rupees Twelve thousand two hundred and twenty 12220

Office 1862
 District Engineer Presidency
 South Col

PUBLIC DEPARTMENT. PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter from Captain E. HEMERY, R. E., Acting Deputy Chief Engineer, Central Circle; to Colonel W. I. BIRDWOOD, R. E., Secretary to Government D. P. W., dated Chepauk, 19th November 1862, No. 351.

I have the honor herewith to submit for sanction and entry in the Budget of 1863-64 an Estimate amounting to Rupees 12,400, for a range of sheds and out-offices proposed to be erected within the compound of the General Hospital as Store-room for the Commissariat Department and Quarters for Hospital Serjeants.

Enclosures 5.
 1 Letter from the District Engineer Presidency, No. 338, dated 2nd June 1862.
 1 Do. No. 309, dated 19th June 1862.
 1 Plan.
 1 Estimate.
 1 Specification.

2. No provision whatever was made for these buildings in the Estimate for the Hospital, and as the arrangements in the Plan have been approved of by the Inspector General of Hospitals and by all the Medical Officers concerned, it seems very desirable that the work should be executed next official year.

Referred to the Public Department.
 (Signed) W. I. BIRDWOOD, Colonel, R. E.,
 Secretary to Government, P. W. D.

20th November 1862.

ORDER THEREON, 2nd December 1862, No. 1,406.
 Estimate, amounting to Rupees (12,100) twelve thousand four hundred, sanctioned, to be entered, as proposed, in the Budget of 1863-64.
 (True Extract.)

G. J. Cantelmo
 Chief Secretary.

To the Department Public Works,
 (with five enclosures.)
 " Accountant General.
 " Principal Inspector General, Medical Department.
 " Civil Paymaster.

Ed. T. McMootry.

