

(1) Number of pages 6(2) Date of repair 5.12.43

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2920	Press Mis.
126-27	
Dated 6-12	1862.

Not to be folded or roughly handled

10

*Proceedings of the Madras Government, Public Works Department,
6th December 1862.*

No. 126. Read the following Proceedings of the Madras Government in the Military Department, dated 28th November 1862, No. 4,108:—

Approving of the estimate of Rupees 2,320 for converting a } (Vide Military Proceedings, 28th November
building at Saint Thomas' Mount known as the Begum's } 1862, Nos. 541-542.)
Bungalow into Recreation Rooms for European Soldiers.

No. 127. ORDER THEREON, 6th December 1862, No. 2,920.

Communicated to the Acting Deputy Chief Engineer, Central Circle, for information and guidance.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

Military Building

Abstract Estimate No. of 1862/63

Repair

Madras District Taluk Hyderabad
 Work Repairing the Begums Bungalow in the Contonment
 of Saint Thomas Mount

Quantities	Descriptions of Charges	Rate	Amount	Total
83	Cubic yards of Brick work in Chumam	3 8	291	
7	do of brick work	5 14 6	41	
12	Squares of terracing the east, and west side rooms of the Main Building and stair case room	21	252	
2	do of terracing the centre room on the east	21	42	
32	do of Plastering, Poling & Painting to flooring	2 4	72	
19	do of Roofing the Verandah with 3 Course of flat tiles and plastering, with wood work Compt. Portion to be knocked down	22	418	
58	Cubic yards of Brick to be removed	1	58	
33	Squares of removing the tiled roof	1 12	58	
119	do of White washing	2 6	19	
14	do of Blue washing	3 6	3	
55	do of Yellow washing	3 6	12	
300	Running feet Cornice work in Chumam	4	75	
157	Cubic feet of Teak wood wrought & put up	3 10 6	208 68	
37	Squares of red paint 2 Coats	1 12	76	
32	do green paint for doors & windows 2. Coats	2 2	68	
5	do of repairing the flooring with 1. feet Squares Bricks in patches where required	12	60	
	Removing 2. wooden stair Cases		15	
152	Palmedah Posts for terrace	1	152	1905
181	Palmedah Posts for terrace wrought & put up	3 10 6	475	96
	Sundries and Extra Establishment		102	75
	Total Estimate No.		2330	2330
	Cost of work		2330	2330

The Mount.
 No. 2 Range Office
 22nd July 1862

W. S. Pringley Esq. V. C. Lieutenant
 of 1st of 1st District Eng. of Madras

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter:—

From the Acting Deputy Chief Engineer Central Circle, Chepauk, 14th November 1862, No. 230; to the Secretary to Government, Department Public Works.

No. 4102, dated 11th November 1862.

Enclosures 7.

1 Letter from the Chief Engineer, No. 4102, dated 11th November 1862, with Deputy Quarter Master General's letter No. 8494, dated 5th November 1862.

1 Letter from the Quarter Master General of the Army, No. 527, dated 8th October 1862.

1 Plan.

1 Estimate.

1 Specification.

1 Copy of letter from the Quarter Master Genl. of the Army, No. 3159, dated 24th Apl. 1862.

The Chief Engineer having, in his letter herewith enclosed, requested me to instruct Captain Moberly to commence and to carry out without delay the work required to convert a building at Saint Thomas' Mount, known as the Begum's Bungalow, into Recreation Rooms for European Soldiers, I have the honor to submit, for the sanction of Government, an Estimate amounting to Rupees 2,320, and a Plan of the Bungalow showing the proposed additions and alterations.

2. This Estimate has been prepared at the request of His Excellency the Commander-in-Chief, and in paragraph 6 of his letter as per margin, the Quarter Master General of the Army observes, with reference to Order of

No. 3159, dated 24th April 1862

Government, No. 1886 of the 15th April 1862, that at the Mount, it is proposed to convert the Begum's Bungalow into Recreation Rooms.

3. The expenditure can be defrayed from the General Funds at the disposal of the District Engineer Madras.

Referred to the Military Department.
(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government, P. W. D.

17th November 1862.

ORDER, No. 4103, 28th November 1862.

Approved.
(True Extract.)

Macmillan
Deputy Secretary to Government.

To the Public Works Department,
with six enclosures and a Plan. ✓

.. Quarter Master General.

.. Barrack Master.

Ed. J. E. Cashart.

Ed. J. E. Cashart

*Chief Engineer
The District Engineer
Madras
Chepauk
14th Nov 1862
No. 230
Enclosures 7
1 Letter from the Chief Engineer, No. 4102, dated 11th November 1862, with Deputy Quarter Master General's letter No. 8494, dated 5th November 1862.
1 Letter from the Quarter Master General of the Army, No. 527, dated 8th October 1862.
1 Plan.
1 Estimate.
1 Specification.
1 Copy of letter from the Quarter Master Genl. of the Army, No. 3159, dated 24th Apl. 1862.*

PPR, 26442/12

189186

Adm. 1869. Extract
of Board of Super
visors 1864-2

Adelbert and
Friedrich Dehrens

Robert M. Johnson
 President of the Board

284105.

Amesbury

Dear Mr. Child, Dear Mr. Child,

27. increase in the estimate
of recovery of the estimate

of Oct 28 21 for Constructing
a building at St. Xavier

Shards down at the Base.

James Thompson into

Declaration before me

Quadrant 2 -

With an order

47-2920-6 Recd.
in copy

Communicated to the Acting Deputy
Chief Engineer Central India for information and guidance

Nov 29 20.

100-126-129.

10

3. The Academy Bay & Cape Centre and with 8 copies of the Military Revue
-4- Museum General with 6 copies of the Military Revue
X: 87
6 Dec 1862