

(1) Number of pages 8(2) Date of repair 13-12-43

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2453	Press ~~Mis.~~
143-44	
Dated 9. 12	1862.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
9th December 1862.*

No. 193. Read the following letter from Captain E. HEMERY, R. E., Acting Deputy Chief Engineer, Central Circle, to Colonel W. I. BIRDWOOD, R. E., Secretary to Government, Public Works Department, dated Chepauk, 25th November 1862, No. 195:—

SIR,

1 Letter from the Acting District Engineer,
North Arcot, No. 1,681, dated 27th October
1862.
1 Survey.
1 Estimate.
1 Report.

1. I have the honor to solicit sanction for the accompanying estimate amounting to Rupees 1,350 for widening a portion of the Nagavadoo channel in the North Arcot District.

2. An Anicut at the head of this channel was re-built last year at a cost of Rupees 1,754, for the purpose of turning the surplus water from the Perancanjee tank (which is fed by a channel from the Poiney Anicut) into the Nagavadoo channel.

3. It is now proposed to widen this channel for a length of 1,733 yards so as to enable it to carry down small freshes into the five tanks below it, the revenue under which amounts to Rupees 5,351.

4. The estimate having met with the approval of the Collector, I beg to recommend the immediate execution of the work from the allotment for the repair of agricultural works in 1862-63 in the North Arcot District.

No. 194.

ORDER THEREON, 9th December 1862, No. 2,953.

Sanctioned from the funds proposed.

(Signed.) W. I. BIRDWOOD, Colonel, R. E.;
Secretary to Government.

Abstract of Detailed Estimate for Repairing Nagavadoo,
Aroombakem, Vadacalattoor, Paruthepathoor and Idamunthoor
Kijda Condam Channar in Malaja Taluk of N. A.

Quantities	Description of Charges	Rate	Est	Amount	Total
18329. 13	Culivards of Earthwork	1	Cyts	1145 9 9½	
168	Do of Rock for Blasting and Removing	1		168	
	Sundries and Superintending allowance			36 6 2½	
	Total Estimate, Rupees One Thousand three Hundred and fifty only				1350

Camp Thuckolum
12th May 1867.
Camp 18

Signed/ C. Aroonachella Mooday
Sub Overseer D. O. N.

Signed/ M. Howard Supervisor
Incharge of Malaja Range N. A.

Signed/ H. C. Penderguth Captain
District Eng^r of N. A.

Signed/ J. Fraser
Acting Collector
(True Copy)

J. Mouth. Over
Incharge of N. Range N. A.

J. W. P. C. E.
District Eng^r N. A.

Central Circle Office
Chepauk
25th November 1862.

N^o 195.

From
Captain E. Hemery R.E.
Acting Deputy Chief Engineer
Central Circle

To
Colonel W. J. Birdwood R.E.
Secretary to Government
Public Works Department

Sir,

I have the honor to solicit sanction
for the accompanying estimate amounting to
Rupees 1350-
for widening a portion of the Nagaradoo
Channel in the North Arcot District.
An anikot at the head of this
channel was rebuilt last year at a cost of
Rupees 1754 for the purpose of turning
the surplus water from the Perancanjes
tank (which is fed by a channel from the
Poiney Anikot) into the Nagaradoo Channel.
It is now proposed to widen this
channel for a length of 1733 yards so as
to enable it to carry down small freshes
into

9091 0055/142

Statement of Estimate for
widening Nagaradoo Channel:-
Small Anikot at the head of the
channel to be widened
Consum Channel in the
North Arcot District

Decr 1357

into the five tanks below it, the revenue under which amounts to Rupees 5351.

4 The estimate having met with the approval of the Collector, I beg to recommend the immediate execution of the work from the allotment for the repair of Agricultural works in 1862/63 in the North Arcot District.

Central Circle Office,
Chennai...
25th November 1862.

I have the honor to be
Very
Respectfully
Yours
Captain R.E.
Acting Deputy Chief Engineer
Central Circle

To
Colonel W. J. Birdwood R.E.
Secretary to Government
Public Works Department

