

(1) Number of pages 6(2) Date of repair 17.12.12

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 2989	Press Mis.
262-63	
Dated 13. 12	1862.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
13th December 1862.*

No. 262. Read the following Proceedings of the Madras Government in the Ecclesiastical Department, dated 4th December 1862, No. 333 :—

Sanctioning the estimate of Rupees 1,190, for constructing a wall along a portion of the Cathedral compound, and requesting that the source from which the above sum can be defrayed may be determined. (Vide Ecclesiastical Proceedings, 4th December 1862, Nos. 1-2.)

No. 263. ORDER THEREON, 13th December 1862, No. 2,989.

1. Communicated to the Acting Deputy Chief Engineer, Central Circle.
2. As the work appears to be of an urgent nature, it will be carried out from the General Funds at the disposal of the District Engineer, Presidency.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

No. 241. of 1862-63.

Estimate of the probable expense of constructing a portion of Compound wall on the eastern side of the enclosure at the Saint George's Cathedral prepared as per letter of the Chaplain dated 5th November 1862.

Measurement					Price				
Length	Depth	Breadth	Height	Cumft					
368.62	23			2487 ³	Foundation of Compound wall				
368.66	91-6			3731 ⁸	Compound wall above including coping				
46-65-9	3		67	31	Pillasters on both sides.				
Total 6285 ⁷ / ₁₆					Brickwork in chunam	2	5	6 ¹ / ₂	949 5 10
5500					Plastering with 2 coats chunam to wall	2	2	4 ¹ / ₂	110 9 2
					Excavating the foundation and levelling the earth				14
					Filling with river sand 15 ft in depth under the foundation & well beaten down with water				53 13
					Costly hire for cutting removing & rooting out the trees & hedges &c				7
					Sundry charges & scaffolding &c				55 4
Total Rs. One thousand one hundred and ninety									1190

Dist. Eng. Office
Madras
12th November 1862

Robertson S. Leitch
Dist. Eng. Presidency

Recd/62/11/234/3

18/12/1862
29/12/1862

ECCLESIASTICAL DEPARTMENT.
PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter from the Venerable THOMAS DEALTRY, Archdeacon of Madras;
to A. J. ARBUTHNOT, Esq., Chief Secretary to Government, Fort Saint
George, dated Madras, 14th November 1862, No. 393.

I have the honor to forward for the consideration of His Excellency the Governor in Coun-
cil an application from the Trustees of Saint George's Cathedral for permission to construct at
at the public expense a wall along a portion of the Cathedral compound. They represent the
need of such an enclosure, and forward an Estimate signed by the District Engineer, amounting
to Rupees (1,190) one thousand one hundred and ninety.

ORDER THEREON, 4th December 1862, No. 333.
Estimate amounting to Rupees (1,190) one thousand one hundred and ninety, sanctioned—
the charge will be defrayed from such source as the Department Public Works may determine.
(True Extract.)

A. J. Arbuthnot
Chief Secretary.

- To the Venerable the Archdeacon,
(with an enclosure.)
- „ Department Public Works,
(with an Estimate.)
- „ Accountant General.

Exd. T. McMootry.

20/12/1862

