M.R.O. 1—77,006—8-6-37.

(1) Number of pages 18

(2) Date of repair 3-1-44

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works **DEPARTMENT.**

G.O. No. 3058 Press / Misc.

406-07

Dated 22 - 12 1862.

Not to be folded or roughly handled

2.1.44

Proceedings of the Madras Government, Public Works Department, 22nd December 1862.

No. 406. Read the following Proceedings of the Madras Government in the Military Department, dated 12th December 1862, No. 4,278 :—

Approving of the estimates amounting in the aggregate to Rupees 3,470 for cleaning, ventilating and improving the Barracks, Cook-rooms and Privies attached to the Recruit Depôt at Saint Thomas' Mount. (Vide Military Proceedings, 12th December 1862, Nos. 270-271.)

No. 407. ORDER THEREON, 22nd December 1862, No. 3,058.

Communicated to the Acting Deputy Chief Engineer, Central Circle, for information and guidance.

(Signed.) W. I. BIRDWOOD, Colonel, R. E.,
Secretary to Government.

Improvements

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

DISTRICT Madras

WORK Ventilating Privies & Centre Cook room, & white and yellow washing those parts of Recruit Depot not entered in last Estimate

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees	Amount. of each part. Rupees.
	Centre Cook room					
9	Cyds Cutting holes in walls 2ft	-	12	-	7	
6	Sqrs Plastering 2 coats 2ft	2	4	-	14	
37	" Blue washing "	-	3	6	8	
2	" Asphalte 3/4 thick "	22	-	-	44	
11	" Pointing with asphalte "	4	-	-	44	
8	" Shifting tiles preparing chunam borders	2	-	-	16	
36	Rft Country wood inright 2ft wide	2	5	-	83	
44	" Teakwood	3	10	-	165	
8	Sqrs Red paint (2 coats) 2ft	1	12	-	14	
378	Rft of 3/4 round bar iron to Ventilators including workmanship	-	3	6	83	
16	Earthen pipes for roof Ventilators	-	8	-	8	
						481
	No 1 Privy					
11	Cyds Cutting holes in walls 2ft	-	12	-	8	
6	Sqrs of 3/4 asphalte 2ft	22	-	-	132	
5	Cyds of Concrete in chunam 2ft	2	-	-	10	
2	" Cut granite for Drains	17	-	-	34	
16	" Excavation	-	1	-	1	
14	Sqrs White washing 2ft	-	2	6	2	
18	" Yellow washing	-	3	6	4	
	Carried over				191	481

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees	Amount of each part. Rupees.
	Brought forward				191	481
448	Rft of 3/4 round iron bar including workmanship ——— ℔Rft	-	3	6	98	
42	bft Country wood wrought & put up ——— ℔bft	2	5	-	97	
60	" Teakwood ———	3	10	-	218	
8	Sqrs Red paint 2 coats ℔Sqr	1	12	-	14	
12	Ventilating earthen pipes in roof ——— E	-	8	-	6	
						624
	No 2 Privy					
4	bfyt Knocking down brick in chunam ——— ℔bfy	-	12	-	3	
6	" Brick in chunam — "	3	8	-	21	
168	Rft 3/4 round iron bar & Ventilators including workmanship ℔Rft	-	3	6	37	
16	bft Country wood wrought & put up ——— ℔bft	2	5	-	37	
21	" Teakwood — — "	3	10	-	76	
5	Sqrs Red paint 2 coats ℔Sqr	1	12	-	9	
4	" Plastering 2 coats "	2	4	-	9	
12	" Whitewashing ——— "	"	2	6	2	
14	" Bluewashing ——— "	"	3	6	3	
4	" Shifting tiles repairing chunam Inders ——— "	2	-	-	8	
4	" 3/4 Thick Asphalte "	22	-	-	88	
1	Sqr Cutpaintc ——— ℔Sqr	17	-	-	17000	
	Carried over				310	1105

Quantities	Description of work	Rate Rs	a	p	Amount Rupees	Amount each part Rupees
	Brought forward				310	1105
16	bfyt Excavation ——— ℔bfy	-	1	-	1	
8	Ventilating earthen pipes E	-	8	-	4	
						315
	No 3 Privy					
6	bfyt Knocking down brick in chunam ——— ℔bfy	-	12	-	5	
3	Sqrs 3/4 thick asphalte ℔Sqr	22	-	-	66	
1	Sqr Cut granite ——— ℔Sqr	17	-	-	17	
4	Sqrs Plastering 2 coats ℔Sqr	2	4	-	9	
9	" Whitewashing ——— "	-	2	6	1	
11	" Yellowwashing ——— "	-	3	6	2	
12	bft Country wood wrought & put up ——— ℔bft	2	5	-	28	
252	Rft 3/4 round iron bar including workmanship ℔Rft	-	3	6	55	
31	bft Teakwood wrought & put up ——— ℔bft	3	10	-	112	
6	Sqrs Red paint 2 coats ℔Sqr	1	12	-	11	
16	bfyt Excavation ——— ℔bfy	-	1	-	1	
10	Ventilating earthen pipes E	-	8	-	5	
						312
	No 4 Privy					
	Same detail as No 3 ———					312
169	Sqrs Bluewashing Compound wall, Shuttle Alley & Ball Alley	-	3	6	37	
22	" Plastering in patches	2	4	-	50	
	Carried over				87	2044

Quantities	Description of work	Rate		Amount	Amount of each Bill
		R	Ag		
	Brought forward			Rupees 87	Rupees 2044
	to levelling away rubbish			25	
	scaffolding			24	
					136
					2180
	Sundries				120
				Total Rupees	2300

Deputy
Captain R.E.
Asst Dy Chief Engineer. C.C.

Dy Chief Engineer's Office
Cheduck.
27th Nov. 1862

Enclosure
No 2 to
Abstract estimate for
constructing Varandah
Cuttur Cook room Pantile
Yellow washing the
Roof Work Repairs
Amount in the Abstract
Rupees, amounting to
Rupees 590

From
The Asst Engineer
Chittoor Division
To
The Secretary to Govt
Public Works Department

Dated Camp Bungalow
Kaptaraka 27th
November 1862.

Sir

I have the honor to forward herewith an abstract estimate for constructing Varandah for Cuttur Cook room Pantile Yellow washing the Roof Work Repairs Amount in the Abstract Rupees, amounting to Rupees 590

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

DISTRICT Madras.

WORK ~~Ventilating & Constructing~~ Varandah to West Cook room Recruit Depot Mount.

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount. of each part. Rupees.
14	Cub.ft P. of Knocking down brick in Chunam	"	12	"	11	
14	D: Brick in Chunam	3	8	"	49	
6	Sq: Plastering with Chunam 2 Coats	2	4	"	14	
12	D: Blue washing	"	3	6	3	
9	D: of Yellow D:	"	3	6	2	
12	D: Shifting tiles Repairing Chu: borders & supplying different tiles	2	"	"	24	
20	Cub.ft of Country wood wrought	2	5	"	46	
4	Sq: of Roofing with Palmirah Rafters Reepers Flat Pantiles &c	22	"	"	88	
7	Sq: Flooring with 3/4" Asphalte	22	"	"	154	
6	Cub.ft Kunkar in Chunam	2	"	"	12	
26	Cub.ft of Teakwood wrought	3	10	"	94	
3	Sq: of Paint 2 Coats	1	12	"	5	
630	lbs of Round Ironbars for Ventilators	"	1	3	49	
	Excavating foundation				1	
5	No Earthern pipes for Roof Ventilators	"	8	"	3	
	Cartage for Removing Rubbish				10	
	Sundries & Extra Establishment				25	
	Total Rupees					590

Deputy Chief Engr Office &c.
Chepauk.
27 November 1862.

Captain RE
Acting Deputy Chief Engr &c.

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees	Amount. of each part. Rupees.

Enclosure
Una Cella

From
The Acting Deputy
Chief Engr C.C.
Chief Engr's Office
No 2 Abstract of 1862

To The Secretary to
Government
of Fort St. George

Dated 27 Nov 1862
Recd. 29 Nov 1862
No. 247

Abstract & Estimate for
Ventilating and Constructing
Verandah to the Mint Cook
Room Record Office Chaunt
in the Madras District
Amount Rs 590 -

BUILDINGS

ABSTRACT of Estimate No. of 186 -6

DISTRICT . Madras

WORK Ventilating flooring and drainage for Mint Cook Room Record Office & the Mint Verandah

Quantities.	Description of Work.	Rate. Rs.	A.	P.	Amount. Rupees.	Amount. of each part. Rupees.
40	Cubic Knocking down brick in chunam flooring	"	12	"	30	
1	Sq. Flooring with granite	35	"	"	210	
2	Cubic Cut granite	17	"	"	34	
1	Do Brick in chunam	3	8	"	11	
6	Sq. Plastering in patches and 2 coats	2	4	"	11	
15	Do White washing	"	2	6	2	
16	Do Yellow Do Do	"	3	6	1	
16	Cubic Excavation	"	1	"	1	
450	Ft. Round bar Iron	"	1	3	35	
7	Sq. Painting with asphaltic	4	"	"	28	
1	Do Plastering Do	22	"	"	22	
10	Cubic Country wood	2	3	"	23	
30	Do Teak Do	3	10	"	109	
3	Sq. Rubble in 2 coats	1	12	"	5	
10	Do Shifting tiles	2	"	"	20	
	Carrying away rubbish				6	
	Sundries				33	
					Total Rupees	590

Dy. Chief Engr's Office
Chennai
27th November 1862

Recd Rs 590

Dy. Chief Engineer

Quantities.	Description of Work.	Rate.			Amount.	Amount. of each part.
		Rs.	A.	P.	Rupees	Rupees.

MILITARY DEPARTMENT.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following letter:—

From the Acting Deputy Chief Engineer, Central Circle, Chepauk, 27th November 1862, *No.* 247; *to the Secretary to Government, Department Public Works.*

Enclosures eight.

1 *Letter from the Acting District Engineer, Madras, No.* 1132, *dated* 11*th October* 1862.
1 *Do. from the Quarter Master General of the Army, No.* 9092, *dated 25th November* 1862.
1 *Estimate, Rupees* 2,300.
1 *Specification.*
1 *Estimate, Rupees* 590.
1 *Specification.*
1 *Estimate, Rupees* 580.
1 *Specification.*

I have the honor to solicit sanction for the enclosed Estimates amounting in the aggregate to Rupees 3,470, for cleaning, ventilating, and improving the Barracks, Cook-rooms and Privies attached to the Recruit Depôt at Saint Thomas' Mount.

2. These Estimates were prepared on an urgent requisition from the Medical Authorities, at the request of the Brigadier, and the work was commenced by the District Engineer, with my concurrence, in anticipation of sanction.

3. His Excellency the Commander-in-Chief having returned the Estimates with his approval, I beg to request sanction for the amount, Rupees 3,470, the cost to be defrayed from the allotment for the repairs of Military Buildings in the Madras District, during the current official year.

Referred to the Military Department.

(Signed) W. I. BIRDWOOD, Colonel, R. E.,
Secy. to Govt. P. W. D.

1st December 1862.

ORDER, No. 4278, 12*th December* 1862.

Approved for immediate execution.

(True Extract.)

Deputy Secretary to Government.

To the Department Public Works, with 8 enclosures. 4 Spare Copies
„ Quarter Master General.
„ Barrack Master.

Exd J. E. Cashart.

P.W. 1862 Depart.
Prov: & Gov.t for Decr.
Fo 3786.

No
Rec: d Agent in the
Military Depart.
Dated 12th Decr. 62
Rec.d 15th Do Fo 2
Fo 4278.
Enc. Cols 8

Approving of the estimate amounting in the aggregate to £8470 for cleaning, Ventilating and whitewashing the Barracks, Cookrooms and Privies attached to the Recruit Depot at the Provost Guard

With an order
No. 3058 - 22nd Decr.

No 406-407-

No. 3058.

Communicated to the
Acting Deputy Chief Engineer
Central Circle for information
and guidance.

Chepstow
22nd Decr 62
13 Copies.

To The Actg Dy Chief Engr. C. Circle with 5 Encls. & 8 Copies
3. — Secty General with Key to Plan of the Military Depot 23.

No 87